

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

| | |
|---|--------------------|
| STATE PROJECT REFERENCE NO. B - 4 3 3 4 | SHEET NO. TCP-1 |
|---|--------------------|

**PLAN FOR PROPOSED
TRAFFIC CONTROL, MARKING & DELINEATION
DAVIDSON COUNTY**

B-4334

TIP PROJECT:

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - ROADWAY DESIGN UNIT-N.C. DEPARTMENT OF TRANSPORTATION-RALEIGH, N.C., DATED JANUARY 2002 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|----------|---|
| 1101.03 | TEMPORARY ROAD CLOSURES |
| 1101.05 | WORK ZONE VEHICLE ACCESSES |
| 1101.11 | TRAFFIC CONTROL DESIGN TABLES |
| 1110.01 | STATIONARY WORK ZONE SIGNS |
| 1145.01 | BARRICADES |
| 1205.01 | PAVEMENT MARKINGS - LINE TYPES & OFFSETS |
| 1205.02 | PAVEMENT MARKINGS - 2 LANE & MULTILANE ROADWAYS |
| 1205.12 | PAVEMENT MARKINGS - BRIDGES |
| 1250.01 | PAVEMENT MARKER SPACING |
| 1251.01 | RAISED PAVEMENT MARKERS |
| 1261.01 | GUARDRAIL & BARRIER DELINEATOR SPACING |
| 1261.02 | GUARDRAIL & BARRIER DELINEATOR TYPES |
| 1262.01 | GUARDRAIL END DELINEATION |
| 1264.01 | OBJECT MARKERS |
| 1264.02 | PLACEMENT OF OBJECT MARKERS |

INDEX OF SHEETS

| SHEET NO. | TITLE |
|-----------|---|
| TCP-1 | LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, FINAL PAVEMENT MARKING SCHEDULE, INDEX OF SHEETS AND LEGEND |
| TCP-2 | GENERAL NOTES AND TRAFFIC CONTROL PHASING |
| TCP-3 | DETOUR SIGN DETAILS |
| TCP-4 | DETOUR ROUTE |
| TCP-5 | STANDARD DRAWING FOR DRUMS |

LEGEND

- GENERAL**
- DIRECTION OF TRAFFIC FLOW
 - NORTH ARROW
 - PROPOSED PVMT. EXIST. PVMT.
 - WORK AREA
 - REMOVAL OF EXISTING PAVEMENT
- TRAFFIC CONTROL DEVICES**
- TYPE I BARRICADE
 - TYPE II BARRICADE
 - TYPE III BARRICADE
 - CONE
 - DRUM
 - FLASHING ARROW PANEL (TYPE C)
 - TYPE 'B' WARNING LIGHT
 - STATIONARY SIGN
 - PORTABLE SIGN
 - STATIONARY OR PORTABLE SIGN
 - WARNING FLAGS
 - CRASH CUSHION
 - CHANGEABLE MESSAGE SIGN
 - TRUCK MOUNTED IMPACT ATTENUATOR (TMIA)
 - POLICE
 - FLAGGER
- PAVEMENT MARKINGS**
- CRYSTAL/CRYSTAL PAVEMENT MARKER
 - YELLOW/YELLOW PAVEMENT MARKER
 - CRYSTAL/RED PAVEMENT MARKER
 - PAVEMENT MARKING SYMBOLS

FINAL PAVEMENT MARKING SCHEDULE

| SYMBOL | DESCRIPTION | PAY ITEM QUANTITY BREAKDOWN | TOTAL QUANTITY |
|--------------------------------------|----------------------|-----------------------------|----------------|
| PAVEMENT MARKINGS | | | |
| THERMOPLASTIC (4", 90 MILS) | | | |
| TA | WHITE EDGELINE | 3600 FT | TOTAL 3600 FT |
| THERMOPLASTIC (4", 120 MILS) | | | |
| TD | 2 FT. WHITE MINISKIP | 32 FT | TOTAL 3632 FT |
| TI | YELLOW DOUBLE CENTER | 3600 FT | |
| MARKERS | | | |
| SNOWPLOWABLE RAISED PAVEMENT MARKERS | | | |
| ME | YELLOW/YELLOW | 23 EA | TOTAL 23 EA |

| | |
|----------------------------|---|
| APPROVED: DATE: 6/17/03 | PLAN PREPARED BY: N.C.D.O.T. TRAFFIC CONTROL, MARKING & DELINEATION SECTION |
| SEAL | J. S. BOURNE, PE TRAFFIC CONTROL ENGINEER |
| | G. L. GETTIER, PE TRAFFIC CONTROL PROJECT ENGINEER |
| | J. W. WOOLARD, PE TRAFFIC CONTROL PROJECT DESIGN ENGINEER |
| | D. J. MEDLEY TRAFFIC CONTROL DESIGN ENGINEER / TECHNICIAN |

11-JUN-2003 15:02
M:\TCP\AD4334\TCP-1.dwg
gmedley AT TEL105140