

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|---|--------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+69.29) | Lump Sum | L.S. | |
| 0004 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 0005 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 0006 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 30 CY | | |
| 0007 | 0199000000-E | SP | TEMPORARY SHORING | 625 SF | | |
| 0008 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 352 TON | | |
| 0009 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 2,032 LF | | |
| 0010 | 0372000000-E | 310 | 18" RC PIPE CULVERTS, CLASS III | 765 LF | | |
| 0011 | 0378000000-E | 310 | 24" RC PIPE CULVERTS, CLASS III | 240 LF | | |
| 0012 | 0384000000-E | 310 | 30" RC PIPE CULVERTS, CLASS III | 168 LF | | |
| 0013 | 0390000000-E | 310 | 36" RC PIPE CULVERTS, CLASS III | 56 LF | | |
| 0014 | 0708000000-E | 310 | 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 56 LF | | |
| 0015 | 0806000000-E | 310 | 15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK | 2 EA | | |
| 0016 | 0995000000-E | 340 | PIPE REMOVAL | 1,038 LF | | |
| 0017 | 1121000000-E | 520 | AGGREGATE BASE COURSE | 1,691 TON | | |
| 0018 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 250 TON | | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|---------------|-----------|--------|
| 0019 | 1330000000-E | 607 | INCIDENTAL MILLING | 250 SY | | |
| 0020 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 10,930 TON | | |
| 0021 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 7,288 TON | | |
| 0022 | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 4,931 TON | | |
| 0023 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 1,110 TON | | |
| 0024 | 1570000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22 | 45 TON | | |
| 0025 | 1663000000-E | 650 | OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MODIFIED | 750 TON | | |
| 0026 | 1693000000-E | 654 | ASPHALT PLANT MIX, PAVEMENT REPAIR | 161 TON | | |
| 0027 | 2000000000-N | 806 | RIGHT OF WAY MARKERS | 37 EA | | |
| 0028 | 2253000000-E | 840 | PIPE COLLARS | 0.893 CY | | |
| 0029 | 2264000000-E | 840 | PIPE PLUGS | 1.074 CY | | |
| 0030 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 38 EA | | |
| 0031 | 2308000000-E | 840 | MASONRY DRAINAGE STRUCTURES | 2.8 LF | | |
| 0032 | 2352000000-N | 840 | FRAME WITH GRATE, STD 840.**** (840.20) | 3 EA | | |
| 0033 | 2364000000-N | 840 | FRAME WITH TWO GRATES, STD 840.16 | 6 EA | | |
| 0034 | 2365000000-N | 840 | FRAME WITH TWO GRATES, STD 840.22 | 10 EA | | |
| 0035 | 2374000000-N | 840 | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E) | 3 EA | | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0036 | 2374000000-N | 840 | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F) | 8 EA | | |
| 0037 | 2374000000-N | 840 | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G) | 6 EA | | |
| 0038 | 2549000000-E | 846 | 2'-6" CONCRETE CURB & GUTTER | 5,078 LF | | |
| 0039 | 2577000000-E | 846 | CONCRETE EXPRESSWAY GUTTER | 863 LF | | |
| 0040 | 2612000000-E | 848 | 6" CONCRETE DRIVEWAY | 158 SY | | |
| 0041 | 2619000000-E | 850 | 4" CONCRETE PAVED DITCH | 185 SY | | |
| 0042 | 2655000000-E | 852 | 5" MONOLITHIC CONCRETE ISLANDS (KEYED IN) | 797 SY | | |
| 0043 | 2830000000-N | 858 | ADJUSTMENT OF MANHOLES | 5 EA | | |
| 0044 | 2845000000-N | 858 | ADJUSTMENT OF METER BOXES OR VALVE BOXES | 12 EA | | |
| 0045 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 2,925 LF | | |
| 0046 | 3045000000-E | 862 | STEEL BM GUARDRAIL, SHOP CURVED | 50 LF | | |
| 0047 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 0048 | 3195000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE AT-1 | 1 EA | | |
| 0049 | 3210000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE CAT-1 | 2 EA | | |
| 0050 | 3215000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE III | 3 EA | | |
| 0051 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 EA | | |
| 0052 | 3360000000-E | 863 | REMOVE EXISTING GUARDRAIL | 1,160 LF | | |
| 0053 | 3380000000-E | 862 | TEMPORARY STEEL BM GUARDRAIL | 100 LF | | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0054 | 3387000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (XI) | 2 EA | | |
| 0055 | 3389100000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY | 2 EA | | |
| 0056 | 3503000000-E | 866 | WOVEN WIRE FENCE, 47" FABRIC | 3,795 LF | | |
| 0057 | 3509000000-E | 866 | 4" TIMBER FENCE POSTS, 7'-6" LONG | 227 EA | | |
| 0058 | 3515000000-E | 866 | 5" TIMBER FENCE POSTS, 8'-0" LONG | 84 EA | | |
| 0059 | 3536000000-E | 866 | CHAIN LINK FENCE, 48" FABRIC | 1,060 LF | | |
| 0060 | 3542000000-E | 866 | METAL LINE POSTS FOR 48" CHAIN LINK FENCE | 87 EA | | |
| 0061 | 3548000000-E | 866 | METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE | 4 EA | | |
| 0062 | 3628000000-E | 876 | PLAIN RIP RAP, CLASS I | 10 TON | | |
| 0063 | 3649000000-E | 876 | PLAIN RIP RAP, CLASS B | 68 TON | | |
| 0064 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 1,060 SY | | |
| 0065 | 3659000000-N | SP | PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON | 1 EA | | |
| 0066 | 4048000000-E | 902 | REINFORCED CONCRETE SIGN FOOTINGS | 2 CY | | |
| 0067 | 4054000000-E | 902 | PLAIN CONCRETE SIGN FOOTINGS | 1 CY | | |
| 0068 | 4060000000-E | 903 | SUPPORTS, BREAKAWAY STEEL BEAM | 1,133 LB | | |
| 0069 | 4072000000-E | 903 | SUPPORTS, 3-LB STEEL U-CHANNEL | 1,265 LF | | |
| 0070 | 4096000000-N | 904 | SIGN ERECTION, TYPE D | 7 EA | | |
| 0071 | 4102000000-N | 904 | SIGN ERECTION, TYPE E | 34 EA | | |
| 0072 | 4108000000-N | 904 | SIGN ERECTION, TYPE F | 8 EA | | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-----------|-----------|--------|
| 0073 | 4110000000-N | 904 | SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A) | 3 EA | | |
| 0074 | 4110000000-N | 904 | SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B) | 2 EA | | |
| 0075 | 4115000000-N | 904 | SIGN ERECTION, OVERLAY (OVER- HEAD) | 3 EA | | |
| 0076 | 4129000000-N | 906 | RELOCATE SIGN, TYPE ***** (D) | 2 EA | | |
| 0077 | 4155000000-N | 907 | DISPOSAL OF SIGN SYSTEM, U- CHANNEL | 33 EA | | |
| 0078 | 4192000000-N | 907 | DISPOSAL OF SUPPORT, U-CHANNEL | 2 EA | | |
| 0079 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 477 SF | | |
| 0080 | 4405000000-E | 1110 | WORK ZONE SIGNS (PORTABLE) | 930 SF | | |
| 0081 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 130 SF | | |
| 0082 | 4415000000-N | 1115 | FLASHING ARROW PANELS, TYPE C | 2 EA | | |
| 0083 | 4420000000-N | 1120 | CHANGEABLE MESSAGE SIGNS | 2 EA | | |
| 0084 | 4430000000-N | 1130 | DRUMS | 400 EA | | |
| 0085 | 4435000000-N | 1135 | CONES | 100 EA | | |
| 0086 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 204 LF | | |
| 0087 | 4455000000-N | 1150 | FLAGGER | 200 MD | | |
| 0088 | 4465000000-N | 1160 | TEMPORARY CRASH CUSHIONS | 6 EA | | |
| 0089 | 4470000000-N | 1160 | RESET TEMPORARY CRASH CUSHIONS | 1 EA | | |
| 0090 | 4475000000-N | 1165 | TRUCK MOUNTED IMPACT ATTENUA- TOR (45 MPH) | 2 EA | | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0091 | 4485000000-E | 1170 | PORTABLE CONCRETE BARRIER | 1,720 | LF | |
| 0092 | 4510000000-N | SP | POLICE | 200 | HR | |
| 0093 | 4615000000-E | 1205 | REMOVABLE TAPE PAVEMENT MARKING LINES (4") | 3,885 | LF | |
| 0094 | 4625000000-E | 1205 | REMOVABLE TAPE PAVEMENT MARKING LINES (8") | 160 | LF | |
| 0095 | 4640000000-N | 1205 | REMOVABLE TAPE PAVEMENT MARKING CHARACTER | 4 | EA | |
| 0096 | 4645000000-N | 1205 | REMOVABLE TAPE PAVEMENT MARKING SYMBOL | 13 | EA | |
| 0097 | 4650000000-N | 1251 | TEMPORARY RAISED PAVEMENT MARKERS | 192 | EA | |
| 0098 | 4685000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) | 12,075 | LF | |
| 0099 | 4686000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) | 12,541 | LF | |
| 0100 | 4695000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS) | 460 | LF | |
| 0101 | 4710000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS) | 260 | LF | |
| 0102 | 4721000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL) | 20 | EA | |
| 0103 | 4725000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) | 55 | EA | |
| 0104 | 4770000000-E | 1205 | COLD APPLIED PLASTIC PAVEMENT MARKING LINES (4") | 2,337 | LF | |
| 0105 | 4780000000-E | 1205 | COLD APPLIED PLASTIC PAVEMENT MARKING LINES (8") | 160 | LF | |
| 0106 | 4800000000-N | 1205 | COLD APPLIED PLASTIC PAVEMENT MARKING CHARACTER | 4 | EA | |
| 0107 | 4805000000-N | 1205 | COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL | 11 | EA | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0108 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 61,660 | LF | |
| 0109 | 4820000000-E | 1205 | PAINT PAVEMENT MARKING LINES (8") | 1,060 | LF | |
| 0110 | 4825000000-E | 1205 | PAINT PAVEMENT MARKING LINES (12") | 448 | LF | |
| 0111 | 4835000000-E | 1205 | PAINT PAVEMENT MARKING LINES (24") | 408 | LF | |
| 0112 | 4840000000-N | 1205 | PAINT PAVEMENT MARKING CHARACTER | 20 | EA | |
| 0113 | 4845000000-N | 1205 | PAINT PAVEMENT MARKING SYMBOL | 79 | EA | |
| 0114 | 4850000000-E | 1205 | REMOVAL OF PAVEMENT MARKING LINES (4") | 5,550 | LF | |
| 0115 | 4900000000-N | 1252 | PERMANENT RAISED PAVEMENT MARKERS | 62 | EA | |
| 0116 | 4905000000-N | 1253 | SNOWPLOWABLE RAISED PAVEMENT MARKERS | 450 | EA | |
| 0117 | 5300000000-E | 1505 | FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI) | 140 | TON | |
| 0118 | 5306000000-E | SP | BEDDING MATERIAL, UTILITIES CLASS ***** (VI) | 140 | TON | |
| 0119 | 5360000000-E | 1510 | 6" DI WATER PIPE, PC 350 | 1,272 | LF | |
| 0120 | 5402000000-E | 1510 | DI RESTRAINED JOINT WATER PIPE FITTINGS, 250# MIN WP | 1,045 | LB | |
| 0121 | 5414000000-E | 1510 | 3/4" COPPER WATER PIPE, TYPE K | 34 | LF | |
| 0122 | 5480000000-E | 1510 | DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP | 375 | LB | |
| 0123 | 5540000000-E | 1510 | 6" GATE VALVE & VALVE BOX, 200# WP | 1 | EA | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0124 | 5558000000-E | 1510 | 12" GATE VALVE & VALVE BOX, *****WP (200# WP) | 2 EA | | |
| 0125 | 5576000000-E | 1510 | ***X*** TAPPING SLEEVE, VALVE & VALVE BOX, *****WP (6" X 6", 200# WP) | 1 EA | | |
| 0126 | 5576000000-E | 1510 | ***X*** TAPPING SLEEVE, VALVE & VALVE BOX, *****WP (8" X 6", 200# WP) | 1 EA | | |
| 0127 | 5648000000-N | 1510 | RELOCATE EXISTING WATER METER | 2 EA | | |
| 0128 | 5672000000-N | 1510 | RELOCATE EXISTING FIRE HYDRANT | 5 EA | | |
| 0129 | 5852000000-E | SP | *** STEEL ENCASEMENT PIPE, ***** THICK, BY BORING & JACKING (24", 0.250") | 780 LF | | |
| 0130 | 5888000000-E | SP | GENERIC UTILITY ITEM 12" DI RJ WATER PIPE, PC 350 | 880 LF | | |
| 0131 | 5888000000-E | SP | GENERIC UTILITY ITEM 8" DI RJ WATER PIPE, PC 350 | 150 LF | | |
| 0132 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 1,925 LF | | |
| 0133 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 450 TON | | |
| 0134 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 1,320 TON | | |
| 0135 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 585 TON | | |
| 0136 | 6015000000-E | 1615 | TEMPORARY MULCHING | 11.5 ACR | | |
| 0137 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 400 LB | | |
| 0138 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 1.75 TON | | |
| 0139 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 245 LF | | |
| 0140 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 6 EA | | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0141 | 6030000000-E | 1630 | SILT EXCAVATION | 3,405 CY | | |
| 0142 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 2,565 SY | | |
| 0143 | 6038000000-E | SP | PERMANENT SOIL REINFORCEMENT MAT | 397 SY | | |
| 0144 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 860 LF | | |
| 0145 | 6084000000-E | 1660 | SEEDING & MULCHING | 13 ACR | | |
| 0146 | 6087000000-E | 1660 | MOWING | 7 ACR | | |
| 0147 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 100 LB | | |
| 0148 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0149 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 275 LB | | |
| 0150 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 9.75 TON | | |
| 0151 | 6109000000-E | SP | SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BLEUGRASS) | 0.2 ACR | | |
| 0152 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 3.5 HR | | |
| 0153 | 6117000000-N | 1675 | RESPONSE FOR EROSION CONTROL | 8 EA | | |
| 0154 | 7060000000-E | 1705 | SIGNAL CABLE | 1,640 LF | | |
| 0155 | 7120000000-E | 1705 | VEHICLE SIGNAL HEAD (12", 3 SECTION) | 17 EA | | |
| 0156 | 7264000000-E | 1710 | MESSENGER CABLE (3/8") | 1,090 LF | | |
| 0157 | 7300000000-E | 1715 | TRENCHING (UNPAVED) | 1,080 LF | | |
| 0158 | 7324000000-N | 1716 | JUNCTION BOX (STANDARD SIZE) | 7 EA | | |
| 0159 | 7360000000-N | 1720 | WOOD POLE | 6 EA | | |
| 0160 | 7372000000-N | 1721 | GUY ASSEMBLY | 8 EA | | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0161 | 7408000000-E | 1722 | 1" RISER WITH WEATHERHEAD | 1 EA | | |
| 0162 | 7420000000-E | 1722 | 2" RISER WITH WEATHERHEAD | 4 EA | | |
| 0163 | 7444000000-E | 1725 | INDUCTIVE LOOP SAWCUT | 1,600 LF | | |
| 0164 | 7456000000-E | 1726 | LEAD-IN CABLE | 2,790 LF | | |
| 0165 | 7484000000-N | SP | MICROWAVE VEHICLE DETECTOR | 1 EA | | |
| 0166 | 7576000000-N | 1740 | METAL STRAIN SIGNAL POLE | 4 EA | | |
| 0167 | 7613000000-N | SP | SOIL TEST | 4 EA | | |
| 0168 | 7614000000-E | SP | DRILLED PIER FOUNDATION (** DIA) (42") | 60 LF | | |
| 0169 | 7636000000-N | 1745 | SIGN FOR SIGNALS | 6 EA | | |
| 0170 | 7684000000-N | 1750 | SIGNAL CABINET FOUNDATION | 1 EA | | |
| 0171 | 7688000000-N | SP | CABINET BASE ADAPTER | 1 EA | | |
| 0172 | 7756000000-N | 1751 | CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED) | 1 EA | | |
| 0173 | 7780000000-N | SP | DETECTOR CARD (TYPE 2070L) | 5 EA | | |
| 0174 | 7980000000-N | SP | GENERIC SIGNAL ITEM RELOCATE MICROWAVE VEHICLE DETECTOR | 2 EA | | |

WALL ITEMS

| | | | | | | |
|------|--------------|----|---|-------------|--|--|
| 0175 | 8847000000-E | SP | GENERIC RETAINING WALL ITEM PILE/PANEL RETAINING WALL (STA. 1+50.00 -REVC-) | 8,695 SF | | |
|------|--------------|----|---|-------------|--|--|

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|------------------------|--------------|-------|--|-----------------|-----------|--------|
| STRUCTURE ITEMS | | | | | | |
| 0176 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+71.54-L-) | Lump Sum | L.S. | |
| 0177 | 8119000000-E | 412 | UNCLASSIFIED STRUCTURE EXCAVATION | 1,904 CY | | |
| 0178 | 8147000000-E | 420 | REINFORCED CONCRETE DECK SLAB | 25,122 SF | | |
| 0179 | 8161000000-E | 420 | GROOVING BRIDGE FLOORS | 26,253 SF | | |
| 0180 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 361 CY | | |
| 0181 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (20+71.54-L-) | Lump Sum | L.S. | |
| 0182 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 53,815 LB | | |
| 0183 | 8238000000-E | 425 | SPIRAL COLUMN REINFORCING STEEL (BRIDGE) | 2,327 LB | | |
| 0184 | 8280000000-E | 440 | APPROX LBS STRUCTURAL STEEL | 1,005,950 LS | | |
| 0185 | 8364000000-E | 450 | HP12X53 STEEL PILES | 7,110 LF | | |
| 0186 | 8475000000-E | 460 | TWO BAR METAL RAIL | 273.55 LF | | |
| 0187 | 8482000000-E | 460 | THREE BAR METAL RAIL | 273.55 LF | | |
| 0188 | 8517000000-E | 460 | 1'-***X ***** CONCRETE PARAPET (1'-2" X 2'-6") | 281.91 LF | | |
| 0189 | 8531000000-E | 462 | 4" SLOPE PROTECTION | 1,060 SY | | |
| 0190 | 8650000000-N | SP | POT BEARINGS | Lump Sum | L.S. | |
| 0191 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 0192 | 8692000000-N | SP | EVAZOTE JOINT SEALS | Lump Sum | L.S. | |

C201006
FORSYTH COUNTY

2/16/99

Contract No: C201006

County: Forsyth

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General