R:\earthwork\earl2.inp

RD04S01C

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

PROJ. REFERENCE NO.	SHEET NO.
U-2717	X1-C

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station RAMP D	A2 Uncl. Exc. (cu. meters)	A2 Embt (cu. meters)
12+00.000	0	906
12+20.000	0	797
12+40.000	0	692
12+60.000	0	593
12+80.000	0	662
13+00.000	0	1026

Station LOOP C	A2 Uncl. Exc. (cu. meters)	A2 Embt (cu. meters)
10+79.235	0	0
10+80.000	0	19
11+00.000	7	321
11+60.000	1375	210
11+80.000	1012	0
12+00.000	1304	0
12+20.000	1390	0
12+40.000	1276	0
12+60.000	1231	0
12+80.000	1111	3
12+91.589	590	3

Station DRWAY1	A2 Uncl. Exc. (cu. meters)	A2 Embt (cu. meters)
10+04.000	0	0
10+20.000	0	384
10+40.000	0	642
10+60.000	0	1026
10+80.000	6	1039
11+00.000	10	602
11+20.000	8	263
11+40.000	8	136
11+60.000	7	103
11+80.000	7	61
11+97.846	7	34

Station DRWAY2	A2 Uncl. Exc. (cu. meters)	A2 Embt (cu. meters)
10+10.235	0	0
10+20.000	77	1
10+40.000	165	1
10+60.000	158	0

Station DRWAY3	A2 Uncl. Exc. (cu. meters)	A2 Embt (cu. meters)
10+20.000	0	0
10+40.000	0	40