

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-M	200	CLEARING & GRUBBING ... HEC-TARE(S)	Lump Sum	L.S.	
0004	0008000000-M	200	SUPPLEMENTARY CLEARING & GRUB-BING	0.4 HA		
0005	0022000000-M	225	UNCLASSIFIED EXCAVATION	46,000 M3		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (40+57.884)	Lump Sum	L.S.	
0007	0036000000-M	225	UNDERCUT EXCAVATION	9,700 M3		
0008	0080000000-M	SP	CLASS IV SUBGRADE STABILIZA-TION	16,000 MTN		
0009	0106000000-M	230	BORROW EXCAVATION	74,000 M3		
0010	0134000000-M	240	DRAINAGE DITCH EXCAVATION	4,450 M3		
0011	0156000000-M	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	4,050 M2		
0012	0163000000-M	250	REMOVAL OF EXISTING CONCRETE PAVEMENT	75 M2		
0013	0177000000-M	250	BREAKING OF EXISTING ASPHALT PAVEMENT	4,750 M2		
0014	0195000000-M	265	SELECT GRANULAR MATERIAL	500 M3		
0015	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	13,500 M2		
0016	0199000000-M	SP	TEMPORARY SHORING	98 M2		
0017	0248000000-N	SP	GENERIC GRADING ITEM VIBRATION MONITORING	Lump Sum	L.S.	
0018	0318000000-M	300	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRS	1,550 MTN		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0342000000-M	310	****MM SIDE DRAIN PIPE (300MM)	74.4 M		
0020	0343000000-M	310	375MM SIDE DRAIN PIPE	28.8 M		
0021	0344000000-M	310	450MM SIDE DRAIN PIPE	14.4 M		
0022	0360000000-M	310	300MM RC PIPE CULVERTS, CLASS III	910.8 M		
0023	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	1,552.8 M		
0024	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	980.4 M		
0025	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	752.4 M		
0026	0384000000-M	310	750MM RC PIPE CULVERTS, CLASS III	55.2 M		
0027	0390000000-M	310	900MM RC PIPE CULVERTS, CLASS III	164.4 M		
0028	0396000000-M	310	1050MM RC PIPE CULVERTS, CLASS III	38.4 M		
0029	0402000000-M	310	1200MM RC PIPE CULVERTS, CLASS III	27.6 M		
0030	0453000000-M	310	***MM PIPE END SECTION (450MM)	2 EA		
0031	0453000000-M	310	***MM PIPE END SECTION (600MM)	1 EA		
0032	0576000000-M	310	***MM CS PIPE CULVERTS, ****MM THICK (150MM, 1.63MM)	8.4 M		
0033	0636000000-M	310	***MM CS PIPE ELBOWS, ****MM THICK (600MM, 1.63MM))	2 EA		
0034	0708000000-M	310	400MM BIT COAT CS PIPE CUL- VERTS, TYPE B 1.63MM THICK	24 M		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	0720000000-M	310	600MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK	26.4 M		
0036	0806000000-M	310	400MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK (400MM, 1.63MM))	2 EA		
0037	0808000000-M	310	600MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK (150MM, 1.63MM)	1 EA		
0038	0980000000-M	SP	****MM WELDED STEEL PIPE, ****MM THICK, GRADE B, INSTALLED BY BORING & JACKING (1050MM, 2.77MM)	76.8 M		
0039	0980000000-M	SP	****MM WELDED STEEL PIPE, ****MM THICK, GRADE B, INSTALLED BY BORING & JACKING (900MM, 2.77MM)	145.2 M		
0040	0986000000-M	SP	GENERIC PIPE ITEM 150MM PVC PIPE	13.2 M		
0041	0992000000-M	SP	GENERIC PIPE ITEM 150MM PVC PIPE ELBOWS	2 EA		
0042	0995000000-M	340	PIPE REMOVAL	2,014.1 M		
0043	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0044	1022000000-M	SP	SEALING EXISTING PAVEMENT CRACKS	100 KG		
0045	1110000000-M	510	STABILIZER AGGREGATE	100 MTN		
0046	1121000000-M	520	AGGREGATE BASE COURSE	3,450 MTN		
0047	1220000000-M	545	INCIDENTAL STONE BASE	500 MTN		
0048	1297000000-M	607	MILLING ASPHALT PAVEMENT, **MM DEPTH (55MM)	100 M2		
0049	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,650 MTN		
0050	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	34,400 MTN		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0051	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	650 MTN		
0052	1503000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	20,100 MTN		
0053	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,100 MTN		
0054	1523000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	19,900 MTN		
0055	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,600 MTN		
0056	1565000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,250 MTN		
0057	1869000000-M	710	***MM PORT CEM CONC PAVEMENT, MISCELLANEOUS (WITHOUT DOWELS) (150MM)	400 M2		
0058	2000000000-N	806	RIGHT OF WAY MARKERS	46 EA		
0059	2022000000-M	815	SUBDRAIN EXCAVATION	276 M3		
0060	2033000000-M	815	SUBDRAIN FINE AGGREGATE	207 M3		
0061	2044000000-M	815	150MM PERFORATED SUBDRAIN PIPE	500 M		
0062	2055000000-M	815	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS	50 EA		
0063	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4 EA		
0064	2077000000-M	815	150MM OUTLET PIPE (SUBDRAINS)	8 M		
0065	2209000000-M	838	ENDWALLS	13.2 M3		
0066	2253000000-M	840	PIPE COLLARS	2.42 M3		
0067	2264000000-M	840	PIPE PLUGS	1.33 M3		
0068	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	186 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	35		M
0070	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	21		EA
0071	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	10		EA
0072	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3		EA
0073	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	24		EA
0074	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	66		EA
0075	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	53		EA
0076	2396000000-N	840	FRAME WITH COVER, STD 840.54	7		EA
0077	2418000000-M	SP	FRAME WITH GRATES, DRIVEWAY DROP INLET	16.4		M
0078	2484000000-M	SP	GENERIC DRAINAGE ITEM 100MM POLYMER DRAIN LINE WITH WIDE SLOT GRATE	14.4		M
0079	2500000000-M	842	CONCRETE RETAINING WALLS	250		M3
0080	2542000000-M	846	450MM CONCRETE CURB & GUTTER	30		M
0081	2549000000-M	846	750MM CONCRETE CURB & GUTTER	5,800		M
0082	2591000000-M	848	100MM CONCRETE SIDEWALK	6,550		M2
0083	2598000000-M	848	CONCRETE WHEELCHAIR RAMPS	650		M2
0084	2612000000-M	848	150MM CONCRETE DRIVEWAY	1,400		M2
0085	2655000000-M	852	125MM MONOLITHIC CONCRETE IS- LANDS (KEYED IN)	175		M2

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	2724000000-M	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	70 M		
0087	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
0088	3030000000-M	862	STEEL BM GUARDRAIL	899.16 M		
0089	3045000000-M	862	STEEL BM GUARDRAIL, SHOP CURVED	53.34 M		
0090	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0091	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0092	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0093	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	5 EA		
0094	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3 EA		
0095	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0096	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0097	3536000000-M	866	CHAIN LINK FENCE, 1200MM FABRIC	2,300 M		
0098	3542000000-M	866	METAL LINE POSTS FOR 1200MM CHAIN LINK FENCE	640 EA		
0099	3548000000-M	866	METAL TERMINAL POSTS FOR 1200MM CHAIN LINK FENCE	80 EA		
0100	3557000000-M	866	ADDITIONAL BARBED WIRE	200 M		
0101	3628000000-M	876	PLAIN RIP RAP, CLASS I	210 MTN		
0102	3649000000-M	876	PLAIN RIP RAP, CLASS B	800 MTN		
0103	3651000000-M	SP	BOULDERS	61 MTN		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	680		M2
0105	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2		EA
0106	4048000000-M	902	REINFORCED CONCRETE SIGN FOOTINGS	3		M3
0107	4054000000-M	902	PLAIN CONCRETE SIGN FOOTINGS	1		M3
0108	4060000000-M	903	SUPPORTS, BREAKAWAY STEEL BEAM	1,437		KG
0109	4066000000-M	903	SUPPORTS, SIMPLE STEEL BEAM	400		KG
0110	4072000000-M	903	SUPPORTS, 4.5KG STEEL U-CHANNEL	721		M
0111	4096000000-N	904	SIGN ERECTION, TYPE D	2		EA
0112	4102000000-N	904	SIGN ERECTION, TYPE E	113		EA
0113	4108000000-N	904	SIGN ERECTION, TYPE F	10		EA
0114	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	4		EA
0115	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	3		EA
0116	4129000000-N	906	RELOCATE SIGN, TYPE ***** (D)	12		EA
0117	4129000000-N	906	RELOCATE SIGN, TYPE ***** (E)	5		EA
0118	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	125		EA
0119	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	3		EA
0120	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	16		EA
0121	4278000000-N	908	TEMPORARY RELOCATE SIGN, TYPE ***** GROUND TO GROUND	4		EA

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	4360000000-N	SP	GENERIC SIGNING ITEM DISPOSAL OF SIGN SYSTEM ON SPAN WIRE	2 EA		
0123	4400000000-M	1110	WORK ZONE SIGNS (STATIONARY)	100 M2		
0124	4405000000-M	1110	WORK ZONE SIGNS (PORTABLE)	59 M2		
0125	4410000000-M	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	6 M2		
0126	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0127	4420000000-N	1120	CHANGEABLE MESSAGE SIGNS	3 EA		
0128	4425000000-N	1125	WARNING FLAG SETS	2 EA		
0129	4430000000-N	1130	DRUMS	400 EA		
0130	4435000000-N	1135	CONES	300 EA		
0131	4445000000-M	1145	BARRICADES (TYPE III)	116 M		
0132	4450000000-N	1150	FLAGGER	3,264 HR		
0133	4460000000-N	1155	WARNING LIGHTS (TYPE B)	2 EA		
0134	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	8 EA		
0135	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	1 EA		
0136	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	2 EA		
0137	4485000000-M	1170	PORTABLE CONCRETE BARRIER	1,720 M		
0138	4490000000-M	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	101 M		
0139	4495000000-M	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	580 M		
0140	4500000000-M	1170	RESET PORTABLE CONCRETE BAR- RIER	2,320 M		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0141	4507000000-M	SP	WATER FILLED BARRIER	200 M		
0142	4510000000-N	SP	POLICE	200 HR		
0143	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	760 EA		
0144	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	9,797 M		
0145	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	13,424 M		
0146	4690000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (150MM, 3.1MM)	108 M		
0147	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	1,133 M		
0148	4697000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 3.1MM)	94 M		
0149	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	666 M		
0150	4721000000-M	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (3.1MM)	32 EA		
0151	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	153 EA		
0152	4770000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES (100MM)	443 M		
0153	4780000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES (200MM)	100 M		
0154	4800000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING CHARACTER	4 EA		
0155	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL	5 EA		
0156	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	32,183 M		
0157	4820000000-M	1205	PAINT PAVEMENT MARKING LINES (200MM)	2,234 M		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0158	4835000000-M	1205	PAINT PAVEMENT MARKING LINES (600MM)	592 M		
0159	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	8 EA		
0160	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	50 EA		
0161	4850000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (100MM)	7,989 M		
0162	4860000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (200MM)	90 M		
0163	4870000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (600MM)	200 M		
0164	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	1,637 EA		
0165	4935000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL)	64 EA		
0166	4940000000-N	1267	FLEXIBLE DELINEATORS (YELLOW)	44 EA		
0167	4945000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL & RED)	10 EA		
0168	4950000000-N	1267	FLEXIBLE DELINEATORS (YELLOW & RED)	10 EA		
0169	5300000000-M	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	1,020 MTN		
0170	5312000000-M	1505	SELECT BACKFILL MATERIAL, UTILITIES CLASS **** (II)	50 MTN		
0171	5318000000-M	1505	PAVEMENT REPAIR FOR UTILITY WORK	1,500 MTN		
0172	5354000000-M	1510	100MM DI WATER PIPE, PC 2.41MPA	7 M		
0173	5360000000-M	1510	150MM DI WATER PIPE, PC 2.41MPA	63 M		
0174	5366000000-M	1510	200MM DI WATER PIPE, PC 2.41MPA	2 M		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0175	5378000000-M	1510	300MM DI WATER PIPE, PC 2.41MPA	2 M		
0176	5384000000-M	1510	400MM DI WATER PIPE, PC ***MPA 2.41	1,214 M		
0177	5402000000-M	1510	DI RESTRAINED JOINT WATER PIPE FITTINGS, 1.72MPA MIN WP	11,069 KG		
0178	5408000000-M	1510	***MM COPPER WATER PIPE, TYPE K 50MM	4 M		
0179	5414000000-M	1510	20MM COPPER WATER PIPE, TYPE K	746 M		
0180	5420000000-M	1510	25MM COPPER WATER PIPE, TYPE K	162 M		
0181	5480000000-M	1510	DUCTILE IRON WATER PIPE FIT- TINGS, 1.72MPA MIN WP	726 KG		
0182	5510000000-M	1510	20MM CORPORATION STOP	55 EA		
0183	5516000000-M	1510	25MM CORPORATION STOP	6 EA		
0184	5534000000-M	1510	***MM GATE VALVE & VALVE BOX, ****MPA WP (400MM,1.38MPA)	7 EA		
0185	5540000000-M	1510	150MM GATE VALVE & VALVE BOX, 1.38MPA WP	23 EA		
0186	5546000000-M	1510	200MM GATE VALVE & VALVE BOX, ****MPA WP (1.38MPA)	5 EA		
0187	5558000000-M	1510	300MM GATE VALVE & VALVE BOX, ****MPA WP (1.38MPA)	5 EA		
0188	5576000000-M	1510	*** X ***MM TAPPING SLEEVE, VALVE & VALVE BOX, ****MPA WP (400MM X 150MM,1.38 MPA)	2 EA		
0189	5576000000-M	1510	*** X ***MM TAPPING SLEEVE, VALVE & VALVE BOX, ****MPA WP (400MM X 400MM,1.38 MPA)	4 EA		
0190	5594000000-M	SP	***MM AIR RELEASE VALVE & MAN- HOLE 150MM	1 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0191	5612000000-M	1510	***MM TRANSITION COUPLING, ***** (100MM, DI TO CI)	1 EA		
0192	5618000000-M	1510	150MM TRANSITION COUPLING, ***** DI TO CI	8 EA		
0193	5624000000-M	1510	200MM TRANSITION COUPLING, ***** DI TO CI	2 EA		
0194	5636000000-M	1510	300MM TRANSITION COUPLING, ***** DI TO CI	4 EA		
0195	5648000000-N	1510	RELOCATE EXISTING WATER METER	30 EA		
0196	5666000000-M	1510	FIRE HYDRANT, ****MPA WP (1.38MPA WP)	13 EA		
0197	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	7 EA		
0198	5690000000-M	1520	***MM PVC SEWER PIPE, SDR ** (100MM, SDR 35)	1,200 M		
0199	5726000000-M	1520	200MM DI SEWER PIPE, PC 2.41MPA	15 M		
0200	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	95 EA		
0201	5774000000-M	1525	****MM DIA PRECAST CONC SEWER MANHOLE 0-1.8M DEPTH 1200MM	1 EA		
0202	5780000000-M	1525	PRECAST CONC MANHOLE WALL, ****MM DIA, OVER 1.8M HT 1200MM	1 M		
0203	5804000000-M	1530	FILL OR REMOVE ABANDONED 300MM PIPE, ***** CI WATER	1,543 M		
0204	5810000000-M	1530	FILL OR REMOVE ABANDONED 400MM PIPE, ***** CI WATER	75 M		
0205	5828000000-N	1530	REMOVE EXISTING MANHOLE	1 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0206	5882000000-N	SP	GENERIC UTILITY ITEM 150MM RESTRAINED RETAINER GLANDS	50 EA		
0207	5882000000-N	SP	GENERIC UTILITY ITEM 200MM RESTRAINED RETAINER GLANDS	50 EA		
0208	5882000000-N	SP	GENERIC UTILITY ITEM 20MM WATER METER AND METER BOX	67 EA		
0209	5882000000-N	SP	GENERIC UTILITY ITEM 300MM RESTAINED RETAINER GLANDS	50 EA		
0210	5882000000-N	SP	GENERIC UTILITY ITEM 400MM RESTRAINED RETAINER GLANDS	50 EA		
0211	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE 100MM WATER METER VAULT	1 EA		
0212	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE 200MM BACKFLOW PREVENTER VAULT	1 EA		
0213	5888000000-M	SP	GENERIC UTILITY ITEM 100MM DI RESTRAINED JOINT WATER PIPE, PC 2.41 MPA	5 M		
0214	5888000000-M	SP	GENERIC UTILITY ITEM 150MM DI RESTRAINED JOINT WATER PIPE, PC 2.41 MPA	299 M		
0215	5888000000-M	SP	GENERIC UTILITY ITEM 200MM DI RESTRAINED JOINT WATER PIPE, PC 2.41 MPA	75 M		
0216	5888000000-M	SP	GENERIC UTILITY ITEM 300MM DI RESTRAINED JOINT WATER PIPE, PC 2.41 MPA	140 M		
0217	5888000000-M	SP	GENERIC UTILITY ITEM 400MM DI RESTRAINED JOINT WATER PIPE, PC 2.41 MPA	444 M		
0218	5900000000-M	SP	GENERIC UTILITY ITEM #67 BEDDING STONE	1,020 MTN		
0219	6000000000-M	1605	TEMPORARY SILT FENCE	4,200 M		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0220	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	460 MTN		
0221	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	5,900 MTN		
0222	6012000000-M	1610	SEDIMENT CONTROL STONE	3,130 MTN		
0223	6015000000-M	1615	TEMPORARY MULCHING	8 HA		
0224	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	400 KG		
0225	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	3.25 MTN		
0226	6024000000-M	1622	TEMPORARY SLOPE DRAINS	200 M		
0227	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	16 EA		
0228	6030000000-M	1630	SILT EXCAVATION	15,150 M3		
0229	6036000000-M	1631	MATTING FOR EROSION CONTROL	8,200 M2		
0230	6038000000-M	SP	PERMANENT SOIL REINFORCEMENT MAT	765 M2		
0231	6042000000-M	1632	6.4MM HARDWARE CLOTH	1,350 M		
0232	6084000000-M	1660	SEEDING & MULCHING	9.5 HA		
0233	6087000000-M	1660	MOWING	4.5 HA		
0234	6090000000-M	1661	SEED FOR REPAIR SEEDING	100 KG		
0235	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	0.5 MTN		
0236	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	275 KG		
0237	6108000000-M	1665	FERTILIZER TOPDRESSING	15.5 MTN		
0238	6109000000-M	SP	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BLUEGRASS)	0.15 HA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0239	6114000000-N	SP	SPECIALIZED HAND MOWING	7.5 HR		
0240	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	16 EA		
0241	6126000000-M	SP	STREAMBANK REFORESTATION	0.2 HA		
0242	6147000000-M	SP	GENERIC EROSION CONTROL ITEM SAFETY FENCE	800 M		
0243	7036000000-M	1705	PEDESTRIAN SIGNAL HEAD (300MM, 1 SECTION)	8 EA		
0244	7060000000-M	1705	SIGNAL CABLE	2,345 M		
0245	7108000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 1 SECTION)	4 EA		
0246	7120000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	49 EA		
0247	7144000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 5 SECTION)	10 EA		
0248	7252000000-M	1710	MESSENGER CABLE (6.35MM)	3,400 M		
0249	7264000000-M	1710	MESSENGER CABLE (9.52MM)	285 M		
0250	7279000000-M	1715	TRACER WIRE	275 M		
0251	7300000000-M	1715	TRENCHING (UNPAVED)	1,355 M		
0252	7301000000-M	SP	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, *****MM (** CONDUIT) (50MM, 2)	480 M		
0253	7302000000-M	SP	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, 31.75MM (** CONDUIT) (1)	480 M		
0254	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	55 EA		
0255	7336000000-N	1716	JUNCTION BOX (OVER-SIZED)	8 EA		
0256	7360000000-N	1720	WOOD POLE	15 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0257	7372000000-N	1721	GUY ASSEMBLY	32 EA		
0258	7408000000-M	1722	25MM RISER WITH WEATHERHEAD	2 EA		
0259	7420000000-M	1722	50MM RISER WITH WEATHERHEAD	8 EA		
0260	7432000000-M	1722	50MM RISER WITH HEAT SHRINK TUBING	7 EA		
0261	7444000000-M	1725	INDUCTIVE LOOP SAWCUT	3,560 M		
0262	7456000000-M	1726	LEAD-IN CABLE	2,500 M		
0263	7484000000-N	SP	MICROWAVE VEHICLE DETECTOR	2 EA		
0264	7516000000-M	1730	COMMUNICATIONS CABLE (**FIBER) (24)	1,500 M		
0265	7516000000-M	1730	COMMUNICATIONS CABLE (**FIBER) (48)	2,500 M		
0266	7528000000-M	1730	DROP CABLE	250 M		
0267	7540000000-N	1731	AERIAL SPLICE ENCLOSURE	4 EA		
0268	7552000000-N	1731	INTERCONNECT CENTER	8 EA		
0269	7566000000-N	1733	DELINEATOR MARKER	8 EA		
0270	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIVER	1 EA		
0271	7575140000-N	SP	FIBER-OPTIC SPLICE CABINET (BASE MOUNTED)	2 EA		
0272	7575160000-M	SP	REMOVE EXISTING COMMUNICATIONS CABLE	2,200 M		
0273	7588000000-N	1741	SIGNAL SUPPORT MAST ARM WITH METAL POLE	15 EA		
0274	7590000000-N	SP	DOUBLE MAST ARM WITH METAL POLE	3 EA		
0275	7613000000-N	SP	SOIL TEST	18 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0276	7614000000-M	SP	DRILLED PIER FOUNDATION (**MM DIA) (1070MM)	90 M		
0277	7631000000-N	1744	MAST ARM WITH METAL POLE DE-SIGN	18 EA		
0278	7636000000-N	1745	SIGN FOR SIGNALS	1 EA		
0279	7684000000-N	1750	SIGNAL CABINET FOUNDATION	8 EA		
0280	7828000000-N	1751	CONTROLLER WITH CABINET (NEMA TS-2, TYPE 2 CONTROLLER, TYPE 1 CABINET, BASE MOUNTED)	6 EA		
0281	7852000000-N	SP	DETECTOR CARD (NEMA TS-2)	51 EA		
0282	7980000000-N	SP	GENERIC SIGNAL ITEM FIBER OPTIC TRANSCEIVER	6 EA		
STRUCTURE ITEMS						
0283	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (40+56.584 -L-)	Lump Sum	L.S.	
0284	8105560000-M	SP	1220MM DIA DRILLED PIERS IN SOIL	66.6 M		
0285	8105660000-M	SP	1220MM DIA DRILLED PIERS NOT IN SOIL	14.4 M		
0286	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0287	8116000000-M	SP	CSL TUBES	342 M		
0288	8147000000-M	420	REINFORCED CONCRETE DECK SLAB	2,319 M2		
0289	8161000000-M	420	GROOVING BRIDGE FLOORS	2,379 M2		
0290	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	227.2 M3		
0291	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (40+56.584 -L-)	Lump Sum	L.S.	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0292	8217000000-M	425	REINFORCING STEEL (BRIDGE)	33,706 KG		
0293	8238000000-M	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,226 KG		
0294	8280000000-M	440	APPROX KG STRUCTURAL STEEL	405,050 LS		
0295	8364000000-M	450	HP310X79 STEEL PILES	720 M		
0296	8482000000-M	460	THREE BAR METAL RAIL	151.26 M		
0297	8531000000-M	462	100MM SLOPE PROTECTION	680 M2		
0298	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0299	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0300	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0943/Sep17/Q908787.07/D1327942020000/E300

Total Amount Of Bid For Entire Project :

C201009
GUILFORD COUNTY

2/16/99

Contract No: C201009

County: Guilford

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General