



| | |
|---------------------|-----------|
| PROJ. REFERENCE NO. | SHEET NO. |
| R-2514A | TCP-3 |

TEMPORARY PAVEMENT MARKING SCHEDULE

| SYMBOL | DESCRIPTION | PAY ITEM QUANTITY BREAKDOWN | TOTAL QUANTITY |
|-----------------------------------|----------------------------|--------------------------------|----------------|
| PAVEMENT MARKING LINES | | | |
| PAINT (100MM) | | | |
| PA | WHITE EDGELINE (2X) | 41936 M | |
| PB | YELLOW EDGELINE (2X) | 3380 M | |
| PC | 3 M. WHITE SKIP (2X) | 544 M | |
| PD | 0.5 M. WHITE MINISKIP (2X) | 213 M | |
| PE | WHITE SOLID LANE LINE (2X) | 1250 M | |
| PI | YELLOW DOUBLE CENTER (2X) | 39600 M | |
| | | TOTAL | 86923 M |
| PAINT (200MM) | | | |
| PS | WHITE DIAGONAL (2X) | 1134 M | |
| PV | YELLOW DIAGONAL (2X) | 138 M | |
| | | TOTAL | 1272 M |
| PAINT (600MM) | | | |
| P4 | WHITE STOPBAR (2X) | 238 M | |
| | | TOTAL | 238 M |
| PAINT MARKING SYMBOLS | | | |
| QA | LEFT TURN ARROW (2X) | 24 EA | |
| QB | RIGHT TURN ARROW (2X) | 30 EA | |
| QC | STRAIGHT ARROW (2X) | 34 EA | |
| QD | COMBO.STRAIGHT/LEFT (2X) | 12 EA | |
| QE | COMBO.STRAIGHT/RIGHT (2X) | 4 EA | |
| | | TOTAL | 104 EA |
| TEMPORARY RAISED PAVEMENT MARKERS | | | |
| MH | YELLOW & YELLOW | 430 EA | |
| MI | CRYSTAL & RED | 154 EA | |
| | | TOTAL | 584 EA |

NOTE: FOR EACH PAINT PAVEMENT MARKING ITEM, 1X IMPLIES A SINGLE APPLICATION, 2X IMPLIES TWO APPLICATIONS, AND 3X IMPLIES THREE APPLICATIONS.

| | | | |
|------------------|----------------|---|-----------|
| APPROVED: _____ | DATE: _____ | TEMPORARY PAVEMENT MARKING QUANTITIES | |
| | SCALE: NONE | | REVISIONS |
| | DATE: 11/18/03 | | |
| | DWG. BY: KWD | | |
| | DESIGN BY: KWD | | |
| REVIEWED BY: JHJ | | | |
| | | <small>CARD FILE R-2514A_TC_TCP03.DGN</small> | |

24-NOV-2003 09:22
 91-CAD\03-11-03\000\R-2514A\TrafficControl\TCP\R-2514A_TC_TCP03.dgn
 Jando AT DUNN