

5/28/99

COMPUTED BY: KVN DATE: 03-08-04  
CHECKED BY: HDB DATE: 03-15-04

PROJECT REFERENCE NO. B-3885  
SHEET NO. 3-A

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

SUMMARY OF EARTHWORK  
IN CUBIC YARDS

Summary of Earthwork table with columns: LOCATION, UNCLASSIFIED EXCAVATION, UNDERCUT, EMBT+%, BORROW, WASTE. Rows include STA 14+35.00 TO STA 16+95.00, STA 18+55.00, STA 10+00.00 TO STA 11+57.32, and project totals.

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, BREAKING OF EXISTING PAVEMENT, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING". PAVEMENT STRUCTURE NO. = 125 CY

SUMMARY OF PAVEMENT REMOVAL  
IN SQUARE YARDS

Summary of Pavement Removal table with columns: LOCATION, ASPHALT REMOVAL, ASPHALT BREAK-UP, CONCRETE REMOVAL, CONCRETE BREAK-UP. Rows include STA 16+02.00 TO STA 17+18+1/2 and STA 18+38+1/2 TO STA 18+80.00.

RIGHT OF WAY AREA DATA

Right of Way Area Data table with columns: PARCEL NO., PROPERTY OWNERS NAMES, TOTAL ACREAGE, AREA TAKEN, AREA REMAINING RT., AREA REMAINING LT., TEMPORARY CONSTRUCTION EASEMENT. Rows list owners like JAY MILLER, JAMES W. ROGERS, and SCHOPLER FAMILY, LLC.

LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48" & UNDER)

Large table listing pipes and endwalls with columns for station, size, thickness, location, pipe type, endwalls, grates, and remarks. Includes pipe sizes from 12" to 48" and materials like Class III R.C. Pipe and Bituminous Coated C.S. Pipe.

GUARDRAIL SUMMARY

Guardrail Summary table with columns: SURVEY LINE, BEG. STA., END STA., LOCATION, LENGTH (STRAIGHT, SHOP CURVED, DOUBLE FACED), WARRANT POINT (APPROACH END, TRAILING END), TOTAL SHOUL. WIDTH, FLARE LENGTH, W, ANCHORS, IMPACT ATTENUATOR, and REMARKS. Includes subtotals and SAY values.

08-SEP-2004 10:37 AM  
R:\Paved\49-P\B-3885.ssm  
k.vn@ndc.com