

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

INDEX OF CROSS SECTION SHEETS

EARTHWORK VOLUME SUMMARY

-L-
-DR1-

X-0
X-1 TO X-7
X-8 TO X-12

CROSS SECTION SUMMARY

EARTHWORK VOLUME
IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	EMBANKMENT	UNDERCUT EXC.
-L- 14+35.00	0	0	
-L- 15+00.00	30	18	
-L- 15+50.00	45	32	
-L- 16+00.00	24	16	
-L- 16+50.00	76	37	
-L- 16+95.00 (Begin Bridge)	91	48	
-L- 18+55.00 (End Bridge)	0	0	
-L- 19+00.00	0	215	
-L- 19+50.00	0	225	
-L- 20+00.00	0	200	
-L- 20+50.00	0	188	
-L- 21+00.00	0	175	
-L- 21+50.00	0	152	
-L- 22+00.00	0	109	
-L- 22+50.00	2	42	
-L- 23+00.00	10	5	
-L- 23+50.00	16	1	
-L- 23+75.00	1	0	
SUBTOTAL 1	298	1463	

LOCATION	UNCLASSIFIED EXCAVATION	EMBANKMENT	UNDERCUT EXC.
-DR1- 10+00.00	0	0	
-DR1- 10+10.00	4	0	
-DR1- 10+20.00	5	0	
-DR1- 10+30.00	6	0	
-DR1- 10+40.00	6	0	
-DR1- 10+50.00	6	0	
-DR1- 10+60.00	6	1	
-DR1- 10+70.00	6	1	
-DR1- 10+80.00	5	1	
-DR1- 10+90.00	7	1	
-DR1- 11+00.00	9	1	
-DR1- 11+10.00	10	0	
-DR1- 11+20.00	14	0	
-DR1- 11+30.00	18	0	
-DR1- 11+40.00	17	0	
-DR1- 11+50.00	10	1	
-DR1- 11+57.32	3	1	
SUBTOTAL 2	132	7	
TOTAL	430	1470	

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the contract lump sum price for "Grading".