

County : Caswell, Rockingham

| Line #               | Item Number  | Sec # | Description                                                        | Quantity      | Unit Cost | Amount |
|----------------------|--------------|-------|--------------------------------------------------------------------|---------------|-----------|--------|
| <b>ROADWAY ITEMS</b> |              |       |                                                                    |               |           |        |
| 0001                 | 0000100000-N | 800   | MOBILIZATION                                                       | Lump Sum      | L.S.      |        |
| 0002                 | 1220000000-E | 545   | INCIDENTAL STONE BASE                                              | 1,025<br>TON  |           |        |
| 0003                 | 1245000000-E | SP    | SHOULDER RECONSTRUCTION                                            | 1.42<br>SMI   |           |        |
| 0004                 | 1297000000-E | 607   | MILLING ASPHALT PAVEMENT, ****<br>DEPTH<br>(2-1/2")                | 8,867<br>SY   |           |        |
| 0005                 | 1297000000-E | 607   | MILLING ASPHALT PAVEMENT, ****<br>DEPTH<br>(3")                    | 4,990<br>SY   |           |        |
| 0006                 | 1308000000-E | 607   | MILLING ASPHALT PAVEMENT, ****<br>TO ***** DEPTH<br>(0" TO 1-1/2") | 1,826<br>SY   |           |        |
| 0007                 | 1308000000-E | 607   | MILLING ASPHALT PAVEMENT, ****<br>TO ***** DEPTH<br>(0" TO 1-1/4") | 59<br>SY      |           |        |
| 0008                 | 1308000000-E | 607   | MILLING ASPHALT PAVEMENT, ****<br>TO ***** DEPTH<br>(0" TO 3")     | 4,144<br>SY   |           |        |
| 0009                 | 1489000000-E | 610   | ASPHALT CONC BASE COURSE, TYPE<br>B25.0B                           | 509<br>TON    |           |        |
| 0010                 | 1498000000-E | 610   | ASPHALT CONC INTERMEDIATE<br>COURSE, TYPE I19.0B                   | 790<br>TON    |           |        |
| 0011                 | 1519000000-E | 610   | ASPHALT CONC SURFACE COURSE,<br>TYPE S9.5B                         | 12,792<br>TON |           |        |
| 0012                 | 1525000000-E | SP    | ASPHALT CONC SURFACE COURSE,<br>TYPE SF9.5A                        | 3,432<br>TON  |           |        |
| 0013                 | 1560000000-E | 620   | ASPHALT BINDER FOR PLANT MIX,<br>GRADE PG 64-22                    | 1,034<br>TON  |           |        |
| 0014                 | 1775000000-E | 660   | ASPHALT SURFACE TREATMENT, MAT<br>COAT, #78M STONE                 | 42,709<br>SY  |           |        |
| 0015                 | 2600000000-N | SP    | RETROFIT EXISTING WHEELCHAIR<br>RAMPS                              | 8<br>EA       |           |        |
| 0016                 | 2830000000-N | 858   | ADJUSTMENT OF MANHOLES                                             | 16<br>EA      |           |        |

County : Caswell, Rockingham

| Line # | Item Number  | Sec # | Description                                          | Quantity      | Unit Cost | Amount |
|--------|--------------|-------|------------------------------------------------------|---------------|-----------|--------|
| 0017   | 2845000000-N | 858   | ADJUSTMENT OF METER BOXES OR VALVE BOXES             | 13<br>EA      |           |        |
| 0018   | 4685000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)   | 59,572<br>LF  |           |        |
| 0019   | 4686000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)  | 47,032<br>LF  |           |        |
| 0020   | 4690000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)  | 434<br>LF     |           |        |
| 0021   | 4695000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)   | 451<br>LF     |           |        |
| 0022   | 4697000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)  | 404<br>LF     |           |        |
| 0023   | 4710000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS) | 177<br>LF     |           |        |
| 0024   | 4721000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)    | 4<br>EA       |           |        |
| 0025   | 4725000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)      | 101<br>EA     |           |        |
| 0026   | 4810000000-E | 1205  | PAINT PAVEMENT MARKING LINES (4")                    | 332,130<br>LF |           |        |
| 0027   | 6110000000-E | 1670  | RESIDENTIAL SEEDING                                  | 0.7<br>ACR    |           |        |
| 0028   | 7300000000-E | 1715  | TRENCHING (UNPAVED)                                  | 100<br>LF     |           |        |
| 0029   | 7312000000-N | 1716  | JUNCTION BOX (*****)<br>(PULL BOX)                   | 3<br>EA       |           |        |
| 0030   | 7444000000-E | 1725  | INDUCTIVE LOOP SAWCUT                                | 3,000<br>LF   |           |        |
| 0031   | 7456000000-E | 1726  | LEAD-IN CABLE                                        | 300<br>LF     |           |        |

1125/Oct14/Q525925.12/D104665100000/E31

Total Amount Of Bid For Entire Project :

C201312  
CASWELL & ROCKINGHAM COUNTIES

2/16/99

Contract No: C201312

Counties: Caswell & Rockingham

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General