R:\earthwork\earl2.inp

RD04S01C

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked

PROJ. REFERENCE NO.	SHEET NO.
U-2912	X1-B

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station Y9	A2 Uncl. Exc. (cu. meters)	A2 Embt (cu. meters)
10+00.000	0	0
10+10.000	73	0
10+22.797	119	0

Station Y10	A2 Uncl. Exc. (cu. meters)	A2 Embt (cu. meters)
10+00.000	0	0
10+12.765	96	0