PROJ. REFERENCE NO.	SHEET NO.
B-4096	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station L Phase I Crossover	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+50.00	41	0
11+00.00	45	0
11+50.00	40	0
12+00.00	41	0
12+50.00	40	0
13+00.00	34	0
13+50.00	29	0
14+00.00	24	1
14+50.00	28	1
15+00.00	26	0
15+48.86	8	0

Station L Phase I Crossover	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
24+41.55	0	0
24+50.00	3	0
25+00.00	34	0
25+50.00	35	0
26+00.00	37	0
26+50.00	37	0
27+00.00	30	2
27+50.00	28	2
28+00.00	32	0
28+50.00	32	0
29+00.00	34	0
29+18.17	7	0

Station L Phase II main line	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+50.00	0	0
15+00.00	19	0
15+50.00	38	0
16+00.00	45	0
16+50.00	59	0
17+00.00	64	0
17+50.00	64	0
18+00.00	64	0
18+50.00	86	0
19+00.00	138	3
22+00.00	75	2
22+50.00	71	6
23+00.00	62	7
23+50.00	83	5
24+00.00	118	2
24+50.00	98	0
25+00.00	73	0
25+50.00	66	0
26+00.00	58	0
26+50.00	50	0
27+00.00	23	0