

Volumes in Cubic Meters

PROJECT R-2568B COUNTY DAVIDSON

DATE 5/20/2004

COMPILED BY: FMY

SHEET 1 OF 3 SHEETS

STATION	STATION	EXCAVATION					EMBANKMENT				BORROW	WASTE					
		TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK	EARTH	EMBANK. (+) 20%		ROCK	SUITABLE	UNSUIT.	TOTAL		
-L-																	
23+20.000	32+20.000	199330				199330	41391		41391	49669				149661			149661
-Y-																	
10+14.200	13+20.000	2921				2921	11292		11292	13550	10629						
-Y1-																	
10+03.600	11+60.000	1125				1125	285		285	342				783			783
SUBTOTAL 1		203376				203376	52968		52968	63561	10629			150444			150444
-L-																	
32+20.000	41+20.000	77251				77251	67569		67569	81083	3832						
-Y9-																	
11+20.000	12+23.870	450				450	497		497	596	146						
12+57.184	13+40.000	62				62	112		112	134	72						
SUBTOTAL 2		77763				77763	68178		68178	81813	4050						
-L-																	
41+20.000	50+20.000	52459				52459	129377		129377	155252	102793						
SUBTOTAL 3		52459				52459	129377		129377	155252	102793						
-L-																	
50+20.000	59+20.000	115107				115107	110412		110412	132494	17387						
-Y10-																	
10+14.200	11+80.000	1921				1921	4753		4753	5704	3783						
-Y10A-																	
10+03.300	11+20.000	584				584	5783		5783	6940	6356						
SUBTOTAL 4		117612				117612	120948		120948	145138	27526						
-L-																	
59+20.000	61+04.888	14986				14986	15088		15088	18106	3120						
SUBTOTAL 5		14986				14986	15088		15088	18106	3120						
SHEET 1 TOTAL:		466196				466196	386559		386559	463870	148118			150444			150444