



PROJ. REFERENCE NO.	SHEET NO.
R-2568B	TCP-02B

# TEMPORARY PM SCHEDULE

Pavement Marking Schedule  
TIP Project # R-2568B

SYMBOL	DESCRIPTION		PAY ITEM QUANTITY BREAKDOWN		TOTAL QUANTITY
TEMPORARY PAVEMENT MARKINGS REMOVABLE TAPE (100MM)					
RA	WHITE EDGELINE		443	M	
RD	0.5 M. WHITE MINISKIP		23	M	
RE	WHITE SOLID LANE LINE		362	M	
RI	YELLOW DOUBLE CENTER		862	M	
			TOTAL		1690 M
REMOVABLE TAPE PAVEMENT MARKING SYMBOLS					
SA	LEFT TURN ARROW		4	EA	
SC	STRAIGHT ARROW		9	EA	
			TOTAL		13 EA
PAINT (100MM)					
PA	WHITE EDGELINE (2X)		39726	M	
PC	3 M. WHITE SKIP (2X)		50	M	
PD	0.5 M. WHITE MINISKIP (2X)		142	M	
PE	WHITE SOLID LANE LINE (2X)		812	M	
PI	YELLOW DOUBLE CENTER (2X)		42652	M	
			TOTAL		83382 M
PAINT (200MM)					
PV	YELLOW DIAGONAL (2X)		160	M	
			TOTAL		160 M
PAINT (600MM)					
P4	WHITE STOPBAR (2X)		188	M	
			TOTAL		188 M
PAINT MARKING CHARACTERS					
QI	ALPHANUMERIC CHAR. (2X)		96	EA	
			TOTAL		96 EA
PAINT MARKING SYMBOLS					
QA	LEFT TURN ARROW (2X)		28	EA	
QB	RIGHT TURN ARROW (2X)		28	EA	

Pavement Marking Schedule  
TIP Project # R-2568B

SYMBOL	DESCRIPTION		PAY ITEM QUANTITY BREAKDOWN		TOTAL QUANTITY
MARKERS TEMPORARY RAISED PAVEMENT MARKERS					
QC	STRAIGHT ARROW (2X)		10	EA	
QD	COMBO. STRAIGHT/LEFT (2X)		12	EA	
QE	COMBO. STRAIGHT/RIGHT (2X)		20	EA	
QF	COMBO. LEFT/RIGHT (2X)		10	EA	
QG	LEFT/RIGHT/STRAIGHT (2X)		8	EA	
			TOTAL		116 EA
MARKERS					
MH	YELLOW & YELLOW		482	EA	
			TOTAL		482 EA

01-SEP-2004 12:41  
M:\TCP\PHASE0\_TCP02\_02B\_TEMP\_PM.dgn  
SJS/Kes AT TETC096813

APPROVED:	DATE: 9/1/04	<b>TEMPORARY PAVEMENT MARKINGS</b>									
	SCALE: NONE										
	DATE: 02/03										
	DWG. BY: SJS										
	DESIGN BY: SJS										
REVIEWED BY: CLM		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">REVISIONS</th> </tr> <tr> <td style="width: 50%;"> </td> <td style="width: 50%;"> </td> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> </table>		REVISIONS							
REVISIONS											