

County: Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-M	200	CLEARING & GRUBBING ... HEC-TARE(S)	Lump Sum	L.S.	
0004	0008000000-M	200	SUPPLEMENTARY CLEARING & GRUB-BING	1.6 HA		
0005	0015000000-N	205	SEALING ABANDONED WELLS	6 EA		
0006	0022000000-M	225	UNCLASSIFIED EXCAVATION	590,000 M3		
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (61+30.523 NBL)	Lump Sum	L.S.	
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (61+32.478 SBL)	Lump Sum	L.S.	
0009	0036000000-M	225	UNDERCUT EXCAVATION	8,000 M3		
0010	0080000000-M	SP	CLASS IV SUBGRADE STABILIZA-TION	2,000 MTN		
0011	0106000000-M	230	BORROW EXCAVATION	36,000 M3		
0012	0134000000-M	240	DRAINAGE DITCH EXCAVATION	4,550 M3		
0013	0141000000-M	240	BERM DITCH CONSTRUCTION	730 M		
0014	0156000000-M	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	28,500 M2		
0015	0192000000-N	260	PROOF ROLLING	35 HR		
0016	0195000000-M	265	SELECT GRANULAR MATERIAL	500 M3		
0017	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	200 M2		
0018	0318000000-M	300	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRS	1,400 MTN		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0343000000-M	310	375MM SIDE DRAIN PIPE	261.6 M		
0020	0344000000-M	310	450MM SIDE DRAIN PIPE	13.2 M		
0021	0345000000-M	310	600MM SIDE DRAIN PIPE	8.4 M		
0022	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	1,790.4 M		
0023	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	344.4 M		
0024	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	536.4 M		
0025	0384000000-M	310	750MM RC PIPE CULVERTS, CLASS III	319.2 M		
0026	0390000000-M	310	900MM RC PIPE CULVERTS, CLASS III	8.4 M		
0027	0396000000-M	310	1050MM RC PIPE CULVERTS, CLASS III	103.2 M		
0028	0408000000-M	310	1350MM RC PIPE CULVERTS, CLASS III	25.2 M		
0029	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (1200MM)	188.4 M		
0030	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (1650MM)	81.6 M		
0031	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (750MM)	168 M		
0032	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (900MM)	206.4 M		
0033	0708000000-M	310	400MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK	356.4 M		
0034	0714000000-M	310	450MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK	60 M		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	0720000000-M	310	600MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK	64.8 M		
0036	0726000000-M	310	800MM BIT COAT CS PIPE CULVERTS, TYPE B 2.01MM THICK	30 M		
0037	0806000000-M	310	400MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	22 EA		
0038	0808000000-M	310	600MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	2 EA		
0039	0980000000-M	SP	****MM WELDED STEEL PIPE, ****MM THICK, GRADE B, INSTALLED BY BORING & JACKING (600MM, 12.7MM)	25.2 M		
0040	0995000000-M	340	PIPE REMOVAL	591.1 M		
0041	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0042	1044000000-M	501	LIME TREATED SOIL (SLURRY METHOD)	42,875 M2		
0043	1066000000-M	501	LIME FOR LIME TREATED SOIL	500 MTN		
0044	1110000000-M	510	STABILIZER AGGREGATE	750 MTN		
0045	1121000000-M	520	AGGREGATE BASE COURSE	2,600 MTN		
0046	1176000000-M	542	***MM SOIL CEMENT BASE (180MM)	79,625 M2		
0047	1187000000-M	542	PORTLAND CEMENT FOR SOIL CEMENT BASE	2,400 MTN		
0048	1198000000-M	SP	AGGREGATE FOR SOIL CEMENT BASE	550 MTN		
0049	1209000000-M	543	ASPHALT CURING SEAL	83,500 L		
0050	1220000000-M	545	INCIDENTAL STONE BASE	1,000 MTN		
0051	1275000000-M	600	PRIME COAT	9,350 L		
0052	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,000 MTN		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	30,900	MTN	
0054	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	800	MTN	
0055	1503000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	26,100	MTN	
0056	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,800	MTN	
0057	1523000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	25,500	MTN	
0058	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3,000	MTN	
0059	1565000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,530	MTN	
0060	1693000000-M	654	ASPHALT PLANT MIX PAVEMENT REPAIR	10	MTN	
0061	1840000000-M	665	MILLED RUMBLE STRIPS	19,600	M	
0062	2000000000-N	806	RIGHT OF WAY MARKERS	195	EA	
0063	2022000000-M	815	SUBDRAIN EXCAVATION	170	M3	
0064	2033000000-M	815	SUBDRAIN FINE AGGREGATE	90	M3	
0065	2044000000-M	815	150MM PERFORATED SUBDRAIN PIPE	200	M	
0066	2055000000-M	815	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS	20	EA	
0067	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2	EA	
0068	2077000000-M	815	150MM OUTLET PIPE (SUBDRAINS)	4	M	
0069	2143000000-M	818	BLOTTING SAND	20	MTN	
0070	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	4	EA	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	2209000000-M	838	ENDWALLS	17.8 M3		
0072	2220000000-M	838	REINFORCED ENDWALLS	3.8 M3		
0073	2253000000-M	840	PIPE COLLARS	1.79 M3		
0074	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	99 EA		
0075	2297000000-M	840	MASONRY DRAINAGE STRUCTURES	15 M3		
0076	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	20 M		
0077	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	3 EA		
0078	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	85 EA		
0079	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
0080	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4 EA		
0081	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	3 EA		
0082	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0083	2516000000-M	SP	SELECT GRANULAR MATERIAL FOR TEMPORARY FABRIC WALL	3,000 M3		
0084	2517000000-M	SP	FABRIC FOR TEMPORARY FABRIC WALL	10,000 M2		
0085	2549000000-M	846	750MM CONCRETE CURB & GUTTER	430 M		
0086	2556000000-M	846	SHOULDER BERM GUTTER	790 M		
0087	2612000000-M	848	150MM CONCRETE DRIVEWAY	33 M2		
0088	2619000000-M	850	100MM CONCRETE PAVED DITCH	100 M2		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	2647000000-M	852	125MM MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	640 M2		
0090	2655000000-M	852	125MM MONOLITHIC CONCRETE ISLANDS (KEYED IN)	800 M2		
0091	2938000000-N	SP	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE COVER	1 EA		
0092	3030000000-M	862	STEEL BM GUARDRAIL	3,844.29 M		
0093	3045000000-M	862	STEEL BM GUARDRAIL, SHOP CURVED	190.5 M		
0094	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	8 EA		
0095	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	15 EA		
0096	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0097	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	25 EA		
0098	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8 EA		
0099	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	38 EA		
0100	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	4 EA		
0101	3360000000-M	863	REMOVE EXISTING GUARDRAIL	250 M		
0102	3380000000-M	862	TEMPORARY STEEL BM GUARDRAIL	26.67 M		
0103	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	3 EA		
0104	3503000000-M	866	WOVEN WIRE FENCE, 1200MM FABRIC	10,500 M		
0105	3509000000-M	866	100MM TIMBER FENCE POSTS, 2.30M LONG	2,050 EA		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	3515000000-M	866	125MM TIMBER FENCE POSTS, 2.50M LONG	775 EA		
0107	3536000000-M	866	CHAIN LINK FENCE, 1200MM FABRIC	370 M		
0108	3542000000-M	866	METAL LINE POSTS FOR 1200MM CHAIN LINK FENCE	75 EA		
0109	3548000000-M	866	METAL TERMINAL POSTS FOR 1200MM CHAIN LINK FENCE	5 EA		
0110	3557000000-M	866	ADDITIONAL BARBED WIRE	300 M		
0111	3595000000-M	869	RELAPPING GUARDRAIL	99.06 M		
0112	3628000000-M	876	PLAIN RIP RAP, CLASS I	1,000 MTN		
0113	3635000000-M	876	PLAIN RIP RAP, CLASS II	30 MTN		
0114	3642000000-M	876	PLAIN RIP RAP, CLASS A	360 MTN		
0115	3649000000-M	876	PLAIN RIP RAP, CLASS B	1,810 MTN		
0116	3651000000-M	SP	BOULDERS	30 MTN		
0117	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	10,420 M2		
0118	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	8 EA		
0119	3691000000-N	SP	GENERIC EROSION CONTROL ITEM PREFORMED SCOUR HOLE	1 EA		
0120	4072000000-M	903	SUPPORTS, 4.5KG STEEL U-CHANNEL	1,008 M		
0121	4096000000-N	904	SIGN ERECTION, TYPE D	3 EA		
0122	4102000000-N	904	SIGN ERECTION, TYPE E	190 EA		
0123	4108000000-N	904	SIGN ERECTION, TYPE F	2 EA		
0124	4129000000-N	906	RELOCATE SIGN, TYPE ***** (D)	2 EA		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0125	4129000000-N	906	RELOCATE SIGN, TYPE ***** (E)	1 EA		
0126	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	67 EA		
0127	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	3 EA		
0128	4400000000-M	1110	WORK ZONE SIGNS (STATIONARY)	36 M2		
0129	4405000000-M	1110	WORK ZONE SIGNS (PORTABLE)	27 M2		
0130	4410000000-M	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	16 M2		
0131	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	1 EA		
0132	4420000000-N	1120	CHANGEABLE MESSAGE SIGNS	7 EA		
0133	4425000000-N	1125	WARNING FLAG SETS	10 EA		
0134	4430000000-N	1130	DRUMS	343 EA		
0135	4435000000-N	1135	CONES	343 EA		
0136	4445000000-M	1145	BARRICADES (TYPE III)	500 M		
0137	4455000000-N	1150	FLAGGER	500 MD		
0138	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	5 EA		
0139	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	5 EA		
0140	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	2 EA		
0141	4485000000-M	1170	PORTABLE CONCRETE BARRIER	978 M		
0142	4500000000-M	1170	RESET PORTABLE CONCRETE BAR- RIER	802 M		
0143	4510000000-N	SP	POLICE	24 HR		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0144	4615000000-M	1205	REMOVABLE TAPE PAVEMENT MARKING LINES (100MM)	1,690 M		
0145	4645000000-N	1205	REMOVABLE TAPE PAVEMENT MARKING SYMBOL	13 EA		
0146	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	482 EA		
0147	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	24,068 M		
0148	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	9,736 M		
0149	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	1,327 M		
0150	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	134 M		
0151	4721000000-M	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (3.1MM)	18 EA		
0152	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	116 EA		
0153	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	83,382 M		
0154	4820000000-M	1205	PAINT PAVEMENT MARKING LINES (200MM)	160 M		
0155	4835000000-M	1205	PAINT PAVEMENT MARKING LINES (600MM)	188 M		
0156	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	96 EA		
0157	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	116 EA		
0158	4850000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (100MM)	1,112 M		
0159	4860000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (200MM)	2,710 M		
0160	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	19 EA		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0161	4905000000-N	1253	SNOWPLOWABLE RAISED PAVEMENT MARKERS	1,286	EA	
0162	5300000000-M	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	594	MTN	
0163	5306000000-M	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	594	MTN	
0164	5318000000-M	1505	PAVEMENT REPAIR FOR UTILITY WORK	6	MTN	
0165	5360000000-M	1510	150MM DI WATER PIPE, PC 2.41MPA	35	M	
0166	5366000000-M	1510	200MM DI WATER PIPE, PC 2.41MPA	2,260	M	
0167	5414000000-M	1510	20MM COPPER WATER PIPE, TYPE K	305	M	
0168	5426000000-M	1510	***MM PVC WATER PIPE, SDR **** (50MM, 17, 1.72MPA WP)	90	M	
0169	5426000000-M	1510	***MM PVC WATER PIPE, SDR **** (75MM, 17, 1.72MPA WP)	452	M	
0170	5444000000-M	1510	150MM PVC WATER PIPE, SDR 21, 1.38MPA WP	798	M	
0171	5480000000-M	1510	DUCTILE IRON WATER PIPE FITTINGS, 1.72MPA MIN WP	3,043	KG	
0172	5510000000-M	1510	20MM CORPORATION STOP	26	EA	
0173	5534000000-M	1510	***MM GATE VALVE & VALVE BOX, ****MPA WP (50MM, 1.38MPA WP)	4	EA	
0174	5534000000-M	1510	***MM GATE VALVE & VALVE BOX, ****MPA WP (75MM, 1.38MPA WP)	1	EA	
0175	5540000000-M	1510	150MM GATE VALVE & VALVE BOX, 1.38MPA WP	10	EA	
0176	5546000000-M	1510	200MM GATE VALVE & VALVE BOX, ****MPA WP (1.38MPA)	12	EA	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0177	5582000000-M	1510	*** X ***MM TAPPING SADDLE (150MM X 20MM)	9 EA		
0178	5582000000-M	1510	*** X ***MM TAPPING SADDLE (150MM X 50MM)	2 EA		
0179	5582000000-M	1510	*** X ***MM TAPPING SADDLE (200MM X 20MM)	12 EA		
0180	5582000000-M	1510	*** X ***MM TAPPING SADDLE (200MM X 50MM)	2 EA		
0181	5582000000-M	1510	*** X ***MM TAPPING SADDLE (50MM X 20MM)	1 EA		
0182	5582000000-M	1510	*** X ***MM TAPPING SADDLE (75MM X 20MM)	3 EA		
0183	5582000000-M	1510	*** X ***MM TAPPING SADDLE (75MM, 50MM)	1 EA		
0184	5606000000-M	SP	50MM BLOW OFF ASSEMBLY	1 EA		
0185	5624000000-M	1510	200MM TRANSITION COUPLING, ***** (DI TO AC)	2 EA		
0186	5648000000-N	1510	RELOCATE EXISTING WATER METER	28 EA		
0187	5654000000-M	SP	RELOCATE EXISTING ***MM WATER METER & METER VAULT (50MM)	2 EA		
0188	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	4 EA		
0189	5708000000-M	1520	***MM PVC FORCE MAIN SEWER PIPE, ***** (150MM, SDR 21, 1.38MPA WP)	32 M		
0190	5756000000-M	1520	DUCTILE IRON SEWER PIPE FIT- TINGS, 1.72MPA MIN WP	300 KG		
0191	5798000000-M	1530	FILL OR REMOVE ABANDONED ***MM PIPE, ***** (150MM, PVC FORCE MAIN)	31 M		
0192	5798000000-M	1530	FILL OR REMOVE ABANDONED ***MM PIPE, ***** (200MM, AC WATER)	224 M		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0193	5798000000-M	1530	FILL OR REMOVE ABANDONED ***MM PIPE, ***** (200MM, PVC WATER)	132 M		
0194	5882000000-N	SP	GENERIC UTILITY ITEM REMOVE EXT WATER METER	3 EA		
0195	5888000000-M	SP	GENERIC UTILITY ITEM 200MM DI RJ WATER PIPE, PC 2.41MPA WP, BY TRENCHLESS METHOD	96 M		
0196	6000000000-M	1605	TEMPORARY SILT FENCE	2,685 M		
0197	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	725 MTN		
0198	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	8,870 MTN		
0199	6012000000-M	1610	SEDIMENT CONTROL STONE	4,145 MTN		
0200	6015000000-M	1615	TEMPORARY MULCHING	45 HA		
0201	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	1,775 KG		
0202	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	14.5 MTN		
0203	6024000000-M	1622	TEMPORARY SLOPE DRAINS	335 M		
0204	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	28 EA		
0205	6030000000-M	1630	SILT EXCAVATION	89,790 M3		
0206	6036000000-M	1631	MATTING FOR EROSION CONTROL	16,960 M2		
0207	6042000000-M	1632	6.4MM HARDWARE CLOTH	890 M		
0208	6069000000-M	1638	STILLING BASINS	40 M3		
0209	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
0210	6084000000-M	1660	SEEDING & MULCHING	42.5 HA		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0211	6087000000-M	1660	MOWING	25.5 HA		
0212	6090000000-M	1661	SEED FOR REPAIR SEEDING	550 KG		
0213	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	2 MTN		
0214	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	1,200 KG		
0215	6108000000-M	1665	FERTILIZER TOPDRESSING	71 MTN		
0216	6109000000-M	SP	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BLEUGRASS)	0.6 HA		
0217	6111000000-M	SP	IMPERVIOUS DIKE	15 M		
0218	6114000000-N	SP	SPECIALIZED HAND MOWING	31.5 HR		
0219	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	20 EA		
0220	6118000000-N	SP	ROOTWADS	5 EA		
0221	6120000000-M	SP	CULVERT DIVERSION CHANNEL	220 M3		
0222	6123000000-M	1670	REFORESTATION	5 HA		
0223	6126000000-M	SP	STREAMBANK REFORESTATION	0.4 HA		
0224	6147000000-M	SP	GENERIC EROSION CONTROL ITEM SAFETY FENCE	3,160 M		
0225	7060000000-M	1705	SIGNAL CABLE	760 M		
0226	7120000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	25 EA		
0227	7132000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 4 SECTION)	1 EA		
0228	7144000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 5 SECTION)	2 EA		
0229	7264000000-M	1710	MESSENGER CABLE (9.52MM)	490 M		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0230	7300000000-M	1715	TRENCHING (UNPAVED)	855 M		
0231	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	18 EA		
0232	7360000000-N	1720	WOOD POLE	10 EA		
0233	7372000000-N	1721	GUY ASSEMBLY	20 EA		
0234	7408000000-M	1722	25MM RISER WITH WEATHERHEAD	3 EA		
0235	7420000000-M	1722	50MM RISER WITH WEATHERHEAD	11 EA		
0236	7444000000-M	1725	INDUCTIVE LOOP SAWCUT	1,210 M		
0237	7456000000-M	1726	LEAD-IN CABLE	1,670 M		
0238	7636000000-N	1745	SIGN FOR SIGNALS	4 EA		
0239	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2 EA		
0240	7688000000-N	SP	CABINET BASE ADAPTER	2 EA		
0241	7708000000-N	SP	DETECTOR CARD (*****) (TYPE 2070L)	18 EA		
0242	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2 EA		
0243	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
CULVERT ITEMS						
0244	8126000000-N	414	CULVERT EXCAVATION, STA ***** (46+85.000 -L)	Lump Sum	L.S.	
0245	8133000000-M	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	177 MTN		
0246	8196000000-M	420	CLASS A CONCRETE (CULVERT)	280.2 M3		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0247	824500000-M	425	REINFORCING STEEL (CULVERT)	28,358 KG		
STRUCTURE ITEMS						
0248	801700000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (61+31.500 -L- LT LN)	Lump Sum	L.S.	
0249	801700000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (61+31.500 -L- RT LN)	Lump Sum	L.S.	
0250	803500000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (61+31.500 -L- LT LN)	Lump Sum	L.S.	
0251	810556000-M	SP	1220MM DIA DRILLED PIERS IN SOIL	26.9 M		
0252	810566000-M	SP	1220MM DIA DRILLED PIERS NOT IN SOIL	14.5 M		
0253	811160000-M	SP	PERMANENT STEEL CASING FOR 1220MM DRILLED PIER	17.4 M		
0254	811500000-N	SP	CROSSHOLE SONIC LOGGING	4 EA		
0255	811600000-M	SP	CSL TUBES	183.6 M		
0256	811900000-M	412	UNCLASSIFIED STRUCTURE EXCAVA- TION (61+31.500 -L- LT LN)	990 M3		
0257	812100000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (61+31.500 -L- RT LN)	Lump Sum	L.S.	
0258	814700000-M	420	REINFORCED CONCRETE DECK SLAB	1,212 M2		
0259	816100000-M	420	GROOVING BRIDGE FLOORS	1,012.6 M2		
0260	818200000-M	420	CLASS A CONCRETE (BRIDGE)	134.9 M3		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0261	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (61+31.500 -L- LT LN)	Lump Sum	L.S.	
0262	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (61+31.500 -L- RT LN)	Lump Sum	L.S.	
0263	821700000-M	425	REINFORCING STEEL (BRIDGE)	16,605 KG		
0264	823800000-M	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,235 KG		
0265	826500000-M	430	1372MM PRESTRESSED CONCRETE GIRDERS	407.04 M		
0266	836400000-M	450	HP310X79 STEEL PILES	280 M		
0267	850300000-M	460	CONCRETE BARRIER RAIL	205.456 M		
0268	860800000-M	876	PLAIN RIP RAP CLASS II (600MM THICK)	1,025 MTN		
0269	862200000-M	876	FILTER FABRIC FOR DRAINAGE	1,048 M2		
0270	865700000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0271	869200000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1117/Oct01/Q1396184.406/D1135160420000/E271

Total Amount Of Bid For Entire Project :

C201069
DAVIDSON COUNTY

2/16/99

Contract No: C201069

County: Davidson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General