

## PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	BREAKDOWN		TOTAL		SYMBOL	DESCRIPTION	BREAKDOWN		TOTAL		
<b>FINAL PAVEMENT MARKINGS</b>						<b>TEMPORARY PAVEMENT MARKINGS</b>						
TA	THERMOPLASTIC (4", 90 MILS) WHITE EDGELINE	5400	LF			PA	PAINT (4") WHITE EDGELINE	52000	LF			
				TOTAL	5400	LF	PB	YELLOW EDGELINE	8400	LF		
TC	THERMOPLASTIC (4", 120 MILS) 10 FT. WHITE SKIP	2100	LF			PD	2 FT. WHITE MINISKIP	970	LF			
TD	2 FT. WHITE MINISKIP	270	LF			PE	WHITE SOLID LANE LINE	3750	LF			
TE	WHITE SOLID LANE LINE	2750	LF			PI	YELLOW DOUBLE CENTER	44,400	LF			
TI	YELLOW DOUBLE CENTER	1540	LF							TOTAL	109,520	LF
				TOTAL	6660	LF						
TT	THERMOPLASTIC (8", 90 MILS) YELLOW DIAGONAL	30	LF			PQ	PAINT (8") WHITE EDGELINE	480	LF			
				TOTAL	30	LF				TOTAL	480	LF
TV	THERMOPLASTIC (8", 120 MILS) WHITE CROSSWALK LINE	746	LF			P4	PAINT (24") WHITE STOPBAR	1484	LF			
				TOTAL	746	LF				TOTAL	1484	LF
T2	THERMOPLASTIC (24", 120 MILS) WHITE STOPBAR	550	LF			<b>PAINT MARKING SYMBOLS</b>						
				TOTAL	550	LF	QA	LEFT TURN ARROW	42	EA		
UA	THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS) LEFT TURN ARROW	28	EA			QB	RIGHT TURN ARROW	10	EA			
UB	RIGHT TURN ARROW	9	EA			QC	STRAIGHT ARROW	20	EA			
UC	STRAIGHT ARROW	32	EA			QE	COMBO. STRAIGHT/RIGHT	30	EA			
UE	COMBO. STRAIGHT/RIGHT	14	EA							TOTAL	102	EA
				TOTAL	83	EA	<b>MARKERS</b>					
MA	PERMANENT RAISED PAVEMENT MARKERS YELLOW & YELLOW	20	EA			<b>TEMPORARY RAISED PAVEMENT MARKERS</b>						
MB	CRYSTAL & RED	348	EA			MH	YELLOW & YELLOW	308	EA			
				TOTAL	368	EA	MI	CRYSTAL & RED	94	EA		
										TOTAL	402	EA
						<b>REMOVABLE TAPE (4")</b>						
						RA	WHITE EDGELINE	1500	LF			
										TOTAL	1500	LF

07-SEP-2004 16:40  
 F:\TCP\2904\_TC\_PMI.dgn  
 jmmahr:iquez AT TETC09/41

APPROVED:	DATE: 7 SEP 04	<b>PAVEMENT MARKING SCHEDULE</b>	
SEAL 	SCALE: NONE		<b>REVISIONS</b>
	DATE: 09-04		
	DWG. BY: MRM		
	DESIGN BY: MRM		
	REVIEWED BY: JWG		