

U-2408

**Project Special Provisions
Erosion Control**

Gaston County

Seeding And Mulching

(6)

The kinds of seed and fertilizer, and the rates of application of seed, fertilizer, and limestone, shall be as stated below. During periods of overlapping dates, the kind of seed to be used shall be determined by the Engineer. All rates are in pounds per acre (kilograms per hectare).

August 1 - June 1

100# (110kg) Tall Fescue
 15# (17kg) Kentucky Bluegrass
 15# (17kg) Hard Fescue
 500# (560kg) Fertilizer
 4000# (4500kg) Limestone

May 1 - September 1

100# (110kg) Tall Fescue
 15# (17kg) Kentucky Bluegrass
 15# (17kg) Hard Fescue
 25# (28kg) Kobe or Korean Lespedeza
 500# (560kg) Fertilizer
 4000# (4500kg) Limestone

Approved Tall Fescue Cultivars:

Adventure	Adventure II	Amigo	Anthem
Apache	Apache II	Arid	Austin
Brookstone	Bonanza	Bonanza II	Chapel Hill
Chesapeake	Chieftain	Coronado	Crossfire II
Debutante	Duster	Falcon	Falcon II
Finelawn Petite	Finelawn	Finelawn I	Genesis
Grande	Guardian	Houndog	Jaguar
Jaguar III	Kentucky 31	Kitty Hawk	Monarch
Montauk	Mustang	Olympic	Pacer
Phoenix	Pixie	Pyramid	Rebel
Rebel Jr.	Rebel II	Renegade	Safari
Shenandoah	Tempo	Titan	Tomahawk
Trailblazer	Tribute	Vegas	Wolfpack
Wrangler			

Approved Kentucky Bluegrass Cultivars:

Adelphi	Baron	Bristol	Challenger
Columbia	Fylking	Glade	Kenblue
Merit	Plush	Ram I	Rugby
Sydsport	Touchdown	Vantage	

Approved Hard Fescue Cultivars:

Aurora	Bardur	Crystal	Reliant	Scaldis
--------	--------	---------	---------	---------

Spartan

Valda

Waldina

Warwick

On cut and fill slopes 2:1 or steeper add 25# (28kg) Rye Grain November 1 - March 1.

On cut and fill slopes 2:1 or steeper add 30# (35 kg) Sericea Lespedeza January 1 - December 31.

Fertilizer shall be 10-20-20 analysis. Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 1-2-2 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as a 10-20-20 analysis.

Temporary Seeding:

Fertilizer shall be the same analysis as specified for "Seeding and Mulching" and applied at the rate of 400 pounds (450kg) and seeded at the rate of 50 pounds per acre (55kg per hectare). Kobe or Korean Lespedeza, German Millet, or Browntop Millet shall be used in summer months and rye grain during the remainder of the year. The Engineer will determine the exact dates for using each kind of seed.

Fertilizer Topdressing:

Fertilizer used for topdressing shall be 16-8-8 grade and shall be applied at the rate of 500 pounds per acre (560 kg per hectare). Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 2-1-1 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as 16-8-8 analysis.

Supplemental Seeding:

The kinds of seed and proportions shall be the same as specified for "Seeding and Mulching", and the rate of application may vary from 25# to 75# per acre (28kg to 85kg per hectare). The actual rate per acre (hectare) will be determined by the Engineer prior to the time of topdressing and the Contractor will be notified in writing of the rate per acre (hectare), total quantity needed, and areas on which to apply the supplemental seed. Minimum tillage equipment, consisting of a sod seeder shall be used for incorporating seed into the soil as to prevent disturbance of existing vegetation. A clodbuster (ball and chain) may be used where degree of slope prevents the use of a sod seeder.

Mowing:

The minimum mowing height on this project shall be six inches (150 mm).

Lawn Type Appearance

All areas adjacent to lawns must be hand finished as directed by the Engineer to give a "lawn type appearance". Remove all trash, debris, and stones ¾ inch (19 mm) and larger in diameter or other obstructions that could interfere with providing a smooth "lawn type

appearance". These areas shall be reseeded to match their original vegetative conditions, unless directed otherwise by the Field Operations Engineer.

Specialized Seeding Under Guiderail and Guardrail (Hard Fescue/Bluegrass):

General:

Areas under guiderail and guardrail sections shall be seeded in accordance with these provisions and as directed by the Engineer. Perform the work covered by this provision including but not limited to litter and debris removal, mowing, disposal of weeds and other unacceptable growth, grading, soil preparation and amendment, surface smoothing, seed applications, and matting installation.

Materials:

Only approved Hard Fescue and Kentucky Bluegrass seed that complies with Section 1060 of the Standard Specifications shall be used.

Soil Preparation:

Remove litter and other debris. Mow and satisfactorily dispose of weeds or other unacceptable growth on the areas to be seeded.

Prior to seeding, all eroded, uneven and rough areas shall be contour graded and/or filled with soil as directed by the Engineer. The soil shall be scarified or otherwise loosened to a depth of not less than 5 inches (130 mm) with a minimum width of 48 inches (1145 mm) and a maximum width of 52 inches (1320 mm). Clods shall be broken and the top 2 to 3 inches (52 to 78 mm) of soil shall be worked into an acceptable soil bed by the use of soil pulverizers, drags, or harrows.

Soil amendments shall be as follows:

Limestone: Limestone shall be applied at a rate of 4000 pounds (4500 Kg/Hectare) per acre.

Fertilizer: Fertilizer shall be 10-20-20 analysis and applied at a rate of 500 pounds (560kg/Hectare) per acre.

After soil preparation, lime and fertilizer shall be uniformly distributed by mechanical means using a 48 inch (1065 mm) drop type spreader and thoroughly mixed with the top five inches (130 mm) of the soil by discing, harrowing, or other approved methods.

The area shall then be harrowed, dragged, raked, or prepared by other approved methods which will give a lawn type finish. All trash, debris and stones larger than 1-1/2 inch (38 mm) in diameter or other obstructions shall also be removed.

Application:

(Hard Fescue/Bluegrass) seed shall be uniformly distributed at a rate of 75 pounds per acre (85 kilograms per hectare) of Hard Fescue and 20 pounds per acre (28 kilograms per hectare) of Kentucky bluegrass by mechanical means.

Immediately following the placement of seed, the area shall be rolled or tamped carefully and firmly by means acceptable to the Engineer to ensure a smooth surface. Use of rubber tired equipment to roll shall not be allowed.

Matting:

Immediately upon completion of seeding work and herbicidal application, 48 inch wide matting shall be installed over the seeded area in accordance with Section 1631 of the Standard Specifications.

Basis of Payment:

The quantity of "Specialized Seeding Under Guiderail and Guardrail (Hard Fescue/Bluegrass)" to be paid for will be the actual number of acres (hectares) of guiderail and guardrail sections, measured along the surface of the ground, over which acceptable seeding has been performed. The quantity of seeding will be paid for at the contract unit price per acre (hectare) for "Specialized Seeding Under Guiderail and Guardrail (Fescue/Bluegrass)".

No payment shall be made for "Specialized Seeding Under Guiderail and Guardrail (Fescue/Bluegrass)" in which the work has not been satisfactorily completed. Complete work includes but is not limited to soil preparation, surface smoothing, seeding, and matting.

Specialized Hand Mowing:

The work covered by this section consists of specialized hand mowing around or under fixed objects, including but not limited to guardrails, signs, barriers and slopes in a method acceptable to the Engineer.

The work of specialized hand mowing shall be completed with mechanically powered trimmers, string trimmers, hand operated rotary mowers, or self-propelled mowers of sufficient size and quality to perform the work timely and efficiently.

The quantity of mowing to be performed will be affected by the actual conditions which occur during the construction of the project. The quantity of mowing may be increased, decreased or eliminated entirely at the direction of the Engineer. Such variations in quantity will not be considered as alterations in the details of construction or a change in the character of the work.

The quantity of specialized hand mowing to be paid for will be the actual number of man hours worked while hand mowing along the surface of the ground, at the direction of the Engineer. Where an area has been mowed more than once, at the direction of the Engineer, separate measurement will be made each time the area is mowed.

Payment will be made under:

Specialized Hand Mowing..... HR

Minimize Removal Of Vegetation

The Contractor shall minimize removal of vegetation at stream banks and disturbed areas within the project limits as directed by the Engineer.

Stockpile Areas

The Contractor shall install and maintain erosion control devices sufficient to contain sediment around any erodible material stockpile areas as directed by the Engineer.

Waste Areas And Borrow Sources:

Payment for temporary erosion control measures, except those made necessary by the Contractor's own negligence or for his own convenience, will be paid for at the appropriate contract unit price for the devices or measures utilized in borrow sources and waste areas.

No additional payment will be made for erosion control devices or permanent seeding and mulching in any commercial borrow or waste pit. All erosion and sediment control practices which may be required on a commercial borrow or waste site will be done at the Contractor's expense.

Temporary Diversion:

The work by this section for installation, maintenance, and cleanout of temporary diversions shall be in accordance with Section 1630. The quantity of excavation for installation and cleanout measured as provided in Article 1630-4 will be paid for at the contract unit price per cubic yard (cubic meter) as provided in Article 1630-5 for "Silt Excavation".

Safety Fence:

Description:

The work of "Safety Fence" shall consist of furnishing, installing and maintaining polyethylene or polypropylene fence along the outside riparian buffer, wetland, or water boundary located within the construction corridor to mark the areas that have been approved to infringe within the buffer, wetland or water, and as directed by the Engineer

in accordance with the special provisions included herein. The fence shall be installed prior to any land disturbing activities.

Materials:

Fence Material:

Polyethylene or polypropylene fence shall be a preconstructed safety fence approved by the Engineer.

Posts:

Either wood posts or steel posts may be used. Wood posts shall be nominal 2" x 4" (51 mm x 102 mm) or 4" x 4" (102 mm x 102 mm), lengths as required, structural light framing, grade No. 2, Southern Pine. Steel posts shall be at least 5 feet (1.6 m) in length, approximately 1 3/8" (35 mm) wide measured parallel to the fence, and have a minimum weight of 1.25 lb./ft. (1.9 kg/m) of length. The steel post shall be equipped with an anchor plate having a minimum area of 14 square inches (90 square centimeters).

Clearing and Grading:

No additional clearing and grubbing is anticipated for the installation of this fence; however, if any clearing and grubbing is required, it will be the minimum required for the installation of the safety fence. Such clearing shall include satisfactory removal and disposal of all trees, brush, stumps and other objectionable material.

The fence shall be erected to conform to the general contour of the ground. When determined necessary by the Engineer, minor grading along the fence line shall be done to meet this requirement provided no obstructions to proper drainage are created.

Installation:

Posts shall be set and maintained in a vertical position and may be hand set or set with a post driver. If hand set, all backfill material shall be thoroughly tamped. If power driven, wood posts may be sharpened to a dull point. Posts damaged by power driving shall be removed and replaced prior to final acceptance. The tops of all wood posts shall be cut at a 30 degree angle. The wood posts may, at the option of the Contractor, be cut at this angle either before or after the posts are erected.

The fence fabric shall be attached to the wood posts with one 2" (51 mm) galvanized wire staple across each cable or to the steel posts with wire or other acceptable means.

The Contractor shall be required to maintain the safety fence in a satisfactory condition for the duration of the project as determined by the Engineer.

Method of Measurement:

The quantity of safety fence to be paid for shall be the actual number of linear feet (meter) of "Safety Fence", installed in place and accepted. No direct payment will be made for post and post bracing. Cost shall be included in the cost of the fence per linear foot (meter).

Basis of Payment:

The quantity of safety fence measured as provided above will be paid for at the contract unit price per linear foot (meter) of safety fence. Such payment will be full compensation for the work as described in the above paragraphs, including but not limited to clearing and grading, furnishing and installing fence fabric with necessary posts and post bracing, staples, tie wires, tools, equipment and incidentals necessary to complete the work.

Payment will be made under:

Safety Fence.....LF (M)

Gravel Construction Entrance:

Description:

The work covered by this section consists of furnishing, installing, and maintaining and removing any and all material required for the construction of a Gravel Construction Entrance.

Materials:

The filter fabric shall meet the requirements of Section 1056 for Type 2 Fabric.

Stone shall be Class A Stone and shall meet the requirements of Section 1042 for Stone for Erosion Control, Class A.

Construction:

The Contractor shall install a Gravel Construction Entrance in accordance with the details in the plans and at locations as directed by the Engineer.

Method Of Measurement:

Gravel Construction Entrance will not be measured for payment under this section.

Basis Of Payment:

Payment for installation of Filter Fabric shall be paid for at the contract unit price per square yard (square meter) "Filter Fabric for Drainage".

Payment for installation of Class A Stone shall be paid for at the contract unit price per ton (metric ton) "Stone for Erosion Control, Class A".

Such price and payment shall be considered full compensation for all work covered by this provision including all materials, construction, maintenance, and removal of Gravel Construction Entrance as directed by the Engineer.