

| | | |
|-------------|-----------|-----------|
| PROJECT NO. | SHEET NO. | TOTAL NO. |
| 39278 | 3 | 7 |

SUMMARY OF QUANTITIES

| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LENGTH MI | WIDTH FT | INCIDENTAL STONE BASE TONS | SHOULDER RECONSTRUCTION SMI | BASE COURSE, B25.0B TONS | SURFACE COURSE, S9.5B TONS | PG 64-22 PLANT MIX TONS | MASONRY DRAINAGE STRUCTURES EA | RESIDENTIAL SEEDING AC | TRENCHING (UNPAVED) LF | PULL BOX EA | INDUCTIVE LOOP SAW CUT LF | LEAD-IN CABLE LF |
|---------------------------------|----------|--------|---------|--|-------------|-----------|------------|----------------------------|-----------------------------|--------------------------|----------------------------|-------------------------|--------------------------------|------------------------|------------------------|-------------|---------------------------|------------------|
| 39278 | Guilford | 1 | SR 1007 | RANDLEMAN ROAD - FROM SOUTH OF SR 3325 (RITTERS LAKE ROAD) TO THE RANDOLPH COUNTY LINE | 1 | 0.04 | 28 - 35 | 705 | 3.85 | | 124 | 7 | | 2.33 | | | | |
| | | | | | 1 | 0.04 | 24 - 28 | | | 49 | 119 | 9 | | | | | | |
| | | | | | 1 | 0.74 | 24 | | | 891 | 2,072 | 163 | | | | | | |
| | | | | | 1 | 0.01 | 24 - 32 | | | 12 | 32 | 2 | | | | | | |
| | | | | | 1 | 0.05 | 32 | | | | 348 | 21 | | | | | | |
| | | | | | 1 | 0.06 | 32 - 34 | | | | 195 | 12 | | | | | | |
| | | | | | 1 | 0.03 | 34 - 35 | | | | 102 | 6 | | | | | | |
| | | | | | 1 | 0.01 | 35 | | | | 55 | 3 | 1 | | | | | |
| | | | | | 1 | 0.05 | 24 - 35 | | | 60 | 165 | 12 | | | | | | |
| | | | | | 1 | 4.89 | 24 | | | 5889 | 14,175 | 1,104 | 2 | | | | | |
| TOTAL FOR PROJ NO. 39278 | | | | | 5.92 | | 705 | 3.85 | 6901 | 17,387 | 1,339 | 3 | 2.33 | 100 | 1 | 800 | 100 | |
| GRAND TOTAL | | | | | 5.92 | | 705 | 3.85 | 6901 | 17,387 | 1,339 | 3 | 2.33 | 100 | 1 | 800 | 100 | |