

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SUMMARY OF EARTHWORK

IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
-L-					
STA. 11+50 TO 16+06.17	111		164	53	
SUMMARY SUBTOTAL	111		164	53	
PROJECT TOTAL	111		164	53	
WASTE TO REPLACE BORROW					
GRAND TOTAL	111		138	53	
SAY	120			60	
DDE	350				
CONTIGENCY UNDERCUT	100				

SUMMARY OF PAVEMENT REMOVAL

LOCATION	SY'S
-L-	
STA. 14+50 TO 15+20	245.89
TOTAL	245.89
SAY	260

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, SHOULDER BORROW, FINE GRADING, CLEARING AND GRUBBING, BREAKING OF EXISTING ASPHALT PAVEMENT, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING"