


# ESTIMATE OF QUANTITIES

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201073

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+52.50)
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+60.00)
004300000-N	226	Lump Sum		GRADING
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
005700000-E	226	250	CY	UNDERCUT EXCAVATION
008000000-E	SP	1,000	TON	CLASS IV SUBGRADE STABILIZATION
013400000-E	240	15	CY	DRAINAGE DITCH EXCAVATION
019500000-E	265	700	CY	SELECT GRANULAR MATERIAL
019600000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
031800000-E	300	13	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
034300000-E	310	60	LF	15" SIDE DRAIN PIPE
070800000-E	310	60	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
080600000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
112100000-E	520	480	TON	AGGREGATE BASE COURSE
122000000-E	545	100	TON	INCIDENTAL STONE BASE
127500000-E	600	335	GAL	PRIME COAT
152500000-E	SP	145	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
156000000-E	620	10	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
202200000-E	815	115	CY	SUBDRAIN EXCAVATION
203300000-E	815	85	CY	SUBDRAIN FINE AGGREGATE
204400000-E	815	500	LF	6" PERFORATED SUBDRAIN PIPE
205500000-E	815	15	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
206600000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET

ItemNumber	Sec #	Quantity	Unit	Description
207700000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)
228600000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES
236400000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.16
255600000-E	846	12	LF	SHOULDER BERM GUTTER
257000000-N	SP	1	EA	MODIFIED CONCRETE FLUME
303000000-E	862	100	LF	STEEL BM GUARDRAIL
304500000-E	862	25	LF	STEEL BM GUARDRAIL, SHOP CURVED
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
319500000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1
321500000-N	862	8	EA	GUARDRAIL ANCHOR UNITS, TYPE III
327000000-N	SP	7	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
365600000-E	876	225	SY	FILTER FABRIC FOR DRAINAGE
365900000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
440000000-E	1110	52	SF	WORK ZONE SIGNS (STATIONARY)
440500000-E	1110	96	SF	WORK ZONE SIGNS (PORTABLE)
441000000-E	1110	36	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
443000000-N	1130	15	EA	DRUMS
443500000-N	1135	15	EA	CONES
444500000-E	1145	20	LF	BARRICADES (TYPE III)
445000000-N	1150	240	HR	FLAGGER
448500000-E	1170	120	LF	PORTABLE CONCRETE BARRIER
450000000-E	1170	60	LF	RESET PORTABLE CONCRETE BARRIER
600000000-E	1605	450	LF	TEMPORARY SILT FENCE
600600000-E	1610	125	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	200	TON	STONE FOR EROSION CONTROL, CLASS B

ItemNumber	Sec #	Quantity	Unit	Description
601200000-E	1610	60	TON	SEDIMENT CONTROL STONE
601500000-E	1615	1.5	ACR	TEMPORARY MULCHING
601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
602400000-E	1622	25	LF	TEMPORARY SLOPE DRAINS
602700000-N	1622	1	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
603000000-E	1630	200	CY	SILT EXCAVATION
603600000-E	1631	750	SY	MATTING FOR EROSION CONTROL
604200000-E	1632	20	LF	1/4" HARDWARE CLOTH
608400000-E	1660	1.5	ACR	SEEDING & MULCHING
608700000-E	1660	1	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	1.25	TON	FERTILIZER TOPDRESSING
611400000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
612300000-E	1670	0.15	ACR	REFORESTATION



**Stantec**  
Stantec Consulting Services Inc.  
Suite 300, 801 Jones Franklin Road  
Raleigh, NC 27606  
Tel. 919.851.6866  
Fax. 919.851.7024  
www.stantec.com