



CONCRETE BARRIER LOCATION DETAIL




ADVANCE WORK ZONE SIGN NOTES

- DO NOT INSTALL ADVANCE WARNING SIGNS MORE THAN 3 DAYS PRIOR TO BEGINNING OF WORK.
- SIGNS SHOWN ARE REQUIRED FOR WORK ZONES THAT WILL REMAIN IN EFFECT OVERNIGHT. FOR SHORT-TERM DAILY MAINTENANCE TYPE OPERATIONS, THIS SIGNING APPLICATION IS OPTIONAL- USE ONLY APPLICABLE ROADWAY STANDARD DRAWINGS. IF THIS SIGNING APPLICATION IS USED, SIGNS MAY BE PORTABLE MOUNTED.
- ALL SIGN SPACING DIMENSIONS ARE APPROXIMATE. FIELD ADJUST AS NECESSARY OR AS DIRECTED.
- USE 3LB STEEL U-CHANNEL POST OR 4" X 4" WOOD POST FOR ALL WORK ZONE SIGNS. 3LB STEEL U-CHANNEL POSTS MUST MEET THE REQUIREMENTS OF SECTION 1094-1(B), MAY BE GALVANIZED STEEL, OR MAY BE PAINTED GREEN BY THE POST MANUFACTURER. SQUARE STEEL TUBING POSTS HAVING EQUIVALENT STRENGTH OF THE 3LB STEEL U-CHANNEL POST ARE ALSO ACCEPTABLE FOR USE. ERECT SIGNS PER ROADWAY STANDARD DRAWING 1110.01. PAYMENT FOR WOOD POSTS, 3LB STEEL U-CHANNEL AND SQUARE STEEL TUBING POSTS WITH SIGNS WILL BE MADE ACCORDING TO STANDARD SPECIFICATION "WORK ZONE SIGNS" SECTION 1110.
- WHEN NECESSARY, USE SPLICING IN ACCORDANCE WITH ROADWAY STANDARD DRAWING 1110.01. REMOVE ENTIRE POST WHEN REMOVING SIGNS WITH SPLICED POSTS.

BRIDGE #47



SECTION A-A  
BRIDGE PHASE CONSTRUCTION



Stantec Consulting Services Inc.  
801 Jones Franklin Road, Suite 300  
Raleigh, NC 27605  
Tel. 919.851.6866  
Fax. 919.851.7024  
www.stantec.com

APPROVED: *[Signature]* DATE: 7/31/04

SEAL

TRAFFIC CONTROL PLAN PHASE I DETAIL		REVISIONS
SCALE: 1" = 50'	DATE: JULY 20, 2004	
DWG. BY: BRP	DESIGN BY: BRP	
REVIEWED BY: GSB		
		CAD FILE: ...B3667_TC_TCP_04.dgn