

County: Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	4 ACR		
0004	0015000000-N	205	SEALING ABANDONED WELLS	5 EA		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	455,000 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+02.46-Y1-)	Lump Sum	L.S.	
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (565+49.40-LT-)	Lump Sum	L.S.	
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (565+49.40-RT-)	Lump Sum	L.S.	
0009	0036000000-E	225	UNDERCUT EXCAVATION	5,000 CY		
0010	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0011	0106000000-E	230	BORROW EXCAVATION	1,400,000 CY		
0012	0134000000-E	240	DRAINAGE DITCH EXCAVATION	15,000 CY		
0013	0141000000-E	240	BERM DITCH CONSTRUCTION	2,400 LF		
0014	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	8,700 SY		
0015	0192000000-N	260	PROOF ROLLING	24 HR		
0016	0195000000-E	265	SELECT GRANULAR MATERIAL	18,000 CY		
0017	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	17,500 SY		
0018	0255000000-E	SP	GENERIC GRADING ITEM DISPOSAL OF CONTAMINATED SOIL	200 TON		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	1,500	TON	
0020	0343000000-E	310	15" SIDE DRAIN PIPE	168	LF	
0021	0354000000-E	310	**** RC PIPE CULVERTS, CLASS ***** (36", V)	308	LF	
0022	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,470	LF	
0023	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,918	LF	
0024	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,136	LF	
0025	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	946	LF	
0026	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	172	LF	
0027	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	316	LF	
0028	0448000000-E	310	**** RC PIPE CULVERTS, CLASS IV (24")	460	LF	
0029	0448000000-E	310	**** RC PIPE CULVERTS, CLASS IV (36")	488	LF	
0030	0448000000-E	310	**** RC PIPE CULVERTS, CLASS IV (42")	688	LF	
0031	0448000000-E	310	**** RC PIPE CULVERTS, CLASS IV (48")	648	LF	
0032	0570000000-E	310	6" CS PIPE CULVERTS, 0.064" THICK (SPRING BOX)	56	LF	
0033	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	1,464	LF	

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	68 LF		
0035	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	184 LF		
0036	0726000000-E	310	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	116 LF		
0037	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	28 EA		
0038	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	4 EA		
0039	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	4 EA		
0040	0809000000-E	310	30" BIT COAT CS PIPE ELBOWS, T YPE B 0.079" THICK	6 EA		
0041	0995000000-E	340	PIPE REMOVAL	692 LF		
0042	1000000000-E	462	6" SLOPE PROTECTION	500 SY		
0043	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0044	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	58,850 SY		
0045	1066000000-E	501	LIME FOR LIME TREATED SOIL	589 TON		
0046	1110000000-E	510	STABILIZER AGGREGATE	1,000 TON		
0047	1121000000-E	520	AGGREGATE BASE COURSE	45,900 TON		
0048	1176000000-E	542	*** SOIL CEMENT BASE (7")	58,850 SY		
0049	1187000000-E	542	PORTLAND CEMENT FOR SOIL CE- MENT BASE	244 TON		
0050	1198000000-E	SP	AGGREGATE FOR SOIL CEMENT BASE	736 TON		
0051	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	1275000000-E	600	PRIME COAT	1,187 GAL		
0053	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	420 TON		
0054	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	11,800 TON		
0055	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	23,700 TON		
0056	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	20,100 TON		
0057	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	1,100 TON		
0058	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,711 TON		
0059	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,206 TON		
0060	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	200 TON		
0061	1840000000-E	665	MILLED RUMBLE STRIPS	39,800 LF		
0062	2022000000-E	815	SUBDRAIN EXCAVATION	175 CY		
0063	2033000000-E	815	SUBDRAIN FINE AGGREGATE	100 CY		
0064	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0065	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0066	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0067	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0068	2099000000-E	816	SHOULDER DRAIN	400 LF		
0069	2110000000-E	816	4" SHOULDER DRAIN PIPE	400 LF		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	2121000000-E	816	4" OUTLET PIPE (SHOULDER DRAINS)	18.5	LF	
0071	2143000000-E	818	BLOTTING SAND	10	TON	
0072	2209000000-E	838	ENDWALLS	40	CY	
0073	2253000000-E	840	PIPE COLLARS	2	CY	
0074	2275000000-E	SP	FLOWABLE FILL	5	CY	
0075	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	89	EA	
0076	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	22	LF	
0077	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	21	EA	
0078	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	44	EA	
0079	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	16	EA	
0080	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2	EA	
0081	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	3	EA	
0082	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1	EA	
0083	2396000000-N	840	FRAME WITH COVER, STD 840.54	1	EA	
0084	2440000000-N	840	CONCRETE APRON FOR CATCH BASIN	6	EA	
0085	2451000000-N	840	CONCRETE APRON FOR DROP INLETS	81	EA	
0086	2535000000-E	846	***X *** CONCRETE CURB (8" X 18")	1,300	LF	
0087	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	2,500	LF	

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0088	2556000000-E	846	SHOULDER BERM GUTTER	4,550 LF		
0089	2570000000-N	SP	MODIFIED CONCRETE FLUME	2 EA		
0090	2580000000-E	846	CONCRETE VALLEY GUTTER	725 LF		
0091	2619000000-E	850	4" CONCRETE PAVED DITCH	65 SY		
0092	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,000 SY		
0093	2675000000-E	852	3" CORRUGATED CONCRETE ISLANDS	110 SY		
0094	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
0095	3030000000-E	862	STEEL BM GUARDRAIL	9,750 LF		
0096	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	20 EA		
0097	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77)	4 EA		
0098	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	7 EA		
0099	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	10 EA		
0100	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	12 EA		
0101	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	2 EA		
0102	3389400000-E	865	DOUBLE FACED CABLE GUIDERAIL	8,400 LF		
0103	3389600000-N	865	CABLE GUIDERAIL ANCHOR UNITS	12 EA		
0104	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	22,500 LF		
0105	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	1,450 EA		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	400 EA		
0107	3557000000-E	866	ADDITIONAL BARBED WIRE	22,500 LF		
0108	3628000000-E	876	PLAIN RIP RAP, CLASS I	515 TON		
0109	3649000000-E	876	PLAIN RIP RAP, CLASS B	2,600 TON		
0110	3651000000-E	SP	BOULDERS	40 TON		
0111	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	12,390 SY		
0112	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	3 EA		
0113	4048000000-E	902	REINFORCED CONCRETE SIGN FOOT- INGS	13 CY		
0114	4054000000-E	902	PLAIN CONCRETE SIGN FOOTINGS	1 CY		
0115	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	2,541 LB		
0116	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	7,169 LB		
0117	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	822 LF		
0118	4096000000-N	904	SIGN ERECTION, TYPE D	5 EA		
0119	4102000000-N	904	SIGN ERECTION, TYPE E	26 EA		
0120	4108000000-N	904	SIGN ERECTION, TYPE F	11 EA		
0121	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	11 EA		
0122	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	6 EA		
0123	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	835 SF		
0124	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	296 SF		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0125	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	220 SF		
0126	4425000000-N	1125	WARNING FLAG SETS	4 EA		
0127	4430000000-N	1130	DRUMS	275 EA		
0128	4435000000-N	1135	CONES	124 EA		
0129	4445000000-E	1145	BARRICADES (TYPE III)	284 LF		
0130	4455000000-N	1150	FLAGGER	384 MD		
0131	4520000000-N	1266	TUBULAR MARKERS (FIXED)	85 EA		
0132	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	240 EA		
0133	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	59,500 LF		
0134	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	25,668 LF		
0135	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	3,341 LF		
0136	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	653 LF		
0137	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	8 EA		
0138	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	61 EA		
0139	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES (4")	1,040 LF		
0140	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	72,607 LF		
0141	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	120 LF		
0142	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	144 LF		



County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0143	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	683	EA	
0144	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	50	TON	
0145	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	50	TON	
0146	5360000000-E	1510	6" DI WATER PIPE, PC 350	951	LF	
0147	5480000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	600	LB	
0148	5840000000-E	1540	*** STEEL ENCASEMENT PIPE, ***** THICK, BY OPEN CUT (12-3/4", 0.188")	318	LF	
0149	6000000000-E	1605	TEMPORARY SILT FENCE	27,785	LF	
0150	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	735	TON	
0151	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	21,025	TON	
0152	6012000000-E	1610	SEDIMENT CONTROL STONE	9,225	TON	
0153	6015000000-E	1615	TEMPORARY MULCHING	110	ACR	
0154	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	3,750	LB	
0155	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	15	TON	
0156	6024000000-E	1622	TEMPORARY SLOPE DRAINS	2,440	LF	
0157	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	41	EA	
0158	6029000000-E	SP	SAFETY FENCE	11,140	LF	
0159	6030000000-E	1630	SILT EXCAVATION	137,875	CY	
0160	6036000000-E	1631	MATTING FOR EROSION CONTROL	16,745	SY	

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0161	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,710 SY		
0162	6042000000-E	1632	1/4" HARDWARE CLOTH	2,930 LF		
0163	6069000000-E	1638	STILLING BASINS	440 CY		
0164	6084000000-E	1660	SEEDING & MULCHING	202.5 ACR		
0165	6087000000-E	1660	MOWING	62.5 ACR		
0166	6090000000-E	1661	SEED FOR REPAIR SEEDING	900 LB		
0167	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	2 TON		
0168	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	2,500 LB		
0169	6108000000-E	1665	FERTILIZER TOPDRESSING	151.75 TON		
0170	6109200000-E	SP	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (CENTI- PEDE)	1.85 ACR		
0171	6111000000-E	SP	IMPERVIOUS DIKE	37 LF		
0172	6114000000-N	SP	SPECIALIZED HAND MOWING	40 HR		
0173	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	36 EA		
0174	6118000000-N	SP	ROOTWADS	96 EA		
0175	6120000000-E	SP	CULVERT DIVERSION CHANNEL	1,130 CY		
0176	6123000000-E	1670	REFORESTATION	4.5 ACR		
0177	6126000000-E	SP	STREAMBANK REFORESTATION	2.11 ACR		
0178	7060000000-E	1705	SIGNAL CABLE	2,000 LF		
0179	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	15 EA		
0180	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	6 EA		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0181	7252000000-E	1710	MESSENGER CABLE (1/4")	3,050 LF		
0182	7279000000-E	1715	TRACER WIRE	370 LF		
0183	7300000000-E	1715	TRENCHING (UNPAVED)	2,190 LF		
0184	7301000000-E	SP	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 2)	1,130 LF		
0185	7302000000-E	SP	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, 1-1/4" (** CONDUIT) (4)	280 LF		
0186	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	15 EA		
0187	7336000000-N	1716	JUNCTION BOX (OVER-SIZED)	9 EA		
0188	7372000000-N	1721	GUY ASSEMBLY	3 EA		
0189	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	3 EA		
0190	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	4,740 LF		
0191	7456000000-E	1726	LEAD-IN CABLE	4,740 LF		
0192	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	4,510 LF		
0193	7552000000-N	1731	INTERCONNECT CENTER	3 EA		
0194	7564000000-N	1732	FIBER-OPTIC TRANSCEIVER	3 EA		
0195	7566000000-N	1733	DELINEATOR MARKER	8 EA		
0196	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIV- ER	1 EA		
0197	7575180000-N	SP	CABLE TRANSFER	1 EA		
0198	7588000000-N	1741	SIGNAL SUPPORT MAST ARM WITH METAL POLE	7 EA		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0199	7590000000-N	SP	DOUBLE MAST ARM WITH METAL POLE	1 EA		
0200	7613000000-N	SP	SOIL TEST	8 EA		
0201	7614000000-E	SP	DRILLED PIER FOUNDATION (*** DIA) (42")	105 LF		
0202	7614000000-E	SP	DRILLED PIER FOUNDATION (*** DIA) (48")	15 LF		
0203	7631000000-N	1744	MAST ARM WITH METAL POLE DE- SIGN	8 EA		
0204	7636000000-N	1745	SIGN FOR SIGNALS	6 EA		
0205	7684000000-N	1750	SIGNAL CABINET FOUNDATION	3 EA		
0206	7688000000-N	SP	CABINET BASE ADAPTER	3 EA		
0207	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	3 EA		
0208	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	14 EA		
0209	7960000000-N	SP	METAL POLE FOUNDATION REMOVAL	2 EA		
0210	7972000000-N	SP	METAL POLE REMOVAL	2 EA		
0211	7980000000-N	SP	GENERIC SIGNAL ITEM MODIFY CONTROLLER WITH CABINET NEMA TS-1	1 EA		
<b>CULVERT ITEMS</b>						
0212	8126000000-N	414	CULVERT EXCAVATION, STA ***** (508+40.00-L-)	Lump Sum	L.S.	
0213	8126000000-N	414	CULVERT EXCAVATION, STA ***** (532+67.00-L-)	Lump Sum	L.S.	
0214	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	645 TON		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0215	8196000000-E	420	CLASS A CONCRETE (CULVERT)	1,409.9 CY		
0216	8245000000-E	425	REINFORCING STEEL (CULVERT)	198,509 LB		
0217	8594000000-E	876	PLAIN RIP RAP CLASS B	109 TON		
<b>STRUCTURE ITEMS</b>						
0218	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 519+42.20-L-)	Lump Sum	L.S.	
0219	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	21,105 SF		
0220	8161000000-E	420	GROOVING BRIDGE FLOORS	23,550 SF		
0221	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	247.1 CY		
0222	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (519+42.20-L-)	Lump Sum	L.S.	
0223	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (565+49.40-L- LT. LANE)	Lump Sum	L.S.	
0224	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (565+49.40-L-RT. LANE)	Lump Sum	L.S.	
0225	8217000000-E	425	REINFORCING STEEL (BRIDGE)	40,652 LB		
0226	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,323 LB		
0227	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	847,300 LS		
0228	8364000000-E	450	HP12X53 STEEL PILES	3,860 LF		
0229	8503000000-E	460	CONCRETE BARRIER RAIL	1,060.4 LF		
0230	8531000000-E	462	4" SLOPE PROTECTION	1,791 SY		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0231	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0232	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0233	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0944/Oct14/Q3884503.11/D959021680000/E233			Total Amount Of Bid For Entire Project :			

C200895 (R-2417BB)  
LEE COUNTY

2/16/99

Contract No: C200895

County: Lee

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General