

10.100m 102 THREAD THREAD 102 -31**.**75mm Ø © 12mm X 127mm Ø WASHER AND HEX NUT (EACH END) 31.75mm Ø TIE ROD ASSEMBLY

(3 COMPLETE ASSEMBLIES REQUIRED)

EMBEDDED PLATE "B-1" DETAILS FOR AASHTO TYPE III GIRDER

(2 REQ'D PER GIRDER)

6mm BEVEL EDGE → |

SECTION "G"

→ 18mm BEVEL EDGE

SECTION "F" (SEE NOTES)

NOTES

ALL PRESTRESSING STRANDS SHALL BE 7-WIRE LOW-RELAXATION GRADE 270 STRANDS AND SHALL CONFORM TO AASHTO M203M EXCEPT FOR SAMPLING REQUIREMENTS WHICH SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

TIE ROD ASSEMBLY SHALL BE AASHTO M270 GRADE 250 STRUCTURAL STEEL.

ALL REINFORCING STEEL SHALL BE GRADE 420.

APPLY EPOXY PROTECTIVE COATING TO END OF GIRDER SURFACES INDICATED IN ELEVATION VIEW. FOR EPOXY PROTECTIVE COATING. SEE SPECIAL PROVISIONS.

EMBEDDED PLATE "B-1" SHALL BE GALVANIZED IN ACCORDANCE WITH THE SPECIFICATIONS. BEVEL EDGES OF PLATE "B-1" TO GIVE CLOSE FIT BUT NOT TIGHT FIT TO STEEL CASTING FORM.

ANCHOR STUDS SHALL CONFORM TO AASHTO M169 GRADES 1010 THROUGH 1020 OR APPROVED EQUAL, AND SHALL MEET THE TYPE "B" REQUIREMENTS OF SUBSECTION 7.3 OF THE ANSI/AASHTO/AWS D1.5 BRIDGE WELDING CODE.

AT ENDS OF GIRDERS TO BE EMBEDDED IN CONCRETE DIAPHRAGMS OR END WALLS, PRESTRESSING STRANDS MAY EXTEND A MAXIMUM OF 50mm BEYOND THE GIRDER ENDS. OTHERWISE, PRESTRESSING STRANDS SHALL BE CUT FLUSH WITH THE GIRDER ENDS.

DEPENDING ON THE TYPE OF SYSTEM USED TO SUPPORT THE DECK SLAB FORMS, PRESET ANCHORS MAY BE NECESSARY IN THE PRESTRESSED CONCRETE GIRDER.

THE TOP SURFACE OF THE GIRDER, EXCLUDING THE OUTSIDE 100mm, SHALL BE RAKED TO A DEPTH OF 6mm.

WHEN DRAPED STRANDS ARE DETAILED, THE LONGITUDINAL LOCATION OF THE HOLD DOWN DEVICES SHALL BE WITHIN 150mm OF THE LOCATION SHOWN AND THE CENTER OF GRAVITY OF THE GROUP OF DRAPED STRANDS SHALL BE LOCATED WITHIN 13mm OF THE THEORETICAL LOCATION SHOWN.

FOR VERTICAL CRACKS IN PRESTRESSED CONCRETE GIRDERS PRIOR TO DETENSIONING, SEE SPECIAL PROVISIONS.

FOR PRESTRESSED CONCRETE MEMBERS, SEE SPECIAL PROVISIONS.

THE TRANSFER OF LOAD FROM THE ANCHORAGES TO THE GIRDER SHALL BE DONE WHEN CONCRETE HAS REACHED A COMPRESSIVE STRENGTH OF NOT LESS THAN 31.0 MPd FOR SPANS A AND C, AND 34.5 MPd FOR SPAN B.

				_		programme and the state of the	***************************************		—DE	AD L	OAD	DEFL	ECT:	ION	TABL	E F	OR G	IRDE	RS —			
12.70mm & LOW DELAYATION		SPAN A & C								SPAN B												
12.70mm Ø LOW RELAXATION	ALL GIRDERS								ALL GIRDERS													
TENTH POINTS	0	.1	.2	.3	.4	. 5	.6	.7	.8	.9	0	0	.1	.2	.3	.4	. 5	.6	.7	.8	.9	0
CAMBER (GIRDER ALONE IN PLACE)	0.000	0.007	0.013	0.018	0.022	0.023	0.022	0.018	0.013	0.007	0.000	0.000	0.020	0.038	0.052	0.061	0.064	0.061	0.052	0.038	0.020	0.000
* DEFLECTION DUE TO SUPERIMPOSED D.L.	0.000	0.003	0.006	0.008	0.010	0.011	0.010	0.008	0.006	0.003	0.000	0.000	0.007	0.013	0.018	0.021	0.023	0.021	0.018	0.013	0.007	0.000
FINAL CAMBER	0	4	7	10	12	12	12	10	7	4	0	0	13	25	34	40	41	40	34	25	13	0

* INCLUDES FUTURE WEARING SURFACE

ALL VALUES ARE SHOWN IN METERS. EXCEPT "FINAL CAMBER" WHICH IS SHOWN IN MILLIMETERS.

PROJECT NO. R-2206C LINCOLN-CATAWBA COUNTY STATION: 256+91.000 -L-

SHEET 3 OF 3

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

STANDARD

PRESTRESSED CONCRETE GIRDER CONTINUOUS FOR LIVE LOAD DETAILS

LEFT LANE

	<u> </u>	- ' '		1 L				
	SHEET NO.							
BY:	DATE:	NO.	BY:	DATE:	S-317			
		3			TOTAL SHEETS			
		4			374			

STD. NO. PCG11SM

ASSEMBLED BY: PEGGY ADKINS DATE: 1-04 CHECKED BY: W.D. CRUTCHER DATE: 1-04 REV. 8/16/99 MAB/LES REV. 10/17/00 RWW/LES REV. 7/10/01 LES/RDR DRAWN BY: ELR 11/91 CHECKED BY: GRP 11/91