

TIP#: R-2206B  
Date:06/24/04  
Revised Date:

## TRAFFIC CONTROL DEVICES TO REMAIN ON PROJECT

### DESCRIPTION.

Furnish, install, maintain during the life of the project, and leave Traffic Control Devices on the project at its completion in accordance with the plans and specifications.

### CONSTRUCTION METHODS.

Install and leave on the project the Traffic Control Devices necessary to accommodate the traffic pattern shown on sheet TCP-9 of the Traffic Control Plan, unless otherwise directed by the Engineer.

Provide devices to remain on the project, which meet the requirements of their respective specifications in the 2002 Standard Specifications or their respective special provisions.

Provide devices to remain on the project that are in good condition and subject to the approval of the Engineer.

The devices required to remain on the project at its completion will become the property of the Department.

### BASIS OF PAYMENT.

No additional payment will be made specifically for leaving devices on the project. These devices will be paid under their respective pay items in the Contract which will include full compensation for furnishing, installing, maintaining during the life of the project, and leaving the devices on the project at its completion.