

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200964

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	3659000000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	7372000000-N	1721	8	EA	GUY ASSEMBLY
0043000000-N	226	Lump Sum		GRADING	4025000000-E	901	19	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	7408000000-E	1722	1	EA	1" RISER WITH WEATHERHEAD
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	4072000000-E	903	165	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	7420000000-E	1722	6	EA	2" RISER WITH WEATHERHEAD
0057000000-E	226	400	CY	UNDERCUT EXCAVATION	4102000000-N	904	3	EA	SIGN ERECTION, TYPE E	7444000000-E	1725	1,884	LF	INDUCTIVE LOOP SAWCUT
0134000000-E	240	200	CY	DRAINAGE DITCH EXCAVATION	4129000000-N	906	3	EA	RELOCATE SIGN, TYPE ***** (D)	7456000000-E	1726	2,590	LF	LEAD-IN CABLE
0195000000-E	265	500	CY	SELECT GRANULAR MATERIAL	4129000000-N	906	2	EA	RELOCATE SIGN, TYPE ***** (E)	7684000000-N	1750	1	EA	SIGNAL CABINET FOUNDATION
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION	4155000000-N	907	17	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	7688000000-N	SP	1	EA	CABINET BASE ADAPTER
0206000000-E	SP	425	SF	TEMPORARY SHORING - BARRIER SUPPORTED	4192000000-N	907	5	EA	DISPOSAL OF SUPPORT, U-CHANNEL	7756000000-N	1751	1	EA	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)
0343000000-E	310	160	LF	15" SIDE DRAIN PIPE	4400000000-E	1110	224	SF	WORK ZONE SIGNS (STATIONARY)	7780000000-N	SP	6	EA	DETECTOR CARD (TYPE 2070L)
0344000000-E	310	56	LF	18" SIDE DRAIN PIPE	4405000000-E	1110	48	SF	WORK ZONE SIGNS (PORTABLE)					
0378000000-E	310	72	LF	24" RC PIPE CULVERTS, CLASS III	4410000000-E	1110	42	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)					
0588000000-E	310	60	LF	18" CS PIPE CULVERTS, 0.064" THICK	4425000000-N	1125	6	EA	WARNING FLAG SETS					
0594000000-E	310	154	LF	24" CS PIPE CULVERTS, 0.064" THICK	4430000000-N	1130	20	EA	DRUMS					
0708000000-E	310	64	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	4435000000-N	1135	14	EA	CONES					
0806000000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4445000000-E	1145	72	LF	BARRICADES (TYPE III)					
0995000000-E	340	300	LF	PIPE REMOVAL	4450000000-N	1150	240	HR	FLAGGER					
1121000000-E	520	1,080	TON	AGGREGATE BASE COURSE	4465000000-N	1160	1	EA	TEMPORARY CRASH CUSHIONS					
1220000000-E	545	300	TON	INCIDENTAL STONE BASE	4485000000-E	1170	500	LF	PORTABLE CONCRETE BARRIER					
1275000000-E	600	815	GAL	PRIME COAT	4650000000-N	1251	80	EA	TEMPORARY RAISED PAVEMENT MARKERS					
1330000000-E	607	1,080	SY	INCIDENTAL MILLING	4810000000-E	1205	31,626	LF	PAINT PAVEMENT MARKING LINES (4")					
1489000000-E	610	1,010	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4820000000-E	1205	40	LF	PAINT PAVEMENT MARKING LINES (8")					
1498000000-E	610	840	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	4835000000-E	1205	312	LF	PAINT PAVEMENT MARKING LINES (24")					
1519000000-E	610	1,840	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4900000000-N	1252	80	EA	PERMANENT RAISED PAVEMENT MARKERS					
1560000000-E	620	203	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	6000000000-E	1605	870	LF	TEMPORARY SILT FENCE					
2000000000-N	806	30	EA	RIGHT OF WAY MARKERS										
2022000000-E	815	23	CY	SUBDRAIN EXCAVATION	6006000000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS A					
2033000000-E	815	17	CY	SUBDRAIN FINE AGGREGATE	6009000000-E	1610	710	TON	STONE FOR EROSION CONTROL, CLASS B					
2044000000-E	815	100	LF	6" PERFORATED SUBDRAIN PIPE	6012000000-E	1610	210	TON	SEDIMENT CONTROL STONE					
2055000000-E	815	3	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6015000000-E	1615	10	ACR	TEMPORARY MULCHING					
2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	6018000000-E	1620	350	LB	SEED FOR TEMPORARY SEEDING					
2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	6021000000-E	1620	1.5	TON	FERTILIZER FOR TEMPORARY SEEDING					
2253000000-E	840	1.1	CY	PIPE COLLARS	6024000000-E	1622	50	LF	TEMPORARY SLOPE DRAINS					
2286000000-N	840	4	EA	MASONRY DRAINAGE STRUCTURES	6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS					
2367000000-N	840	3	EA	FRAME WITH TWO GRATES, STD 840.29	6030000000-E	1630	1,450	CY	SILT EXCAVATION					
2396000000-N	840	1	EA	FRAME WITH COVER, STD 840.54	6036000000-E	1631	1,750	SY	MATting FOR EROSION CONTROL					
2529000000-E	SP	1,900	SF	GENERIC GRADING ITEM (SF) TEMPORARY FABRIC WALL	6042000000-E	1632	40	LF	1/4" HARDWARE CLOTH					
2556000000-E	846	20	LF	SHOULDER BERM GUTTER	6048000000-E	SP	55	SY	FLOATING TURBIDITY CURTAIN					
3030000000-E	862	250	LF	STEEL BM GUARDRAIL	6084000000-E	1660	10	ACR	SEEDING & MULCHING					
3045000000-E	862	75	LF	STEEL BM GUARDRAIL, SHOP CURVED	6087000000-E	1660	6	ACR	MOWING					
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	6090000000-E	1661	100	LB	SEED FOR REPAIR SEEDING					
3195000000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING					
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	6096000000-E	1662	250	LB	SEED FOR SUPPLEMENTAL SEEDING					
3270000000-N	SP	3	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6108000000-E	1665	7.25	TON	FERTILIZER TOPDRESSING					
3380000000-E	862	150	LF	TEMPORARY STEEL BM GUARDRAIL	6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING					
3387000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL					
3389100000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6123000000-E	1670	0.5	ACR	REFORESTATION					
3642000000-E	876	2	TON	PLAIN RIP RAP, CLASS A	7060000000-E	1705	670	LF	SIGNAL CABLE					
3649000000-E	876	13	TON	PLAIN RIP RAP, CLASS B	7120000000-E	1705	8	EA	VEHICLE SIGNAL HEAD (12", 3 SECTION)					
3656000000-E	876	343	SY	FILTER FABRIC FOR DRAINAGE	7264000000-E	1710	510	LF	MESSENGER CABLE (3/8")					
					7300000000-E	1715	1,180	LF	TRENCHING (UNPAVED)					
					7324000000-N	1716	7	EA	JUNCTION BOX (STANDARD SIZE)					
					7360000000-N	1720	6	EA	WOOD POLE					

5/28/99
 27-MAY-2004 10:57
 R:\Projects\B387\rdj\super-det.dgn
 jenniferevans AT