

PROJECT NO.	SHEET NO.	TOTAL NO.
5CR.10731.3, 5CR.20731.3 5CR.307322.3,	1	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	INCIDENTAL MILLING SY	LEVELING COURSE, SF9.5A TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TONS	PG 64-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	SEED & MULCHING AC
5CR.10731.3	Person	1	US 501	FROM SR 1413 (JEWELL WRENN RD) TO VA STATE LINE	1	8.08	24	646	16.16	500	250	11,722		720	400	11.72
TOTAL FOR PROJ NO. 5CR.10731.3						8.08		646	16.16	500	250	11,722		720	400	11.72
5CR.20731.3	Person	2	SR 1107 (HURDLE MILLS RD)	FROM SR 1102 (WHEELERS CHURCH RD) TO SR 1108 (BRADSHER RD)	2	2.3	18	184	4.6		15		2,274	149	25	3.33
		3	SR 1144 (TAPP RD)	FROM ROXBORO CL TO SR 1141 (DAVIS RD)	2	1.42	20	114	2.84		25		1,686	111	75	2.06
		4	SR 1534 (BURCH AVE)	ROXBORO CL TO NC 49	2	1.44	22	115	2.88		25		1,806	119	50	2.09
		5	SR 1123 (HOLLIMAN RD)	FROM ORANGE CO LINE TO BRIDGE OVER FLAT RIVER	2	1.8	20	144	3.6		20		2,094	137	25	2.61
		6	SR 1521 (MOUNTAIN RD)	FROM NC 49 TO SR 1536 (DEPOT ST)	2	2.1	18	168	4.2		75		2,081	140	125	3.05
TOTAL FOR PROJ NO. 5CR.20731.3						9.06		725	18.12	0	160		9,941	656	300	13.14
5CR.307322.3	Person	7	SR 1144 (TAPP RD)	FROM US 501 TO ROXBORO CL	2	0.26	20	80	0.52				279	18		0.38
TOTAL FOR PROJ NO. 5CR.307322.3						0.26		80	0.52	0	0		279	18		0.38
GRAND TOTAL						17.4		1451	34.8	500	410	11,722	10,220	1,394	700	25.24