

SUMMARY OF EARTHWORK IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	EMBT + %	BORROW	WASTE
-L- 12+50 - 17+15 (BEGIN BRIDGE)	4106	1530		2576
-L- 18+80 (END BRIDGE) - 25+00	9417	1210		8207
-DRIVE- 10+20 - 11+45.82	499	0		499
PROJECT TOTALS	14022	2740		11282
LOSS DUE TO CLEARING AND GRUBBING	-500			-500
GRAND TOTAL	13522	2740		10782
SAY	13600			

UNDERCUT EXCAVATION = 700 CY
 -L- PAVEMENT STRUCTURE VOLUME = 370 CY

NOTE:
 APPROXIMATE QUANTITIES ONLY. FINE GRADING,
 CLEARING AND GRUBBING, BREAKING OF EXISTING
 PAVEMENT AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID
 FOR AT THE LUMP SUM PRICE FOR "GRADING".

SUMMARY OF PAVEMENT REMOVAL IN SQUARE YARDS

LINE	STATION TO STATION	LOCATION	ASPHALT REMOVAL
-L-	15+07.500 TO 17+41.020	LT & RT	351.761
-L-	16+69.150 TO 17+71.900	LT & RT	90.773
-L-	18+29.650 TO 19+50.000	LT & RT	181.865
-L-	19+50.000 TO 24+74.700	LT & RT	933.569
		TOTAL	1557.968
		SAY	1600

SUMMARY OF SHOULDER BERM GUTTER

LINE	STATION TO STATION	LOCATION	LENGTH
-L-	15+14.00 TO 16+80.10	RT	166.10
-L-	16+91.75 TO 16+96.50	LT	4.75
-L-	19+09.76 TO 19+14.25	LT	4.49
-L-	19+09.76 TO 19+14.25	RT	4.49
		TOTAL	179.83
		SAY	190.00