



PROJ. REFERENCE NO.	SHEET NO.
R-0513A	TCP-13

Temporary Pavement Marking Schedule

SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY	BREAKDOWN	TOTAL QUANTITY
TEMPORARY PAVEMENT MARKINGS					
REMOVABLE TAPE (100MM)					
RA	WHITE EDGELINE		400	M	
					TOTAL 400 M
REMOVABLE TAPE PAVEMENT MARKING SYMBOLS					
SC	STRAIGHT ARROW		5	EA	
					TOTAL 5 EA
PAINT (100MM)					
PA	WHITE EDGELINE (1X)		55800	M	
PB	YELLOW EDGELINE (1X)		8700	M	
PC	3 M. WHITE SKIP (1X)		250	M	
PD	0.5 M. WHITE MINISKIP (1X)		150	M	
PI	YELLOW DOUBLE CENTER (1X)		49600	M	
					TOTAL 114500 M
PAINT (200MM)					
PR	WHITE GORELINE (1X)		2350	M	
PV	YELLOW DIAGONAL (1X)		150	M	
					TOTAL 2500 M
PAINT (600MM)					
P4	WHITE STOPBAR (1X)		150	M	
					TOTAL 150 M
PAINT MARKING SYMBOLS					
QA	LEFT TURN ARROW (1X)		6	EA	
QB	RIGHT TURN ARROW (1X)		6	EA	
QC	STRAIGHT ARROW (1X)		12	EA	
					TOTAL 24 EA
MARKERS					
TEMPORARY RAISED PAVEMENT MARKERS					
MH	YELLOW & YELLOW		1250	EA	
MI	CRYSTAL & RED		190	EA	
					TOTAL 1440 EA

05-OCT-2004 16:32
 W:\TCP\Phase1\R0513A_TC_Top3_PFI.dgn
 dahyes AT TETC192272

APPROVED: DATE: 10/6/04	TEMPORARY PAVEMENT MARKING SCHEDULE										
	<table border="1" style="width: 100%;"> <tr> <td style="width: 50%;">SCALE: NONE</td> <td style="width: 50%; text-align: center;">REVISIONS</td> </tr> <tr> <td>DATE: 07/03</td> <td></td> </tr> <tr> <td>DWG. BY: DAH</td> <td></td> </tr> <tr> <td>DESIGN BY: DAH</td> <td></td> </tr> <tr> <td>REVIEWED BY: JDK</td> <td></td> </tr> </table>	SCALE: NONE	REVISIONS	DATE: 07/03		DWG. BY: DAH		DESIGN BY: DAH		REVIEWED BY: JDK	
	SCALE: NONE	REVISIONS									
	DATE: 07/03										
	DWG. BY: DAH										
DESIGN BY: DAH											
REVIEWED BY: JDK											