

PROP. 381M - FILL OR REMOVE
ABANDONED 300MM PIPE, PVC WATER

ALL WATER LINES OWNED
BY ROBESON COUNTY

PROP. 341M OF 300MM PVC WATER
PIPE, SDR 21, 1.38MPA WP
1 - 300MM 22 1/2° DI BEND
CONNECT USING NECESSARY FITTINGS

PROP.
1 - REMOVE EXIST. WATER METER

PROP. 138M - FILL OR REMOVE
ABANDONED 200MM PIPE,
PVC WATER

PROP. 90M OF 200MM PVC WATER
PIPE, SDR 21, 1.38MPA WP
2 - RELOCATE EXISTING WATER METER
3M OF 20MM PE WATER TUBING,
SDR 7, 1.38MPA WP
2 - 200MM X 20MM TAPPING SADDLES
2 - 20MM CORPORATION STOPS
CONNECT USING NECESSARY FITTINGS

PROP.
1 - RELOCATE EXISTING FIRE HYDRANT
1M OF 150MM DI WATER PIPE,
PC 2.41 MPA WP
1 - 200MM X 150MM DI REDUCER
1 - 150MM GATE VALVE AND VALVE BOX,
1.38MPA WP
CONNECT USING NECESSARY FITTINGS

PAVEMENT REMOVAL

MATCHLINE SEE SHEET UC-8
-Y1- Sta. 12 + 60

MATCHLINE SEE SHEET UC-3
-L- Sta. 15 + 10

MATCHLINE SEE SHEET UC-5
-Y1- Sta. 19 + 75

6/7/2014 C:\ADDY\0513\04\0513\UC04.dwg
05/27/2014