

TIP #: R-0513A
Date: 08/13/04
Revised:

POLICE

DESCRIPTION.

The work covered by this special provision consists of furnishing police officers and marked police vehicles to direct traffic in accordance with the plans.

CONSTRUCTION METHODS.

Police officers shall be outfitted with police uniforms.

Marked police vehicles shall be equipped with police lights mounted on top of the vehicle, and police vehicle emblems.

Police officers and marked police vehicles will be required to be provided simultaneously, or separately to direct or control traffic. The plans or the Engineer will designate the locations where only police officers are required, where only marked police vehicles are required, or where they are both required to be utilized simultaneously.

METHOD OF MEASUREMENT.

The quantity of police officers and police vehicles to be paid for will be the actual number of hours that every police officer is provided to direct traffic during the life of the project as approved by the Engineer.

The Contractor will not be paid for using police officers and marked police vehicles unless prior approval for each use is obtained from the Engineer.

BASIS OF PAYMENT.

The quantity of police officers and marked police vehicles measured as provided above, will be paid for at the contract unit price per hour for "Police".

Such price and payment will be full compensation for all work covered by this provision, including but not limited to furnishing police officers, marked police vehicles, utilizing the police officers and marked police vehicles to direct traffic, and removing them when no longer needed.

Payment will be made under:

Police.....Hour.

107 B

TIP #: R-0513A
Date: 08/13/04
Revised:

TRAFFIC CONTROL DEVICES TO REMAIN ON PROJECT

DESCRIPTION.

The work covered by this special provision consists of furnishing, installing and leaving traffic control devices on the project at its completion in accordance with the plans.

CONSTRUCTION METHODS.

The Contractor shall install and leave on the project the traffic control devices necessary to accommodate the traffic pattern shown on sheet PM-2, PM-3, and PM-4 of the Traffic Control Plan, unless otherwise directed by the Engineer.

The devices remaining on the project shall meet the requirements of their respective specifications in the 2002 Standard Specifications or their respective special provisions contained elsewhere in this Contract.

All devices that are required to remain on the project at its completion shall be in good condition subject to the approval of the Engineer.

The devices required to remain on the project at its completion will become the property of the Department.

BASIS OF PAYMENT.

No additional payment will be made specifically for leaving devices on the project. These devices will be paid for under their respective pay items in the Contract which will include full compensation for furnishing, installing, maintaining during the life of the project, leaving the devices on the project at its completion, and turning over ownership of the devices to the Department.