STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200963

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
0057000000-E	226	200	CY	UNDERCUT EXCAVATION
0063000000-N	SP	Lump Sum		GRADING
0106000000-E	230	12,600	CY	BORROW EXCAVATION
0134000000-E	240	760	CY	DRAINAGE DITCH EXCAVATION
0141000000-E	240	300	LF	BERM DITCH CONSTRUCTION
0195000000-E	265	100	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	35	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0342000000-E	310	28	LF	*" SIDE DRAIN PIPE (30")
0366000000-E	310	204	LF	15" RC PIPE CULVERTS, CLASS III
0372000000-E	310	52	LF	18" RC PIPE CULVERTS, CLASS III
0708000000-E	310	36	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
1110000000-E	510	100	TON	STABILIZER AGGREGATE
1220000000-E	545	100	TON	INCIDENTAL STONE BASE
1489000000-E	610	625	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	380	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	52	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	8	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2000000000-N	806	18	EA	RIGHT OF WAY MARKERS
2286000000-N	840	4	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	4	EA	FRAME WITH TWO GRATES, STD 840.29

ItemNumber	Sec #	Quantity	Unit	Description
2556000000-E	846	435	LF	SHOULDER BERM GUTTER
3030000000-E	862	850	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3270000000-N	SP	6	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3628000000-E	876	45	TON	PLAIN RIP RAP, CLASS I
3649000000-E	876	355	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	1,190	SY	FILTER FABRIC FOR DRAINAGE
4400000000-E	1110	213	SF	WORK ZONE SIGNS (STATIONARY)
4410000000-E	1110	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4445000000-E	1145	96	LF	BARRICADES (TYPE III)
4810000000-E	1205	7,600	LF	PAINT PAVEMENT MARKING LINES (4")
4900000000-N	1252	24	EA	PERMANENT RAISED PAVEMENT MARKERS
6000000000-E	1605	725	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	355	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	155	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	1.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
6024000000-E	1622	115	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	3	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6030000000-E	1630	765	CY	SILT EXCAVATION
6036000000-E	1631	1,240	SY	MATTING FOR EROSION CONTROL
6038000000-E	SP	50	SY	PERMANENT SOIL REINFORCEMENT MAT
6042000000-E	1632	80	LF	1/4" HARDWARE CLOTH

ItemNumber	Sec #	Quantity	Unit	Description
6070000000-N	SP	2	EA	SPECIAL STILLING BASINS
6084000000-E	1660	2.5	ACR	SEEDING & MULCHING
6087000000-E	1660	1	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1.75	TON	FERTILIZER TOPDRESSING
6111000000-E	SP	235	LF	IMPERVIOUS DIKE
6114000000-N	SP	2.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
6132000000-N	SP	15	EA	GENERIC EROSION CONTROL ITEM TEMPORARY SILT DIKE

5/28/99
08-JUN-2004 08:50
R:\Proj\B3695_rdy_sum_quant.dgn
smith