3B/16

Volumes in Cubic **YARDS**

PROJECT **I-4025A** COUNTY **YADKIN/SURRY** DATE **8/4/2004** COMPILIED BY: **DCW** CHECKED BY: **SRW** SHEET 1 OF 1 SHEETS

STATION	STATION	EXCAVATION					EMBANKMENT				BORROW	WASTE		
		TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK	EARTH	EMBANK. (+) 20 %		ROCK	SUITABLE	UNSUIT.
SUMMARY NO. 1														
-SBL- 10+41.33	25+15.00	13703				13703	10860		10860	13032			671	
TOTAL SUMMARY NO. 1		13703				13703	10860		10860	13032			671	
SUMMARY NO. 2														
-SBL- 32+75.00	45+75.00	26064				26064	111		111	134			25930	
TOTAL SUMMARY NO. 2		26064				26064	111		111	134			25930	
SUB-TOTAL (SUMMARY 1 & 2)		39767				39767	10971		10971	13166			26601	
EST. LOSS DUE TO CLEAR. & GRUB.		-2500				-2500							-2500	
SUB-TOTAL		37267				37267	10971		10971	13166			24101	
PROJECT TOTALS		37267				37267	10971		10971	13166			24101	
SAY		37300												
ESTIMATED SHOULDER BORROW		1500												

UNDERCUT CONTINGENCY: 1000