

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200956

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+17.50)
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
005700000-E	226	500	CY	UNDERCUT EXCAVATION
006300000-N	SP	Lump Sum		GRADING
008000000-E	SP	500	TON	CLASS IV SUBGRADE STABILIZATION
010600000-E	230	7,100	CY	BORROW EXCAVATION
013400000-E	240	30	CY	DRAINAGE DITCH EXCAVATION
019500000-E	265	500	CY	SELECT GRANULAR MATERIAL
019600000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
031800000-E	300	50	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
034400000-E	310	24	LF	18" SIDE DRAIN PIPE
036600000-E	310	264	LF	15" RC PIPE CULVERTS, CLASS III
070800000-E	310	56	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
072000000-E	310	80	LF	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
080600000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
099500000-E	340	90	LF	PIPE REMOVAL
099600000-N	350	1	EA	PIPE CLEAN-OUT
112100000-E	520	220	TON	AGGREGATE BASE COURSE
122000000-E	545	50	TON	INCIDENTAL STONE BASE
148900000-E	610	650	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
152500000-E	SP	350	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
156000000-E	620	51	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
169300000-E	654	50	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR

ItemNumber	Sec #	Quantity	Unit	Description
200000000-N	806	18	EA	RIGHT OF WAY MARKERS
202200000-E	815	134	CY	SUBDRAIN EXCAVATION
203300000-E	815	101	CY	SUBDRAIN FINE AGGREGATE
204400000-E	815	600	LF	6" PERFORATED SUBDRAIN PIPE
205500000-E	815	18	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
206600000-N	815	2	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
207700000-E	815	12	LF	6" OUTLET PIPE (SUBDRAINS)
228600000-N	840	6	EA	MASONRY DRAINAGE STRUCTURES
236300000-N	840	4	EA	FRAME WITH TWO GRATES, STD 840.***** (840.33)
236600000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.24
255600000-E	846	60	LF	SHOULDER BERM GUTTER
303000000-E	862	700	LF	STEEL BM GUARDRAIL
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
355900000-E	866	1,740	LF	** STRAND BARBED WIRE FENCE WITH POSTS (4)
364900000-E	876	250	TON	PLAIN RIP RAP, CLASS B
365600000-E	876	1,190	SY	FILTER FABRIC FOR DRAINAGE
365900000-N	SP	3	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
440000000-E	1110	305	SF	WORK ZONE SIGNS (STATIONARY)
441000000-E	1110	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
442500000-N	1125	4	EA	WARNING FLAG SETS
443000000-N	1130	25	EA	DRUMS
443500000-N	1135	25	EA	CONES

ItemNumber	Sec #	Quantity	Unit	Description
444500000-E	1145	96	LF	BARRICADES (TYPE III)
445000000-N	1150	24	HR	FLAGGER
481000000-E	1205	9,320	LF	PAINT PAVEMENT MARKING LINES (4")
600000000-E	1605	500	LF	TEMPORARY SILT FENCE
600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	280	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	280	TON	SEDIMENT CONTROL STONE
601500000-E	1615	3	ACR	TEMPORARY MULCHING
601800000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
602400000-E	1622	90	LF	TEMPORARY SLOPE DRAINS
602700000-N	1622	4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
602900000-E	SP	250	LF	SAFETY FENCE
603000000-E	1630	795	CY	SILT EXCAVATION
603600000-E	1631	1,330	SY	MATting FOR EROSION CONTROL
603800000-E	SP	260	SY	PERMANENT SOIL REINFORCEMENT MAT
604200000-E	1632	120	LF	1/4" HARDWARE CLOTH
607000000-N	SP	8	EA	SPECIAL STILLING BASINS
608400000-E	1660	3.5	ACR	SEEDING & MULCHING
608700000-E	1660	2	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	2.5	TON	FERTILIZER TOPDRESSING
611400000-N	SP	2	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL