

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000960000-M	SP	GENERIC MISCELLANEOUS ITEM TEMPORARY FABRIC WALL	94 M2		
0004	0001000000-M	200	CLEARING & GRUBBING ... HEC- TARE(S)	Lump Sum	L.S.	
0005	0008000000-M	200	SUPPLEMENTARY CLEARING & GRUB- BING	2 HA		
0006	0022000000-M	225	UNCLASSIFIED EXCAVATION	54,000 M3		
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (178+79.50) LT	Lump Sum	L.S.	
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (178+79.50) RT	Lump Sum	L.S.	
0009	0036000000-M	225	UNDERCUT EXCAVATION	3,600 M3		
0010	0080000000-M	SP	CLASS IV SUBGRADE STABILIZA- TION	250 MTN		
0011	0106000000-M	230	BORROW EXCAVATION	94,000 M3		
0012	0134000000-M	240	DRAINAGE DITCH EXCAVATION	1,400 M3		
0013	0156000000-M	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	7,500 M2		
0014	0192000000-N	260	PROOF ROLLING	38 HR		
0015	0195000000-M	265	SELECT GRANULAR MATERIAL	15,000 M3		
0016	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	1,500 M2		
0017	0199000000-M	SP	TEMPORARY SHORING	2,600 M2		
0018	0318000000-M	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	2,500 MTN		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0343000000-M	310	375MM SIDE DRAIN PIPE	79.2 M		
0020	0344000000-M	310	450MM SIDE DRAIN PIPE	86.4 M		
0021	0345000000-M	310	600MM SIDE DRAIN PIPE	15.4 M		
0022	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	2,990.4 M		
0023	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	1,408.8 M		
0024	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	1,428 M		
0025	0384000000-M	310	750MM RC PIPE CULVERTS, CLASS III	807.6 M		
0026	0390000000-M	310	900MM RC PIPE CULVERTS, CLASS III	588 M		
0027	0396000000-M	310	1050MM RC PIPE CULVERTS, CLASS III	319.2 M		
0028	0402000000-M	310	1200MM RC PIPE CULVERTS, CLASS III	136.8 M		
0029	0453000000-M	310	***MM PIPE END SECTION (375MM)	7 EA		
0030	0453000000-M	310	***MM PIPE END SECTION (450MM)	10 EA		
0031	0456000000-M	310	****MM RC FLARED END SECT (375MM)	1 EA		
0032	0456000000-M	310	****MM RC FLARED END SECT (450MM)	4 EA		
0033	0456000000-M	310	****MM RC FLARED END SECT (750MM)	1 EA		
0034	0708000000-M	310	400MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK	36 M		
0035	0806000000-M	310	400MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	4 EA		

County: Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	0995000000-M	340	PIPE REMOVAL	871 M		
0037	0996000000-N	350	PIPE CLEAN-OUT	5 EA		
0038	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0039	1022000000-M	SP	SEALING EXISTING PAVEMENT CRACKS	3,000 KG		
0040	1110000000-M	510	STABILIZER AGGREGATE	500 MTN		
0041	1121000000-M	520	AGGREGATE BASE COURSE	1,600 MTN		
0042	1220000000-M	545	INCIDENTAL STONE BASE	1,000 MTN		
0043	1275000000-M	600	PRIME COAT	4,605 L		
0044	1330000000-M	607	INCIDENTAL MILLING	2,500 M2		
0045	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	32,610 MTN		
0046	1503000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	41,300 MTN		
0047	1523000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	38,300 MTN		
0048	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3,344 MTN		
0049	1565000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	2,298 MTN		
0050	1693000000-M	654	ASPHALT PLANT MIX PAVEMENT REPAIR	200 MTN		
0051	2000000000-N	806	RIGHT OF WAY MARKERS	182 EA		
0052	2022000000-M	815	SUBDRAIN EXCAVATION	1,242 M3		
0053	2033000000-M	815	SUBDRAIN FINE AGGREGATE	621 M3		
0054	2044000000-M	815	150MM PERFORATED SUBDRAIN PIPE	1,500 M		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	2055000000-M	815	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS	150 EA		
0056	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	10 EA		
0057	2077000000-M	815	150MM OUTLET PIPE (SUBDRAINS)	20 M		
0058	2209000000-M	838	ENDWALLS	4.6 M3		
0059	2253000000-M	840	PIPE COLLARS	2.64 M3		
0060	2264000000-M	840	PIPE PLUGS	1.19 M3		
0061	2275000000-M	SP	FLOWABLE FILL	152 M3		
0062	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	176 EA		
0063	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	20.83 M		
0064	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	2 EA		
0065	2354200000-N	840	FRAME WITH GRATE, STD 840.24	2 EA		
0066	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	169 EA		
0067	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0068	2451000000-N	840	CONCRETE APRON FOR DROP INLETS	1 EA		
0069	2535000000-M	846	*** X ***MM CONCRETE CURB (200MM X 300MM)	50 M		
0070	2549000000-M	846	750MM CONCRETE CURB & GUTTER	90 M		
0071	2556000000-M	846	SHOULDER BERM GUTTER	37 M		
0072	2570000000-N	SP	MODIFIED CONCRETE FLUME	2 EA		
0073	2591000000-M	848	100MM CONCRETE SIDEWALK	155 M2		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	2598000000-M	848	CONCRETE WHEELCHAIR RAMPS	2		
				M2		
0075	2612000000-M	848	150MM CONCRETE DRIVEWAY	40		
				M2		
0076	2655000000-M	852	125MM MONOLITHIC CONCRETE ISLANDS (KEYED IN)	610		
				M2		
0077	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	60		
				EA		
0078	2950000000-N	SP	CONVERT EXISTING JUNCTION BOX TO DROP INLET	1		
				EA		
0079	3030000000-M	862	STEEL BM GUARDRAIL	613.41		
				M		
0080	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		
				EA		
0081	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	6		
				EA		
0082	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8		
				EA		
0083	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6		
				EA		
0084	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	4		
				EA		
0085	3628000000-M	876	PLAIN RIP RAP, CLASS I	224.2		
				MTN		
0086	3649000000-M	876	PLAIN RIP RAP, CLASS B	240		
				MTN		
0087	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	4,670		
				M2		
0088	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2		
				EA		
0089	4025000000-M	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	107		
				M2		
0090	4025000000-M	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	7		
				M2		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	4072000000-M	903	SUPPORTS, 4.5KG STEEL U-CHANNEL	990 M		
0092	4102000000-N	904	SIGN ERECTION, TYPE E	153 EA		
0093	4108000000-N	904	SIGN ERECTION, TYPE F	13 EA		
0094	4129000000-N	906	RELOCATE SIGN, TYPE ***** (D)	15 EA		
0095	4129000000-N	906	RELOCATE SIGN, TYPE ***** (E)	2 EA		
0096	4129000000-N	906	RELOCATE SIGN, TYPE ***** (F)	2 EA		
0097	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	1 EA		
0098	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	41 EA		
0099	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	19 EA		
0100	4400000000-M	1110	WORK ZONE SIGNS (STATIONARY)	32 M2		
0101	4405000000-M	1110	WORK ZONE SIGNS (PORTABLE)	49 M2		
0102	4410000000-M	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	4 M2		
0103	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0104	4425000000-N	1125	WARNING FLAG SETS	2 EA		
0105	4430000000-N	1130	DRUMS	350 EA		
0106	4435000000-N	1135	CONES	375 EA		
0107	4445000000-M	1145	BARRICADES (TYPE III)	20 M		
0108	4455000000-N	1150	FLAGGER	180 MD		
0109	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	6 EA		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0110	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	10 EA		
0111	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	2 EA		
0112	4485000000-M	1170	PORTABLE CONCRETE BARRIER	400 M		
0113	4500000000-M	1170	RESET PORTABLE CONCRETE BARRIER	400 M		
0114	4615000000-M	1205	REMOVABLE TAPE PAVEMENT MARKING LINES (100MM)	600 M		
0115	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	930 EA		
0116	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	36,200 M		
0117	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	7,840 M		
0118	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	520 M		
0119	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	11 M		
0120	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	70 EA		
0121	4770000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES (100MM)	300 M		
0122	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	94,000 M		
0123	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,390 EA		
0124	5300000000-M	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	792 MTN		
0125	5306000000-M	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	792 MTN		
0126	5318000000-M	1505	PAVEMENT REPAIR FOR UTILITY WORK	187 MTN		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0127	5360000000-M	1510	150MM DI WATER PIPE, PC 2.41MPA	77 M		
0128	5444000000-M	1510	150MM PVC WATER PIPE, SDR 21, 1.38MPA WP	115 M		
0129	5450000000-M	1510	200MM PVC WATER PIPE, SDR 21, 1.38MPA WP	4,906 M		
0130	5480000000-M	1510	DUCTILE IRON WATER PIPE FIT- TINGS, 1.72MPA MIN WP	9,215 KG		
0131	5492000000-M	SP	20MM PE WATER TUBING, SDR 9, ****MPA WP (1.38MPA WP)	490 M		
0132	5510000000-M	1510	20MM CORPORATION STOP	25 EA		
0133	5540000000-M	1510	150MM GATE VALVE & VALVE BOX, 1.38MPA WP	8 EA		
0134	5546000000-M	1510	200MM GATE VALVE & VALVE BOX, ****MPA WP (1.38MPA WP)	6 EA		
0135	5582000000-M	1510	*** X ***MM TAPPING SADDLE (200MM X 20MM)	25 EA		
0136	5600000000-M	SP	***MM BLOW OFF ASSEMBLY (150MM)	1 EA		
0137	5648000000-N	1510	RELOCATE EXISTING WATER METER	23 EA		
0138	5660000000-N	SP	REMOVE EXISTING WATER METER	5 EA		
0139	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	12 EA		
0140	5882000000-N	SP	GENERIC UTILITY ITEM RECONNECT EXISTING WATER METER	8 EA		
0141	5888000000-M	SP	GENERIC UTILITY ITEM 250MM HDPE WATER PIPE BY DIRECTIONAL BORE	244 M		
0142	6000000000-M	1605	TEMPORARY SILT FENCE	4,315 M		
0143	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	1,380 MTN		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0144	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	4,365 MTN		
0145	6012000000-M	1610	SEDIMENT CONTROL STONE	3,545 MTN		
0146	6015000000-M	1615	TEMPORARY MULCHING	12.5 HA		
0147	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	600 KG		
0148	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	4.75 MTN		
0149	6024000000-M	1622	TEMPORARY SLOPE DRAINS	190 M		
0150	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	12 EA		
0151	6029000000-M	SP	SAFETY FENCE	1,277 M		
0152	6030000000-M	1630	SILT EXCAVATION	15,600 M3		
0153	6036000000-M	1631	MATTING FOR EROSION CONTROL	19,335 M2		
0154	6042000000-M	1632	6.4MM HARDWARE CLOTH	2,295 M		
0155	6045000000-M	SP	***MM TEMPORARY PIPE (600MM)	80 M		
0156	6045000000-M	SP	***MM TEMPORARY PIPE (900MM)	35 M		
0157	6069000000-M	1638	STILLING BASINS	158 M3		
0158	6070000000-N	SP	SPECIAL STILLING BASINS	1 EA		
0159	6084000000-M	1660	SEEDING & MULCHING	14 HA		
0160	6087000000-M	1660	MOWING	7 HA		
0161	6090000000-M	1661	SEED FOR REPAIR SEEDING	150 KG		
0162	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	0.5 MTN		
0163	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	400 KG		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0164	6108000000-M	1665	FERTILIZER TOPDRESSING	23.25 MTN		
0165	6109200000-M	SP	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (CENTI-PEDE)	0.1 HA		
0166	6111000000-M	SP	IMPERVIOUS DIKE	46 M		
0167	6114000000-N	SP	SPECIALIZED HAND MOWING	4 HR		
0168	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	32 EA		
0169	6123000000-M	1670	REFORESTATION	3 HA		
0170	7060000000-M	1705	SIGNAL CABLE	175 M		
0171	7108000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 1 SECTION)	6 EA		
0172	7312000000-N	1716	JUNCTION BOX (***** (TBJB)	1 EA		
0173	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	3 EA		
0174	7636000000-N	1745	SIGN FOR SIGNALS	1 EA		
0175	7912000000-N	SP	BEACON CONTROLLER ASSEMBLY & CABINET (***** (F1)	1 EA		
CULVERT ITEMS						
0176	8126000000-N	414	CULVERT EXCAVATION, STA ***** (146+61.950 -L- REV)	Lump Sum	L.S.	
0177	8126000000-N	414	CULVERT EXCAVATION, STA ***** (155+04.780 -L- REV)	Lump Sum	L.S.	
0178	8133000000-M	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	168 MTN		
0179	8196000000-M	420	CLASS A CONCRETE (CULVERT)	168.3 M3		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0180	8245000000-M	425	REINFORCING STEEL (CULVERT)	12,947 KG		
STRUCTURE ITEMS						
0181	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (178+79.500-L-REV LEFT LANE)	Lump Sum	L.S.	
0182	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (178+79.500-L-REV RIGHT LANE)	Lump Sum	L.S.	
0183	8112700000-N	SP	DYNAMIC LOAD TEST	1 EA		
0184	8119000000-M	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	3,820 M3		
0185	8147000000-M	420	REINFORCED CONCRETE DECK SLAB	1,720.8 M2		
0186	8161000000-M	420	GROOVING BRIDGE FLOORS	1,832.2 M2		
0187	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	144.9 M3		
0188	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (178+79.500-L-REV LEFT LANE)	Lump Sum	L.S.	
0189	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (178+79.500-L-REV RIGHT LANE)	Lump Sum	L.S.	
0190	8217000000-M	425	REINFORCING STEEL (BRIDGE)	12,912 KG		
0191	8262000000-M	430	1143MM PRESTRESSED CONCRETE GIRDERS	689.879 M		
0192	8364000000-M	450	HP310X79 STEEL PILES	598.5 M		
0193	8385000000-M	450	PP *** X ***** STEEL PILES (610 X 12.70)	377 M		
0194	8503000000-M	460	CONCRETE BARRIER RAIL	253.054 M		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0195	8608000000-M	876	PLAIN RIP RAP CLASS II (600MM THICK)	1,432 MTN		
0196	8622000000-M	876	FILTER FABRIC FOR DRAINAGE	1,462 M2		
0197	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0198	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0651/Dec14/Q588254.403/D787288560000/E198			Total Amount Of Bid For Entire Project :			

C201117(R-2562C)
BLADEN COUNTY

2/16/99

Contract No: C201117

County: Bladen

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General