METRIC
PROJECT REFERENCE NO. R-2562D
SHEET NO. UC-6
DESIGNED BY: MRB
DRAWN BY: MRB
CHECKED BY: RBW
APPROVED BY: RBW
REVISED:
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DESIGN SERVICES UNIT
PHONE:(919)250-4128
FAX:(919)250-4119
NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 10157 RONALD B. WILKINS
UTILITY CONSTRUCTION PLANS ONLY
SCALE 5 0 10
UTILITY CONSTRUCTION
NAD 83
MATCH TO SHEET UC-5
MATCH TO SHEET UC-7
-LREV- STA.24+80.000
-LREV- STA.28+20.000
PROP. - 6 - RELOCATE EXIST. WATER METERS 24M OF 20MM PE WATER TUBING, SDR 9, 1.38MPA WP CONNECT USING NECESSARY FITTINGS
PROP. - 1 - RELOCATE EXIST. FIRE HYDRANT 6M OF 150MM DI WATER PIPE, PC 2.41MPA CONNECT USING NECESSARY FITTINGS
PROP. - 20M OF 200MM PVC WATER PIPE, SDR 21, 1.38MPA WP 4 - 200MM - 45° DI BENDS CONNECT USING NECESSARY FITTINGS
PROP. - 1 - RELOCATE EXIST. FIRE HYDRANT 8M OF 150MM DI WATER PIPE, PC 2.41MPA 1 - 150MM - 45° DI BEND CONNECT USING NECESSARY FITTINGS
PROP. - 12M OF 150MM DI WATER PIPE, PC 2.41MPA 4 - 150MM - 45° DI BENDS CONNECT USING NECESSARY FITTINGS
PROP. - 1 - RELOCATE EXIST. FIRE HYDRANT 4M OF 150MM DI WATER PIPE, PC 2.41MPA 1 - 150MM GATE VALVE & VALVE BOX, 1.38MPA WP CONNECT USING NECESSARY FITTINGS
-Y2-
PI Sta 10+31.797
Δ = 35° 15' 42.0" (LT)
L = 30.772
T = 15.891
R = 50.000
SE = 0.04
-Y4- POT Sta.10+20.000 BEGIN CONSTRUCTION
-Y5- POT Sta.10+20.000 BEGIN CONSTRUCTION
-Y2- POT Sta.11+00.000 END CONSTRUCTION
-Y3- POT Sta.10+80.000 END CONSTRUCTION
-Y4A- POT Sta.10+50.000 END CONSTRUCTION
DO NOT DISTURB BUILDING
30-AUG-2004 08:09
R:\Utilities\Rdy_Ut\Proj\R-2562D09_UC6_ut_psh.dgn
mbright AT DS21242I