

PROJECT: R-2237B  
COUNTY: Caldwell

PROJECT SPECIAL PROVISIONS  
Utility

UTILITY CONFLICTS:

General:

The following utility companies have facilities that will be in conflict with the construction of this project:

- A. Blue Ridge Electric Membership Corporation
- B. BellSouth Telephone

The conflicting facilities will be adjusted prior to the date of availability except where noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owners. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

A. Blue Ridge Electric Membership Corporation

1. See "Utility By Others Plans" for utility conflicts.
2. All Power Poles outside of the cut/fill areas will be relocated by the Date of Availability.
3. All new Power Poles in the areas of the cut/fill will need the rough grading completed by the contractor before Blue Ridge Electric Membership Corporation (Blue Ridge EMC) can complete their work.
4. After rough grading is completed at each new Distribution Power Pole within the cut/fill areas, the Contractor will provide Blue Ridge EMC one week notice to install each new Distribution Pole and one day to complete the work from Sta. 72+00 to Sta. 142+00.
5. After rough grading is completed at each new Transmission Pole within the cut/fill areas, the Contractor will provide Blue Ridge EMC two weeks notice to install each new Transmission Pole and one week to complete the work from Sta. 142+00 to Sta. 350+00.
6. Existing Power Poles in conflict with the proposed road cannot be removed until there is continuity in Blue Ridge EMC's lines.

## B. BellSouth Telephone

1. See "Utility By Others Plans" for utility conflicts.
2. Section 1: All aerial telephone lines between Sta. 82+34 to Sta. 125+00 will be attached in joint use with Blue Ridge EMC poles. Placement cannot begin until Blue Ridge EMC completes Pole and Line placements in this section. Eleven weeks are required to complete line relocation work in this section.
3. Section 2a: All underground telephone lines between Sta. 125+00 to Sta. 182+00 will be attached in joint use with Blue Ridge EMC poles. Placement cannot begin until Blue Ridge EMC completes Pole and Line placements in this section. Fourteen weeks are required to complete line relocation work in this section.
4. Section 2b: Required work in this section includes Sta. 125+00 relocate one pole, Sta. 125+00 to Sta. 130+00 remove three poles and associated aerial lines, Sta. 143+00 to Sta. 146+00 replace two existing poles in place with taller poles. Three weeks are required to complete line relocation work in this section.
5. Section 3: All aerial telephone lines between Sta. 204+00 to Sta. 218+00 will be attached in joint use with Blue Ridge EMC poles. Placement cannot begin until Blue Ridge EMC completes Pole and Line placements in this section. Six weeks are required to complete line relocation work in this section.
6. Section 4: All aerial telephone lines between Sta. 218+00 to Sta. 312+00 will be attached in joint use with Blue Ridge EMC poles. Placement cannot begin until Blue Ridge EMC completes Pole and Line placements in this section. Placement of underground lines will be required in the Falcon Ridge development. Twenty-four weeks are required to complete line relocation work in this section.
7. Section 5: All aerial telephone lines between Sta. 344+00 to Sta. 356+50 will be attached to poles placed by BellSouth. Five weeks are required to complete line relocation work in this section.