

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
**SUMMARY OF QUANTITIES**

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201121														
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION										
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+75.00)	3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING	3649000000-E	876	2	TON	PLAIN RIP RAP, CLASS B	6108000000-E	1665	1.5	TON	FERTILIZER TOPDRESSING
0057000000-E	226	200	CY	UNDERCUT EXCAVATION	3656000000-E	876	427	SY	FILTER FABRIC FOR DRAINAGE	6114000000-N	SP	2.5	HR	SPECIALIZED HAND MOWING
0063000000-N	SP	Lump Sum		GRADING	4400000000-E	1110	158	SF	WORK ZONE SIGNS (STATIONARY)	6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
0106000000-E	230	6,100	CY	BORROW EXCAVATION	4410000000-E	1110	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)					
0134000000-E	240	49	CY	DRAINAGE DITCH EXCAVATION	4455000000-E	1145	112	LF	BARRICADES (TYPE III)					
0195000000-E	265	100	CY	SELECT GRANULAR MATERIAL	4810000000-E	1205	7,600	LF	PAINT PAVEMENT MARKING LINES (4")					
0196000000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION	6000000000-E	1605	560	LF	TEMPORARY SILT FENCE					
0318000000-E	300	5	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A					
0708000000-E	310	16	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	6009000000-E	1610	270	TON	STONE FOR EROSION CONTROL, CLASS B					
0806000000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6012000000-E	1610	285	TON	SEDIMENT CONTROL STONE					
1220000000-E	545	100	TON	INCIDENTAL STONE BASE	6015000000-E	1615	1.5	ACR	TEMPORARY MULCHING					
1489000000-E	610	360	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING					
1498000000-E	610	230	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEED- ING					
1525000000-E	SP	340	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	6024000000-E	1622	85	LF	TEMPORARY SLOPE DRAINS					
1560000000-E	620	49	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	6027000000-N	1622	3	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS					
2000000000-N	806	12	EA	RIGHT OF WAY MARKERS	6029000000-E	SP	300	LF	SAFETY FENCE					
2286000000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES	6030000000-E	1630	1,100	CY	SILT EXCAVATION					
2367000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.29	6036000000-E	1631	1,200	SY	MATTING FOR EROSION CONTROL					
2556000000-E	846	80	LF	SHOULDER BERM GUTTER	6038000000-E	SP	740	SY	PERMANENT SOIL REINFORCEMENT MAT					
3030000000-E	862	800	LF	STEEL BM GUARDRAIL	6042000000-E	1632	300	LF	1/4" HARDWARE CLOTH					
3150000000-N	862	10	EA	ADDITIONAL GUARDRAIL POSTS	6070000000-N	SP	6	EA	SPECIAL STILLING BASINS					
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	6084000000-E	1660	2	ACR	SEEDING & MULCHING					
					6087000000-E	1660	1	ACR	MOWING					
					6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING					
					6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING					