

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (27+49.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	300 TON		
0008	0106000000-E	230	BORROW EXCAVATION	19,700 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	360 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	53 TON		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	80 LF		
0014	0345000000-E	310	24" SIDE DRAIN PIPE	172 LF		
0015	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	132 LF		
0016	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	108 LF		
0017	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0018	0995000000-E	340	PIPE REMOVAL	133 LF		
0019	0996000000-N	350	PIPE CLEAN-OUT	1 EA		

County: Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1121000000-E	520	AGGREGATE BASE COURSE	55 TON		
0021	1220000000-E	545	INCIDENTAL STONE BASE	80 TON		
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	740 TON		
0023	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	510 TON		
0024	1514000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5A	980 TON		
0025	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	120 TON		
0026	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	5 TON		
0027	2000000000-N	806	RIGHT OF WAY MARKERS	21 EA		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0029	2355000000-N	840	FRAME WITH GRATE, STD 840.29	4 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	400 LF		
0031	3030000000-E	862	STEEL BM GUARDRAIL	700 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0033	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0035	3628000000-E	876	PLAIN RIP RAP, CLASS I	20 TON		
0036	3649000000-E	876	PLAIN RIP RAP, CLASS B	160 TON		
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	650 SY		
0038	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	559 SF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144	SF	
0040	4425000000-N	1125	WARNING FLAG SETS	4	EA	
0041	4430000000-N	1130	DRUMS	30	EA	
0042	4445000000-E	1145	BARRICADES (TYPE III)	192	LF	
0043	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,600	LF	
0044	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,632	LF	
0045	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	23	EA	
0046	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (IV)	90	TON	
0047	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	90	TON	
0048	5318000000-E	1505	PAVEMENT REPAIR FOR UTILITY WORK	25	TON	
0049	5360000000-E	1510	6" DI WATER PIPE, PC 350	115	LF	
0050	5366000000-E	1510	8" DI WATER PIPE, PC 350	1,677	LF	
0051	5378000000-E	1510	12" DI WATER PIPE, PC 350	55	LF	
0052	5414000000-E	1510	3/4" COPPER WATER PIPE, TYPE K	225	LF	
0053	5480000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	1,085	LB	
0054	5510000000-E	1510	3/4" CORPORATION STOP	4	EA	
0055	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	3	EA	
0056	5546000000-E	1510	8" GATE VALVE & VALVE BOX, *****WP (200#)	3	EA	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	5558000000-E	1510	12" GATE VALVE & VALVE BOX, *****WP (200#)	2	EA	
0058	5618000000-E	1510	6" TRANSITION COUPLING, ***** (AC TO DI)	2	EA	
0059	5648000000-N	1510	RELOCATE EXISTING WATER METER	4	EA	
0060	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	1	EA	
0061	5798000000-E	1530	FILL OR REMOVE ABANDONED *** PIPE, ***** (6", AC WATER)	256	LF	
0062	5798000000-E	1530	FILL OR REMOVE ABANDONED *** PIPE, ***** (8", AC WATER)	1,310	LF	
0063	5882000000-N	SP	GENERIC UTILITY ITEM 12" RESTRAINED RETAINER GLAND	4	EA	
0064	5882000000-N	SP	GENERIC UTILITY ITEM 6" RESTRAINED RETAINER GLAND	4	EA	
0065	5882000000-N	SP	GENERIC UTILITY ITEM 8" RESTRAINED RETAINER GLAND	8	EA	
0066	5888000000-E	SP	GENERIC UTILITY ITEM TRENCHLESS INSTALLATION OF 8" WATER PIPE IN SOIL	100	LF	
0067	5888000000-E	SP	GENERIC UTILITY ITEM TRENCHLESS INSTALLATION OF 8" WATER PIPE NOT IN SOIL	100	LF	
0068	6000000000-E	1605	TEMPORARY SILT FENCE	425	LF	
0069	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	175	TON	
0070	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	575	TON	
0071	6012000000-E	1610	SEDIMENT CONTROL STONE	192	TON	
0072	6015000000-E	1615	TEMPORARY MULCHING	3	ACR	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0074	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0075	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
0076	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0077	6030000000-E	1630	SILT EXCAVATION	1,535 CY		
0078	6033000000-E	1631	SYNTHETIC ROVING	700 SY		
0079	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,130 SY		
0080	6037000000-E	SP	COIR FIBER MAT	225 SY		
0081	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
0082	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
0083	6087000000-E	1660	MOWING	2 ACR		
0084	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0085	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0086	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0087	6108000000-E	1665	FERTILIZER TOPDRESSING	3 TON		
0088	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0089	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	12 EA		
0090	6126000000-E	SP	STREAMBANK REFORESTATION	0.07 ACR		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0091	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (27+49.00-L-)	Lump Sum	L.S.	
0092	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (27+49.00-L-)	Lump Sum	L.S.	
0093	8112700000-N	SP	DYNAMIC LOAD TEST	1 EA		
0094	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	500 CY		
0095	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	7,608 SF		
0096	8161000000-E	420	GROOVING BRIDGE FLOORS	6,169 SF		
0097	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	78.5 CY		
0098	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (27+49.00-L-)	Lump Sum	L.S.	
0099	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,087 LB		
0100	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	906.33 LF		
0101	8364000000-E	450	HP12X53 STEEL PILES	710 LF		
0102	8385000000-E	450	PP ** X **** STEEL PILES (30 X 0.625)	500 LF		
0103	8503000000-E	460	CONCRETE BARRIER RAIL	457.6 LF		
0104	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	501 TON		
0105	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	556 SY		
0106	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0107	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

C201360(B-4334)  
DAVIDSON COUNTY

2/16/99

Contract No: C201309

County: Davidson

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General