



PAVEMENT SCHEDULE	
C	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS PER SQ YD
C-1	PROP. APPROX. 1.62" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 180 LBS PER SQ YD
C-2	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS PER SQ YD
M	MILLING ASPHALT PAVEMENT, 1" DEPTH
M-1	MILLING ASPHALT PAVEMENT, 0" TO 1" DEPTH
M-2	MILLING ASPHALT PAVEMENT, 0" TO 1.5" DEPTH