

SUMMARY OF QUANTITIES

Work Order No.	County/Municipality	Map No.	Route No./Route Name	To/From Description	Typ Sect No	Length	Final Width	Incidental Stone Base	Mill Asph Pvm 1" Depth	Mill Asph Pvm 0" to 1"	Mill Asph Pvm 0" to 1.5"	ACSC Type S9.5B	ACSC Type S9.5C	PG 64-22 Plant Mix	PG 70-22 Plant Mix	Patching Existing Pavement	Adjust Manholes	Adjust Meter/Valve Boxes
						MI	FT	TONS	SY	SY	SY	TONS	TONS	TONS	TONS	TONS	EA	EA
9CR.10301.3	Davie	1	US 601	Rowan Co Line to Pvm Jt Near Rollingwood Dr	2	7.050	26	71					10,334		620	30		8
		2	US 64	WB Divided Lanes at I-40 Interchange	3	0.072	33	2					132		8			
		2	US 64	EB Divided Lanes at I-40 Interchange	3	0.072	32	2					192		12			
		2	US 64	End of Divided Lanes to SR 1357 (Fred Lanier Rd)	2	2.685	26	27					3,802		228	20		
Total For Map No. 2						2.829		31	0	0	0	0	4,126	0	248	20	0	0
		3	NC 801	SR 1617 (Bailey's Chapel Rd) to US 64	2	3.831	25	38	342	278			5,218		313	30		
		4	NC 801	SR 1814 (Riverview Rd) to US 601	2	5.841	25	58			278		7,986		479	30		2
		5	NC 801	US 601 to Coolee NCL	2	1.253	25	13					1,707		102	10		1
TOTAL FOR WORK ORDER NO. 9CR.10301.3						20.804		211	342	278	278	0	29,371	0	1,762	120	0	11
9CR.20301.3	Davie	6	SR 1616 Cornatzer Rd	SR 1611 (Fork Bixby Rd) to SR 1600 (Milling Rd)	1	2.025	24	20				2,648		159		20		
		6	SR 1606 Cornatzer Rd	SR 1600 (Milling Rd) to US 64	1	3.176	24	32	110	267		4,388		263		25		2
TOTAL FOR WORK ORDER NO. 9CR.20301.3						5.201		52	110	267	0	7,036	0	422	0	45	0	2
9CR.303012.3	Mocksville	7	SR 1147 Salisbury St.	Pvm Jt at School to Mocksville WCL	1	0.483	20	5				550		33		15	6	1
		8	US 601 Main St	Pvm Jt at E Maple St (NS) to Bridge #49 at Mocksville SCL	2	0.756	24	4			267		989		59		2	1
TOTAL FOR WORK ORDER NO. 9CR.303012.3						1.239		9	0	0	267	550	989	33	59	15	8	2
9CR.303025.3	Coolee	9	NC 801	Coolee NCL to Pvm Jt Before SR 1105 (Legion Cemetery Rd)	2	0.155	26	2					220		13	5		1
TOTAL FOR WORK ORDER NO. 9CR.303025.3						0.155		2	0	0	0	0	220	0	13	5	0	1
TOTAL FOR 2005 CONTRACT RESURFACING						27.399		274	452	545	545	7,586	30,580	455	1,834	185	8	16
39157	Davie	10	SR 1320 Bear Creek Ch Rd	Pvm Jt at SR 1002 (Liberty Ch Rd) to Iredell Co Line	4	3.169	22	16				4,107		246		50		
TOTAL FOR NCMA WORK ORDER NO. 39157						3.169		16	0	0	0	4,107	0	246	0	50	0	0
TOTAL FOR 2005 NCMA						3.169		16	0	0	0	4,107	0	246	0	50	0	0
GRAND TOTAL FOR 2005 DAVIE COUNTY RESURFACING						30.568		290	452	545	545	11,693	30,580	701	1,834	235	8	16