

PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM QUANTITY BREAKDOWN	TOTAL QUANTITY
<u>FINAL PAVEMENT MARKINGS</u>			
POLYUREA (6", 20MLS)			
V6	WHITE EDGELINE	52800 LF	
V7	YELLOW EDGELINE	52800 LF	
VJ	10 FT. WHITE SKIP	13200 LF	
VK	2 FT. WHITE MINISKIP	100 LF	
			TOTAL 118900 LF
POLYUREA (12", 20MLS)			
VY	WHITE GORELINE	1600 LF	
			TOTAL 1600 LF
POLYUREA PAVEMENT MARKING SYMBOL			
WC	STRAIGHT ARROW	6 EA	
			TOTAL 6 EA
<u>PERMANENT MARKERS</u>			
SNOWPLOWABLE RAISED PAVEMENT MARKERS			
MF	CRYSTAL & RED	820 EA	
			TOTAL 820 EA
<u>TEMPORARY PAVEMENT MARKINGS</u>			
REMOVABLE TAPE (6")			
R6	WHITE EDGELINE	20700 LF	
R7	YELLOW EDGELINE	20700 LF	
RK	10 FT. WHITE SKIP	1260 LF	
			TOTAL 42660 LF
PAINT (6")			
PA	WHITE EDGELINE	335545 LF	
PB	YELLOW EDGELINE	322675 LF	
PC	10 FT. WHITE SKIP	26260 LF	
PL	2 FT. WHITE MINISKIP	200 LF	
			TOTAL 684680 LF
PAINT (12")			
P1	WHITE GORELINE	9600 LF	
			TOTAL 9600 LF
PAINT PAVEMENT MARKING SYMBOL			
QC	STRAIGHT ARROW	12 EA	
			TOTAL 12 LF
<u>MARKERS</u>			
TEMPORARY RAISED PAVEMENT MARKERS			
MI	CRYSTAL & RED	1480 EA	
			TOTAL 1480 EA

03-SEP-2004 14:52
 H:\TDC\A\IC-PMSchedule.dwg
 rgermiller AT 10/2/2003

APPROVED: DATE: 09/04	<h2 style="margin: 0;">PAVEMENT MARKING SCHEDULE</h2>				
SCALE: NONE DATE: 09/04 DWG. BY: TAG DESIGN BY: TAG REVIEWED BY: JWG	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left;">REVISIONS</th> </tr> <tr> <td style="height: 20px;"> </td> </tr> <tr> <td style="height: 20px;"> </td> </tr> <tr> <td style="height: 20px;"> </td> </tr> </table>	REVISIONS			
REVISIONS					