

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201233

ItemNumber	Sec #	Quantity	Unit	Description
000010000-N	800	Lump Sum		MOBILIZATION
002200000-E	225	78,139	CY	UNCLASSIFIED EXCAVATION
003600000-E	225	5,081	CY	UNDERCUT EXCAVATION
010600000-E	230	54,906	CY	BORROW EXCAVATION
015600000-E	250	80,031	SY	REMOVAL OF EXISTING ASPHALT PAVEMENT
019600000-E	270	169,161	SY	FABRIC FOR SOIL STABILIZATION
101100000-N	500	Lump Sum		FINE GRADING
112100000-E	520	73,857	TON	AGGREGATE BASE COURSE
129700000-E	607	487	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")
149100000-E	610	11,064	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C
150300000-E	610	12,599	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C
150800000-E	610	43,377	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D
152300000-E	610	5,205	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
156000000-E	620	1,090	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
156500000-E	620	2,740	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
184000000-E	665	102,897	LF	MILLED RUMBLE STRIPS
188000000-E	SP	104	TON	GENERIC PAVING ITEM ABC FOR BACKFILL
188000000-E	SP	42,376	TON	GENERIC PAVING ITEM ASPHALT CONC SURFACE COURSE, TYPE S9.5D
189100000-E	SP	455	SY	GENERIC PAVING ITEM 8" CONTINUOUSLY REINFORCED CONCRETE PAVEMENT REPAIR
204300000-E	815	30,960	LF	4" PERFORATED SUBDRAIN PIPE
207600000-E	815	3,220	LF	4" OUTLET PIPE (SUBDRAINS)
209900000-E	816	30,960	LF	SHOULDER DRAIN
213200000-N	816	49	EA	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET

ItemNumber	Sec #	Quantity	Unit	Description
281500000-N	858	2	EA	ADJUSTMENT OF DROP INLETS
303000000-E	862	15,700	LF	STEEL BM GUARDRAIL
315000000-N	862	10	EA	ADDITIONAL GUARDRAIL POSTS
321000000-N	862	18	EA	GUARDRAIL ANCHOR UNITS, TYPE CAT-1
327000000-N	SP	18	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
334500000-E	864	2,534.4	LF	REMOVE & RESET EXISTING GUARDRAIL
336000000-E	863	16,919	LF	REMOVE EXISTING GUARDRAIL
342000000-E	SP	500	LF	GENERIC GUARDRAIL ITEM REMOVE & RESET CABLE GUIDERAIL
365600000-E	876	375	SY	FILTER FABRIC FOR DRAINAGE
404800000-E	902	5	CY	REINFORCED CONCRETE SIGN FOOTINGS
405400000-E	902	1	CY	PLAIN CONCRETE SIGN FOOTINGS
406000000-E	903	3,179	LB	SUPPORTS, BREAKAWAY STEEL BEAM
407200000-E	903	435	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
407800000-E	903	10	EA	SUPPORTS, 2-LB STEEL U-CHANNEL
410200000-N	904	20	EA	SIGN ERECTION, TYPE E
410800000-N	904	3	EA	SIGN ERECTION, TYPE F
411000000-N	904	12	EA	SIGN ERECTION, TYPE *** (GROUND MOUNTED) A
411000000-N	904	4	EA	SIGN ERECTION, TYPE *** (GROUND MOUNTED) B
411400000-N	904	10	EA	SIGN ERECTION, MILEMARKERS
412900000-N	906	2	EA	RELOCATE SIGN, TYPE ***** A (GROUND MOUNTED)
413800000-N	907	4	EA	DISPOSAL OF SUPPORT, STEEL BEAM
415200000-N	907	4	EA	DISPOSAL OF SIGN SYSTEM, STEEL BEAM
415500000-N	907	26	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL

ItemNumber	Sec #	Quantity	Unit	Description
423600000-N	907	7	EA	DISPOSAL OF SIGN, A OR B (GROUND MOUNTED)
440000000-E	1110	840	SF	WORK ZONE SIGNS (STATIONARY)
440500000-E	1110	902	SF	WORK ZONE SIGNS (PORTABLE)
441000000-E	1110	40	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
441500000-N	1115	4	EA	FLASHING ARROW PANELS, TYPE C
442000000-N	1120	2	EA	CHANGEABLE MESSAGE SIGNS
443000000-N	1130	400	EA	DRUMS
444500000-E	1145	48	LF	BARRICADES (TYPE III)
446000000-N	1155	4	EA	WARNING LIGHTS (TYPE B)
446500000-N	1160	4	EA	TEMPORARY CRASH CUSHIONS
447000000-N	1160	14	EA	RESET TEMPORARY CRASH CUSHIONS
448000000-N	1165	2	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)
448500000-E	1170	900	LF	PORTABLE CONCRETE BARRIER
450000000-E	1170	6,300	LF	RESET PORTABLE CONCRETE BARRIER
451000000-N	SP	312	HR	POLICE
462000000-E	1205	42,660	LF	REMOVABLE TAPE PAVEMENT MARKING LINES (6")
465000000-N	1251	1,480	EA	TEMPORARY RAISED PAVEMENT MARKERS
481500000-E	1205	684,680	LF	PAINT PAVEMENT MARKING LINES (6")
482500000-E	1205	9,600	LF	PAINT PAVEMENT MARKING LINES (12")
484500000-N	1205	12	EA	PAINT PAVEMENT MARKING SYMBOL
484710000-E	SP	118,900	LF	POLYUREA PAVEMENT MARKING LINES (6")
484712000-E	SP	1,600	LF	POLYUREA PAVEMENT MARKING LINES (12")
484722000-N	SP	6	EA	POLYUREA PAVEMENT MARKING SYMBOL
485000000-E	1205	81,330	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
485500000-E	1205	105,600	LF	REMOVAL OF PAVEMENT MARKING LINES (6")
486500000-E	1205	1,600	LF	REMOVAL OF PAVEMENT MARKING LINES (12")
490500000-N	1253	820	EA	SNOWPLOWABLE PAVEMENT MARKERS
600000000-E	1605	1,000	LF	TEMPORARY SILT FENCE
600600000-E	1610	200	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	500	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	200	TON	SEDIMENT CONTROL STONE
601500000-E	1615	21.5	ACR	TEMPORARY MULCHING
601800000-E	1620	750	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	3	TON	FERTILIZER FOR TEMPORARY SEEDING
603000000-E	1630	1,200	CY	SILT EXCAVATION
603600000-E	1631	2,000	SY	MATTING FOR EROSION CONTROL
604200000-E	1632	1,000	LF	1/4" HARDWARE CLOTH
608400000-E	1660	29.5	ACR	SEEDING & MULCHING
608700000-E	1660	12.5	ACR	MOWING
609000000-E	1661	250	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.5	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	500	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	22	TON	FERTILIZER TOPDRESSING
610900000-E	SP	1.6	ACR	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BLUEGRASS)
611400000-N	SP	34	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

5/28/99

14-SEP-2004 15:58
RD203026
JEJOHNSON