



8/17/99

PROJECT REFERENCE NO. 1-3600	SHEET NO. 2
RW SHEET NO.	
ROADWAY DESIGN ENGINEER SEAL 14493 11-16-04	PAVEMENT DESIGN ENGINEER SEAL 22886 11/16/04

PAVEMENT SCHEDULE			
C1	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE TYPE S9.5D, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.	E1	PROP. APPROX. 3" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
C2	PROP. APPROX. 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.	E2	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5½" IN DEPTH.
C3	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH, TO BE PLACED IN LAYERS NOT LESS THAN 1½" IN DEPTH OR GREATER THAN 2¼" IN DEPTH.	J	PROP. 8" AGGREGATE BASE COURSE.
D1	PROP. APPROX. 3" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0D, AT AN AVERAGE RATE OF 399 LBS. PER SQ. YD.	T	EARTH MATERIAL.
D2	PROP. APPROX. 3½" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YD.	U	EXISTING PAVEMENT.
D3	PROP. VAR. DEPTH ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH, TO BE PLACED IN LAYERS NOT LESS THAN 2¼" IN DEPTH OR GREATER THAN 4" IN DEPTH.	V	GEOTECHNICAL FABRIC (AS DIRECTED BY ENGINEER)

NOTE : PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.



### TYPICAL SECTION NO. 1

USE TYPICAL SECTION NO. 1  
-MP- 175.00 TO -MP- 179.80

- \* NOTE : DO NOT DISTURB EXISTING CABLE GUIDERAIL
- \*\* NOTE : MILLED RUMBLE STRIPS REQUIRED (STD. 665.01)

15-NOV-2004 09:42  
B:\000\106081-01-tyr.dgn  
MRHussey