

County: Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	78,139 CY		
0003	0036000000-E	225	UNDERCUT EXCAVATION	5,081 CY		
0004	0106000000-E	230	BORROW EXCAVATION	54,906 CY		
0005	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	80,031 SY		
0006	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	169,161 SY		
0007	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0008	1121000000-E	520	AGGREGATE BASE COURSE	73,857 TON		
0009	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	11,064 TON		
0010	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	12,599 TON		
0011	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	43,377 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	5,205 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,090 TON		
0014	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	2,740 TON		
0015	1840000000-E	665	MILLED RUMBLE STRIPS	102,897 LF		
0016	1880000000-E	SP	GENERIC PAVING ITEM ABC FOR BACKFILL	104 TON		
0017	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT CONC SURFACE COURSE, TYPE S9.5D	42,376 TON		
0018	1891000000-E	SP	GENERIC PAVING ITEM 8" CONTINUOUSLY REINFORCED CONCRETE PAVEMENT REPAIR	455 SY		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2043000000-E	815	4" PERFORATED SUBDRAIN PIPE	30,960 LF		
0020	2076000000-E	815	4" OUTLET PIPE (SUBDRAINS)	3,220 LF		
0021	2099000000-E	816	SHOULDER DRAIN	30,960 LF		
0022	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	49 EA		
0023	2815000000-N	858	ADJUSTMENT OF DROP INLETS	2 EA		
0024	3030000000-E	862	STEEL BM GUARDRAIL	15,700 LF		
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0026	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	18 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	18 EA		
0028	3345000000-E	864	REMOVE & RESET EXISTING GUARDRAIL	2,534.4 LF		
0029	3360000000-E	863	REMOVE EXISTING GUARDRAIL	16,919 LF		
0030	3420000000-E	SP	GENERIC GUARDRAIL ITEM REMOVE & RESET CABLE GUIDERAIL	500 LF		
0031	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	375 SY		
0032	4048000000-E	902	REINFORCED CONCRETE SIGN FOOTINGS	5 CY		
0033	4054000000-E	902	PLAIN CONCRETE SIGN FOOTINGS	1 CY		
0034	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	3,179 LB		
0035	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	435 LF		
0036	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	10 EA		
0037	4102000000-N	904	SIGN ERECTION, TYPE E	20 EA		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4108000000-N	904	SIGN ERECTION, TYPE F	3 EA		
0039	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	12 EA		
0040	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	4 EA		
0041	4114000000-N	904	SIGN ERECTION, MILEMARKERS	10 EA		
0042	4129000000-N	906	RELOCATE SIGN, TYPE ***** (A, GROUND MOUNTED)	2 EA		
0043	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	4 EA		
0044	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	4 EA		
0045	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	26 EA		
0046	4236000000-N	907	DISPOSAL OF SIGN, A OR B (GROUND MOUNTED)	7 EA		
0047	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	840 SF		
0048	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	902 SF		
0049	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	40 SF		
0050	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	4 EA		
0051	4420000000-N	1120	CHANGEABLE MESSAGE SIGNS	2 EA		
0052	4430000000-N	1130	DRUMS	400 EA		
0053	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0054	4460000000-N	1155	WARNING LIGHTS (TYPE B)	4 EA		
0055	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	14 EA		
0057	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	2 EA		
0058	4485000000-E	1170	PORTABLE CONCRETE BARRIER	900 LF		
0059	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	6,300 LF		
0060	4510000000-N	SP	POLICE	312 HR		
0061	4620000000-E	1205	REMOVABLE TAPE PAVEMENT MARKING LINES (6")	42,660 LF		
0062	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,480 EA		
0063	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	684,680 LF		
0064	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	9,600 LF		
0065	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	12 EA		
0066	4847100000-E	SP	POLYUREA PAVEMENT MARKING LINES (6")	118,900 LF		
0067	4847120000-E	SP	POLYUREA PAVEMENT MARKING LINES (12")	1,600 LF		
0068	4847220000-N	SP	POLYUREA PAVEMENT MARKING SYMBOL	6 EA		
0069	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	81,330 LF		
0070	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	105,600 LF		
0071	4865000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (12")	1,600 LF		
0072	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	820 EA		
0073	6000000000-E	1605	TEMPORARY SILT FENCE	1,000 LF		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	200 TON		
0075	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	500 TON		
0076	6012000000-E	1610	SEDIMENT CONTROL STONE	200 TON		
0077	6015000000-E	1615	TEMPORARY MULCHING	21.5 ACR		
0078	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	750 LB		
0079	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	3 TON		
0080	6030000000-E	1630	SILT EXCAVATION	1,200 CY		
0081	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000 SY		
0082	6042000000-E	1632	1/4" HARDWARE CLOTH	1,000 LF		
0083	6084000000-E	1660	SEEDING & MULCHING	29.5 ACR		
0084	6087000000-E	1660	MOWING	12.5 ACR		
0085	6090000000-E	1661	SEED FOR REPAIR SEEDING	250 LB		
0086	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0087	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	500 LB		
0088	6108000000-E	1665	FERTILIZER TOPDRESSING	22 TON		
0089	6109000000-E	SP	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BLUEGRASS)	1.6 ACR		
0090	6114000000-N	SP	SPECIALIZED HAND MOWING	34 HR		
0091	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		

C201233 (I-3600)  
DAVIE COUNTY

2/16/99

Contract No: C201233

County: Davie

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General