

PROJECT: U-3328
 COUNTY: EDGEcombe

PROJECT SPECIAL PROVISIONS
 Utility

UTILITY CONFLICTS:

General:

The following utility companies have facilities that will be in conflict with the construction of this project:

- A. CITY OF ROCKY MOUNT (POWER)
- B. SPRINT TELEPHONE COMPANY
- C. COX COMMUNICATION COMPANY
- D. CITY OF ROCKY MOUNT (GAS)
- E. CITY OF ROCKY MOUNT (WATER AND SEWER)

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. The utility owners will do all utility work listed herein. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

- A. CITY OF ROCKY MOUNT (POWER)
 These facilities will be relocated and finished by January 31, 2005.
 See Utility Conflict Plan for details.
- B. SPRINT TELEPHONE COMPANY
 These facilities will be relocated in joint use with power poles and finished by date of availability. See Utility Conflict Plan for details.
- C. COX COMMUNICATION COMPANY
 These facilities will be abandoned and relocated in joint use with power poles by date of availability
 See Utility Conflict Plan for details.
- D. CITY OF ROCKY MOUNT (GAS)
 Existing Facilities will remain in place and be adjusted as necessary.
 Need 2 weeks notice and 2 working days for finishing the job in any adjusted point.

- F. CITY OF ROCKY MOUNT (WATER AND SEWER)
Existing Facilities will relocate or remain in place and be adjusted as necessary. Need 2 weeks notice and 2 working days for finishing the job in any adjusted point.