

WORK ORDER NOS. 9CR.10341.3, 9CR.20341.3,
 9CR.303409.3, 9CR.303418.3, 9CR.303423.3,
 9CR.303426.3, 9CR.303428.3, 9CR.303499.3
 NCMA WORK ORDER NOS. 36913,
 37784, 37785, 37786, 37787, 37807

SUMMARY OF QUANTITIES

Work Order No	County/Municipality	Map No.	Route No/ Route Name	To/From Description	Typ Sect No	Length	Widening	Final Width	Inc Stone Base	Shldr Reconst	Mill Asph Pvm 1-1/2" Depth	Mill Asph Pvm 0" To 1-1/2" Depth	ACBC Type B25.0C	ACBC Type B25.0B	ACSC Type S9.5B	ACSC Type S9.5C	Level Course ACSC Type S9.5C	PG 64-22 Plant Mix	PG 70-22 Plant Mix	Patch Exist Pvm	Adjust DI	Adjust MH	Adjust MB / VB	
						MI	FT	FT	TONS	SMI	SY	SY	TONS	TONS	TONS	TONS	TONS	TONS	TONS	TONS	TONS	TONS	TONS	EA
36913	Forsyth	24	NC 109 SB Thomasville Rd	Intersection at Bridge #29 (I-40/US 311)	14	0.090		25				139				133			8	8				
		24	NC 109 NB Thomasville Rd	Intersection at Bridge #29 (I-40/US 311)	15	0.090		33				183				214			13	8		1		
		24	SR 3825 Parallel Ramp - WB-140	NC 109 (Thomasville Rd) to SR 2747 (Clemmonsville Rd)	6	0.260		24			3,661					340			20					
		24	SR 3826 Parallel Ramp - EB 1-40	SR 2747 (Clemmonsville Rd) to NC 109 (Thomasville Rd)	6	0.450		24			6,336					588			35					
		24	NC 109 Thomasville Rd	Bridge #29 to Charles St (NS)	13	0.066		48								172			10	8		3	5	
		24	NC 109 Thomasville Rd	Charles St (NS) to Culvert #C17	13	1.369		28	14							2,086			125	30		2	14	
		24	NC 109 Thomasville Rd	Culvert #C17 to Beg 2-Lane after SR 2643 (Union Cross Rd)	5	0.156		40	2							513	150		40					
		24	NC 109 Thomasville Rd	Beg 2-Lane after SR 2643(Union Cross Rd) to Davidson Co Line	13	1.821		28	18							2,776			167	30		1	6	
TOTAL FOR NCMA WORK ORDER NO. 36913						4.302			34	0.00	9,997	322	0	0	0	6,822	150	0	418	84	0	7	25	
37784	Forsyth	25	SR 1173 Williams Rd	SR 1176 (Double Spring Rd) to Pvm Jt after Lewisville CL	12	3.011		24	30						4,228			254		40				
TOTAL FOR NCMA WORK ORDER NO. 37784						3.011			30	0.00	0	0	0	0	4,228	0	0	254	0	40	0	0	0	
37785	Forsyth	26	SR 2211 Baux Mountain Rd	Stokes Co Line to SR 1917 (Red Bank Rd)	11	4.723		22	47						5,665			340		50				
TOTAL FOR NCMA WORK ORDER NO. 37785						4.723			47	0.00	0	0	0	0	5,665	0	0	340	0	50	0	0	0	
37786	Forsyth	27	SR 2632 Sedge Garden Rd	Pvm Jt at SR 2643 (Union Cross Rd) to EOP of SR 4315 (Kernersville Rd)	11	1.872		22	19						2,245			135			1	1	12	
		27	SR 2632 Sedge Garden Rd	EOP of SR 4315 (Kernersville Rd) to SR 2667 (Hasting Hill Rd)	11	1.317		22	13			244			1,580			99					3	
TOTAL FOR NCMA WORK ORDER NO. 37786						3.189			32	0.00	0	244	0	0	3,825	0	0	234	0	0	1	1	15	
37787	Forsyth	28	SR 2030 Linville Springs Rd	Pvm Jt at SR 1969 (Piney Grove Rd) to SR 2021 (Dobson St)	11	0.657		24	7						873			52				2	7	
TOTAL FOR NCMA WORK ORDER NO. 37787						0.657			7	0.00	0	0	0	0	873	0	0	52	0	0	0	0	2	7
37807	Stokes	29	SR 1949 Baux Mountain Rd	Radius at NC 65 to Forsyth Co Line	11	0.821		22	8						985			59						
TOTAL FOR NCMA WORK ORDER NO. 37807						0.821			8	0.00	0	0	0	0	985	0	0	59	0	0	0	0	0	0
TOTAL FOR 2005 NCMA						16.703			158	0.00	9,997	566	0	0	15,576	6,822	150	939	418	174	1	10	47	
GRAND TOTAL FOR FORSYTH COUNTY 2005 RESURFACING						58.101			576	12.11	10,492	3,763	415	4,953	50,454	26,085	150	3,299	1,589	709	3	43	147	