

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200813

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000010000-N	800	Lump Sum		MOBILIZATION	600000000-E	1605	275	LF	TEMPORARY SILT FENCE
004300000-N	226	Lump Sum		GRADING	600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	600900000-E	1610	125	TON	STONE FOR EROSION CONTROL, CLASS B
031800000-E	300	4	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	601200000-E	1610	50	TON	SEDIMENT CONTROL STONE
070800000-E	310	32	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	601500000-E	1615	1.5	ACR	TEMPORARY MULCHING
080600000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
122000000-E	545	150	TON	INCIDENTAL STONE BASE	602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
148900000-E	610	100	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	602400000-E	1622	30	LF	TEMPORARY SLOPE DRAINS
151400000-E	610	160	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5A	602700000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
156000000-E	620	15	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	603000000-E	1630	200	CY	SILT EXCAVATION
228600000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES	603300000-E	1631	225	SY	SYNTHETIC ROVING
236700000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29	603600000-E	1631	425	SY	MATTING FOR EROSION CONTROL
255600000-E	846	35	LF	SHOULDER BERM GUTTER	604200000-E	1632	50	LF	1/4" HARDWARE CLOTH
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	608400000-E	1660	1.5	ACR	SEEDING & MULCHING
342000000-E	SP	112.5	LF	GENERIC GUARDRAIL ITEM STEEL BM GUARDRAIL WEATHERING STEEL W/ WOOD POSTS	608700000-E	1660	1	ACR	MOWING
343500000-N	SP	4	EA	GENERIC GUARDRAIL ITEM GUARDRAIL ANCHOR UNITS, TYPE III, WEATHERING STEEL	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
343500000-N	SP	4	EA	GENERIC GUARDRAIL ITEM GUARDRAIL ANCHOR UNITS, TYPE350, WEATHERING STEEL	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
355900000-E	866	2,000	LF	** STRAND BARBED WIRE FENCE WITH POSTS (6)	609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
356300000-E	SP	800	LF	TEMP *** WOVEN WIRE FENCE, COMPLETE W/POSTS (47)	610800000-E	1665	1.25	TON	FERTILIZER TOPDRESSING
364900000-E	876	62	TON	PLAIN RIP RAP, CLASS B	611400000-N	SP	1	HR	SPECIALIZED HAND MOWING
365600000-E	876	850	SY	FILTER FABRIC FOR DRAINAGE	611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
440000000-E	1110	192	SF	WORK ZONE SIGNS (STATIONARY)	612300000-E	1670	0.5	ACR	REFORESTATION
441000000-E	1110	134	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL STATION ***** (15+52.00-L-)
444500000-E	1145	96	LF	BARRICADES (TYPE III)					