

County : New Hanover, Onslow, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001020000-N	SP	GENERIC MISCELLANEOUS ITEM ADJUST MONUMENTS	41 EA		
0003	0264000000-E	SP	GENERIC GRADING ITEM GRADING PER SHOULDER MILE	2.94 SMI		
0004	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	103 TON		
0005	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	8 LF		
0006	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	360 LF		
0007	0546000000-E	310	*** CAA PIPE CULVERTS, ***** THICK (15", 0.064")	540 LF		
0008	0546000000-E	310	*** CAA PIPE CULVERTS, ***** THICK (18", 0.064")	60 LF		
0009	0995000000-E	340	PIPE REMOVAL	206 LF		
0010	1220000000-E	545	INCIDENTAL STONE BASE	2,662 TON		
0011	1231000000-E	560	SHOULDER BORROW	13,769 CY		
0012	1245000000-E	SP	SHOULDER RECONSTRUCTION	116.5 SMI		
0013	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	76,955 SY		
0014	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	66,504 SY		
0015	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	71,104 SY		
0016	1330000000-E	607	INCIDENTAL MILLING	14,725 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	10,505 TON		

County : New Hanover, Onslow, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	26,209 TON		
0019	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	22,034 TON		
0020	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	92,526 TON		
0021	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	200 TON		
0022	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	54,030 TON		
0023	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	24,487 TON		
0024	1525100000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A (LEVELING COURSE)	295 TON		
0025	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	9,894 TON		
0026	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	3,242 TON		
0027	1770000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #6 STONE	22,650 SY		
0028	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXT PAVEMENT (FULL DEPTH)	2,243 TON		
0029	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXT PAVEMENT (MILL)	8,268 TON		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	15 EA		
0031	2354200000-N	840	FRAME WITH GRATE, STD 840.24	4 EA		
0032	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,235 LF		
0033	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	31 EA		
0034	2605000000-N	SP	WHEELCHAIR RAMPS	66 EA		

County : New Hanover, Onslow, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	2739000000-E	852	GENERIC PAVING ITEM INCIDENTAL CONCRETE	1,010 SY		
0036	2815000000-N	858	ADJUSTMENT OF DROP INLETS	14 EA		
0037	2830000000-N	858	ADJUSTMENT OF MANHOLES	79 EA		
0038	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	47 EA		
0039	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXT DROP INLET TO OPEN THROAT CATCH BASIN	30 EA		
0040	3030000000-E	862	STEEL BM GUARDRAIL	375 LF		
0041	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0042	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0043	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	15 EA		
0044	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	35 LF		
0045	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	635,400 LF		
0046	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	444,988 LF		
0047	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	290 LF		
0048	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,720 LF		
0049	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,170 LF		
0050	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	72 EA		
0051	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	612 EA		

County : New Hanover, Onslow, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	419,366	LF	
0053	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	590	LF	
0054	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	272	LF	
0055	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	928	LF	
0056	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	38	EA	
0057	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	320	EA	
0058	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	2,323	EA	
0059	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	7,340	EA	
0060	6000000000-E	1605	TEMPORARY SILT FENCE	1,000	LF	
0061	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100	TON	
0062	6012000000-E	1610	SEDIMENT CONTROL STONE	20	TON	
0063	6042000000-E	1632	1/4" HARDWARE CLOTH	600	LF	
0064	6084000000-E	1660	SEEDING & MULCHING	95.88	ACR	
0065	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	12,710	LF	

0826/Nov22/Q2056662.32/D185016420000/E65

Total Amount Of Bid For Entire Project :

**C201352**  
NEW HANOVER, ONSLOW, PENDER COUNTIES

2/16/99

Contract No: C201352

Counties: New Hanover, Onslow, Pender

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General