

30/58

EARTHWORK SUMMARIES

Volumes in Cubic Meters

PROJECT 34420 3.3
~~8-T190301~~

COUNTY Onslow

DATE 06/28/04

SHEET 2 OF 4 SHEETS

RD10501C

LINE	STATION	STATION	TOTAL EXCAV. (UNCL.)	ROCK EXCAV.	UNDERCUT	UNSUIT. EXCAV.	SUITABLE EXCAV.	TOTAL EMB.	ROCK EMB.	EARTH EMB.	EMBANK. +25%	BORROW	SUITABLE WASTE	UNSUIT. WASTE	TOTAL WASTE
-LMED- RT	99+00	100+80	18			14	4	738		738	923	919		14	14
-YB-	0+00	1+00	244			195	49	102		102	128	79		195	195
		SUBTOTAL	262			209	53	840		840	1,051	998		209	209
-LMED- RT	101+65	104+00	856		176	861	171	1,970		1,794	2,463	2,292		861	861
-DET1-	0+00	3+00.385						606		606	758	758			
		SUBTOTAL	856		176	861	171	2,576		2,400	3,221	3,050		861	861
NBTIE-	193+70	197+70.709						621		621	776	776			
		SUBTOTAL						621		621	776	776			
-LMED- RT	100+85	101+65	344			275	69	170		170	213	144		275	275
		SUBTOTAL	344			275	69	170		170	213	144		275	275
-LMED- LT	107+20	117+00	764			611	153	331		331	414	261		611	611
		SUBTOTAL	764			611	153	331		331	414	261		611	611
-LMED- LT	117+00	127+00	401			321	80	216		216	270	190		321	321
		SUBTOTAL	401			321	80	216		216	270	190		321	321
-LMED- LT	127+00	137+00	421			337	84	228		228	285	201		337	337
		SUBTOTAL	421			337	84	228		228	285	201		337	337
-LMED- LT	137+00	147+00	492			394	98	182		182	228	130		394	394
		SUBTOTAL	492			394	98	182		182	228	130		394	394
-LMED- LT	147+00	157+00	347			278	69	447		447	559	490		278	278
		SUBTOTAL	347			278	69	447		447	559	490		278	278
-LMED- LT	157+00	167+00	366			293	73	621		621	776	703		293	293
		SUBTOTAL	366			293	73	621		621	776	703		293	293
SHEET 2 TOTALS:			4,253		176	3,579	850	6,232		6,056	7,793	6,943		3,579	3,579