W:\GEOPAK\KD_EAR.log

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

PROJ. REFERENCE NO.	SHEET NO.
R-2514A	X-0e

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L_Med Rt.	Uncl. Exc. (cu. meters)	Embt (cu. meters)	UnderCut (cu. meters)	Station L_Med Rt.	Uncl. Exc. (cu. meters)	Embt (cu. meters)	UnderCut (cu. meters)	Station L_Med Rt.	Uncl. Exc. (cu. meters)	Embt (cu. meters)	UnderCut (cu. meters)
168+20.00	6	227	115	178+80.00	107	153	141	189+40.00	77	211	0
168+40.00	10	212	57	179+00.00	137	205	70	189+60.00	41	223	0
168+60.00	20	172	57	179+20.00	128	281	0	189+80.00	18	207	0
168+80.00	32	123	113	179+40.00	76	316	0	190+00.00	13	192	0
169+00.00	39	104	113	179+60.00	52	244	0	190+20.00	9	167	0
169+20.00	41	98	56	179+80.00	35	248	0	190+40.00	12	113	0
169+40.00	73	85	55	180+00.00	25	310	0	190+60.00	17	80	0
169+60.00	109	85	112	180+20.00	41	317	0	190+80.00	24	74	0
169+80.00	119	92	127	180+40.00	44	314	0	191+00.00	32	64	0
170+00.00	123	65	150	180+60.00	53	176	0	191+20.00	39	85	0
170+20.00	116	78	164	180+80.00	88	107	0	191+40.00	38	117	84
170+40.00	121	124	167	181+00.00	138	123	0	191+60.00	29	118	171
170+60.00	126	129	83	181+20.00	180	71	58	191+80.00	18	113	87
170+80.00	120	101	85	181+40.00	196	65	112	192+00.00	11	156	87
171+00.00	119	78	177	181+60.00	184	110	109	192+20.00	15	192	175
171+20.00	65	41	92	181+80.00	159	185	109	192+40.00	24	193	176
171+40.00	33	29	71	182+00.00	158	342	114	192+60.00	27	175	248
171+60.00	94	37	71	182+20.00	87	530	118	192+80.00	25	116	0
171+80.00	127	8	0	182+40.00	4	616	116	193+00.00	16	137	0
172+00.00	178	7	0	182+60.00	3	670	115	193+20.00	8	168	53
172+20.00	205	15	0	182+66.40	0	290	37	193+40.00	15	120	53
172+40.00	182	8	0	183+08.40	0	0	0	193+60.00	22	91	0
172+60.00	216	5	0	183+20.00	9	364	35	193+80.00	29	79	0
172+80.00	266	32	0	183+40.00	8	512	120	194+00.00	26	87	54
173+00.00	281	52	0	183+60.00	9	462	116	194+20.00	19	107	54
173+20.00	233	84	25	183+80.00	7	456	112	194+40.00	11	182	55
173+40.00	208	133	49	184+00.00	9	372	105	194+60.00	1	325	56
173+60.00	329	109	24	184+20.00	20	284	50	194+80.00	1	380	59
173+80.00	355	75	0	184+40.00	30	268	0	195+00.00	0	320	117
174+00.00	247	96	0	184+60.00	35	253	32	195+20.00	0	304	59
174+20.00	254	102	0	184+80.00	31	235	32	195+40.00	0	288	0
174+40.00	293	79	0	185+00.00	23	184	0	195+60.00	0	176	0
174+60.00	211	87	0	185+20.00	10	153	0	195+80.00	66	84	0
174+80.00	144	111	0	185+40.00	1	170	0	196+00.00	66	31	0
175+00.00	204	97	0	185+60.00	0	194	0				
175+20.00	251	77	26	185+80.00	0	228	0	Station	Uncl. Exc.	Embt	UnderCut
175+40.00	205	59	26	186+00.00	1	278	0				
175+60.00	151	37	0	186+20.00	2	327	0	YA_REV	(cu. meters)	(cu. meters)	(cu. meters)
175+80.00	157	37	0	186+40.00	7	387	0	0+40	11	26	0
176+00.00	155	59	0	186+60.00	52	420	0	0+60	20	39	0
176+20.00	148	68	54	186+80.00	111	429	0	0+80	44	40	0
176+40.00	138	111	110	187+00.00	172	435	0	1+00	96	56	0
176+60.00	111	162	57	187+20.00	240	374	0	1+20	71	61	0
176+80.00	66	193	50	187+40.00	248	325	0	1+30	4	10	0
177+00.00	37	146	51	187+60.00	237	324	0				
177+20.00	84	89	52	187+80.00	238	289	0				
177+40.00	103	177	106	188+00.00	224	249	0				
177+60.00	88	201	108	188+20.00	211	213	0				
177+80.00	142	127	109	188+40.00	178	182	0				
178+00.00	177	87	111	188+60.00	155	217	0				
178+20.00	159	79	106	188+80.00	134	218	0				
178+40.00	136	94	50	189+00.00	105	177	0				
178+60.00	106	121	70	189+20.00	98	179	0				

Station YB	Uncl. Exc. (cu. meters)	Embt (cu. meters)	UnderCut (cu. meters)
0+40	60	10	0
0+60	78	8	0
0+80	70	42	0
1+00	35	42	0

Station Y1	Uncl. Exc. (cu. meters)	Embt (cu. meters)	UnderCut (cu. meters)
0+40	15	108	0
0+60	23	83	0
0+80	17	65	0
0+90	0	13	0

Station Y2	Uncl. Exc. (cu. meters)	Embt (cu. meters)	UnderCut (cu. meters)
0+40	153	73	0
0+60	107	50	0
0+80	84	28	0
1+00	63	13	0
1+10	14	3	0

Station Y3	Uncl. Exc. (cu. meters)	Embt (cu. meters)	UnderCut (cu. meters)
0+40	63	72	0
0+60	44	42	0
0+80	50	25	0
0+90	17	6	0

Station Y4	Uncl. Exc. (cu. meters)	Embt (cu. meters)	UnderCut (cu. meters)
0+40	78	152	0
0+60	74	73	0
0+80	116	47	0
1+00	82	33	0
1+05	4	0	0