

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+47.5)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0255000000-E	SP	GENERIC GRADING ITEM DISPOSAL OF CONTAMINATED SOIL	40 TON		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	65 TON		
0009	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	44 LF		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	284 LF		
0011	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	160 LF		
0012	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	72 LF		
0013	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	44 LF		
0014	0995000000-E	340	PIPE REMOVAL	60 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	933 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	858 TON		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	955 TON		
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	138 TON		
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0021	2275000000-E	SP	FLOWABLE FILL	14 CY		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	17 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0024	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	5 EA		
0025	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4 EA		
0026	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	2 EA		
0027	2396000000-N	840	FRAME WITH COVER, STD 840.54	4 EA		
0028	2473000000-N	SP	GENERIC DRAINAGE ITEM FLAP GATE	2 EA		
0029	2535000000-E	846	***X*** CONCRETE CURB (9" X 12")	540 LF		
0030	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,630 LF		
0031	2591000000-E	848	4" CONCRETE SIDEWALK	645 SY		
0032	2598000000-E	848	CONCRETE WHEELCHAIR RAMPS	41 SY		
0033	2612000000-E	848	6" CONCRETE DRIVEWAY	286 SY		
0034	2830000000-N	858	ADJUSTMENT OF MANHOLES	10 EA		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	5 EA		
0036	3649000000-E	876	PLAIN RIP RAP, CLASS B	3 TON		
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	160 SY		
0038	3982000000-N	SP	GENERIC WALL ITEM PILE/PANEL RETAINING WALL	Lump Sum	L.S.	
0039	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	73 SF		
0040	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	52 SF		
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57 SF		
0042	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	1 EA		
0043	4420000000-N	1120	CHANGEABLE MESSAGE SIGNS	5 EA		
0044	4425000000-N	1125	WARNING FLAG SETS	2 EA		
0045	4430000000-N	1130	DRUMS	260 EA		
0046	4435000000-N	1135	CONES	260 EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0048	4455000000-N	1150	FLAGGER	200 MD		
0049	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	41 EA		
0050	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,984 LF		
0051	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	145 LF		
0052	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	44 LF		
0053	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	16 EA		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,966 LF		
0055	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	290 LF		
0056	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	88 LF		
0057	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	32 EA		
0058	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	41 EA		
0059	5300000000-E	1505	FOUNDATION CONDITIONING MATE- RIAL, UTILITIES CLASS ***** (VI)	68.1 TON		
0060	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	68.1 TON		
0061	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	1 EA		
0062	5564000000-E	SP	*** BUTTERFLY VALVE & VALVE BOX (16")	1 EA		
0063	5666000000-E	1510	FIRE HYDRANT, *****# WP (150 # WP)	1 EA		
0064	5775000000-E	1525	4' DIA PRECAST CONC SEWER MAN- HOLE 0-6' DEPTH	1 EA		
0065	5780000000-E	1525	PRECAST CONC MANHOLE WALL, ** DIA, OVER 6' HT (4' DIA, OVER 6' HT)	4 LF		
0066	5798000000-E	1530	FILL OR REMOVE ABANDONED *** PIPE, ***** (8", TC SEWER)	399 LF		
0067	5810000000-E	1530	FILL OR REMOVE ABANDONED 16" PIPE, ***** (DI WATER)	478 LF		
0068	5882000000-N	SP	GENERIC UTILITY ITEM 4' DIA PRECAST CONC SEWER MAN- HOLE, 0-6' DEPTH WITH WATERTIGHT RING & COVER	1 EA		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	5882000000-N	SP	GENERIC UTILITY ITEM INSTALL 4" WATER METER & VAULT	1 EA		
0070	5882000000-N	SP	GENERIC UTILITY ITEM REMOVE & STOCKPILE EXT FIRE HYDRANT	1 EA		
0071	5888000000-E	SP	GENERIC UTILITY ITEM 16" DI WATER PIPE, PC 350	493.3 LF		
0072	5888000000-E	SP	GENERIC UTILITY ITEM 6" DI WATER PIPE, PC 350	10 LF		
0073	5888000000-E	SP	GENERIC UTILITY ITEM 8" DI RESTRAINED JOINT SEWER PIPE, CLASS 50	279.4 LF		
0074	5888000000-E	SP	GENERIC UTILITY ITEM 8" DI SEWER PIPE, CLASS 50	154.25 LF		
0075	5888000000-E	SP	GENERIC UTILITY ITEM 8" DI WATER PIPE, PC 350	357.05 LF		
0076	5894000000-E	SP	GENERIC UTILITY ITEM CONCRETE FOR PIERS, CLASS A	4 CY		
0077	5906000000-E	SP	GENERIC UTILITY ITEM DUCTILE IRON WATER PIPE FIT- TINGS, 250# MIN WP	2,405 LB		
0078	5912000000-N	SP	GENERIC UTILITY ITEM INSTALL 6" GAS MAIN	Lump Sum	L.S.	
0079	6000000000-E	1605	TEMPORARY SILT FENCE	1,550 LF		
0080	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0081	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	75 TON		
0082	6012000000-E	1610	SEDIMENT CONTROL STONE	65 TON		
0083	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0084	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0085	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	6024000000-E	1622	TEMPORARY SLOPE DRAINS	35 LF		
0087	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0088	6029000000-E	SP	SAFETY FENCE	350 LF		
0089	6030000000-E	1630	SILT EXCAVATION	85 CY		
0090	6036000000-E	1631	MATTING FOR EROSION CONTROL	785 SY		
0091	6042000000-E	1632	1/4" HARDWARE CLOTH	220 LF		
0092	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0093	6087000000-E	1660	MOWING	1 ACR		
0094	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0095	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0096	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0097	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0098	6114000000-N	SP	SPECIALIZED HAND MOWING	1 HR		
0099	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0100	7060000000-E	1705	SIGNAL CABLE	475 LF		
0101	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	2 EA		
0102	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	4 EA		
0103	7264000000-E	1710	MESSENGER CABLE (3/8")	295 LF		
0104	7288000000-E	1715	TRENCHING (PAVED)	25 LF		
0105	7300000000-E	1715	TRENCHING (UNPAVED)	130 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	6 EA		
0107	7360000000-N	1720	WOOD POLE	2 EA		
0108	7372000000-N	1721	GUY ASSEMBLY	4 EA		
0109	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0110	7420000000-E	1722	2" RISER WITH WEATHERHEAD	2 EA		
0111	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,755 LF		
0112	7456000000-E	1726	LEAD-IN CABLE	1,180 LF		
0113	7636000000-N	1745	SIGN FOR SIGNALS	5 EA		
0114	7852000000-N	SP	DETECTOR CARD (NEMA TS-2)	1 EA		

STRUCTURE ITEMS

0115	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+47.50 -L-)	Lump Sum	L.S.	
0116	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+47.50 -L-)	Lump Sum	L.S.	
0117	8364000000-E	450	HP12X53 STEEL PILES	495 LF		
0118	8384000000-E	450	HP14X73 STEEL PILES	600 LF		
0119	8406000000-N	SP	GALVANIZING STEEL PILES AT STA ***** (17+47.50 -L-)	Lump Sum	L.S.	
0120	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	305 TON		
0121	8765000000-N	SP	CONSTRUCTION OF SUBSTRUCTURE	Lump Sum	L.S.	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	8766000000-N	SP	CONSTRUCTION OF SUPERSTRUCTURE	Lump Sum	L.S.	

1424/Nov12/Q31486.7/D573910500000/E122

Total Amount Of Bid For Entire Project :

C201075 (B-3685)
PITT COUNTY

2/16/99

Contract No: C201075

County: Pitt

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General