



PROJ. REFERENCE NO.	SHEET NO.
R-3303	PM-1

FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM/QUANTITY BREAKDOWN	TOTAL QUANTITY
<u>PAVEMENT MARKING LINES</u>			
	<u>THERMOPLASTIC (100mm, 2.3mm)</u>		
TA	WHITE EDGELINE	8823 m	TOTAL 8823 m
	<u>THERMOPLASTIC (100mm, 3.1mm)</u>		
TC	3M WHITE SKIP	16 m	
TD	0.5M WHITE MINISKIP	113 m	
TE	WHITE SOLID LANE LINE	583 m	
TI	YELLOW DOUBLE CENTER LINE	8898 m	TOTAL 9610 m
	<u>THERMOPLASTIC (100mm, 6.2mm)</u>		
T2	WHITE STOP BAR	110 m	TOTAL 110 m
	<u>THERMOPLASTIC SYMBOLS (2.3mm)</u>		
UA	LEFT TURN ARROW	17 EA	
UB	RIGHT TURN ARROW	4 EA	
UD	COMBO STARIGHT AND LEFT TURN ARROW	2 EA	TOTAL 23 EA
	<u>THERMOPLASTIC THICK CHARACTER (120mm, 3.1mm)</u>		
UI	ALPHANUMERIC CHARACTER	4 EA	TOTAL 4 EA
<u>SNOWPLOWABLE PAVEMENT MARKERS</u>			
ME	YELLOW AND YELLOW	112 EA	
MF	CRYSTAL AND RED	76 EA	TOTAL 188 EA

APPROVED:	DATE: 2/1/04	FINAL PAVEMENT MARKING SCHEDULE	
	SCALE: NONE	REVISIONS	
	DATE: 2004		
	DWG. BY: DER		
	DESIGN BY: DER		
REVIEWED BY: MJH			

29-JUN-2004 14:39
 I:\TCP\3303\pm_base.dgn
 derichardson AT TETC206432